

# **Sensor-Actuator Interfaces and Cables, Round Plugs and IP 67 Remote-I/O Systems**

## Catalogue 2013/2014


Signal and Power Transmission



**Weidmüller** 

# The World of Industrial Connectivity

As experienced experts we support our customers and partners around the world with products, solutions and services in the industrial environment of power, signal and data. Immerse yourself in our world of Industrial Connectivity.  
Let's connect.



# Dear Customers,



The PDF versions of our catalogues offer practical additional functions, helping you to find your way around our product range and simplifying the ordering process.

In addition to the catalogue, the PDF also contains:

- Internal page links
- Links to the online catalogue

Try it out for yourself. Click the order number to obtain more detailed information and close-up images via your web browser. The links in the PDF file also enable you to go directly to the next desired catalogue page.

Further Weidmüller product catalogues can be accessed by clicking the following:





# Sensor-Actuator Interfaces and Cables, Round Plugs and IP 67 Remote-I/O Systems

## Catalogue 8

### Sensor-Actuator Interfaces and Cables, Round Plugs and IP 67 Remote-I/O Systems

Sensor Actuator Interface

M8, M12 Sensor and actuator cables

M8, M12 Fieldbus, data cables and accessories

M8, M12 Plug in connectors and protective caps

7/8" connectors

IP 67 Remote I/O system SAI Active

SAI empty housing

JACKPAC® (IP 67)

Passive distributors

M23 Connectors and cables

Tools and markers

### Appendix

### Technical appendix

### Index

Search according to type or order number  
Addresses worldwide

## M8, M12 Sensor and actuator cables

**M12 one end without connector**

Page B.11



**M12 one end without connector,  
shielded**

Page B.17



**Twin cabling M12  
one end without connector**

Page B.18



**M5 one end without connector**

Page B.23



**Connecting cables M12 to M12**

Page B.25



**Connecting cables M12 to M12**

Page B.26



**Connecting cables M12 to M8**

Page B.29



**Connecting cables M8 to M8**

Page B.32



**Twin sensor cables**

Page B.37



**M12 one end without connector,  
B-coded**

Page B.43



**Valve cables one-sided**

Page B.50



**Valve M12**

Page B.56



# M8, M12 Fieldbus, data cables and accessories

<b>PROFIBUS-DP - cables</b> Page C.6	<b>PROFIBUS-DP - plug-in connector (M12, Sub-D)</b> Page C.10	<b>PROFIBUS-DP - FBCon T-distributor</b> Page C.22	<b>PROFIBUS-PA - cables</b> Page C.28
			
<b>PROFIBUS-PA - plug-in connector</b> Page C.31	<b>PROFIBUS-PA - FBCon T-distributor</b> Page C.34	<b>PROFIBUS-PA - FBCon T-distributor with surge protection</b> Page C.40	<b>PROFIBUS-PA - FBCon T-distributor ATEX Ex(ia)</b> Page C.50
			
<b>ASI - SAI distributor</b> Page C.59	<b>ASI - Cables</b> Page C.60	<b>ASI - T-piece</b> Page C.61	<b>CANopen &amp; DeviceNet™ - cables (M12, M8)</b> Page C.62
			
<b>CANopen &amp; DeviceNet™ - connectors</b> Page C.67	<b>EtherCAT</b> Page C.68	<b>Ethernet - cables</b> Page C.69	<b>Ethernet - plug-in connector</b> Page C.77
			
<b>FOUNDATION Fieldbus - connector (7/8")</b> Page C.80	<b>Accessories cable glands</b> Page C.81		
			

## M8, M12 Plug in connector and protective caps

Customisable connectors

M12

Page D.7



Customisable connectors

M8

Page D.20



Insulation displacement connection

M12

Page D.24



Insulation displacement connection

M8

Page D.26



Y-distributor

Page D.28



Twin plugs and wall bushings

Page D.30



Protective caps

Page D.31



Built in plugs

M12

Page D.33



Built in plugs

M8/M5

Page D.35



Valve plugs for custom assembly

Page D.40



Protective sleeve adapter

Page D.42



## 7/8" connector

7/8" connector

Page E.6



7/8" built-in plug

Page E.8



7/8" one end without connector

Page E.11



# IP 67 Remote I/O system SAI Active

SAI-AU for PROFIBUS-DP

Page F.8



SAI-AU for CANopen

Page F.12



SAI-AU for DeviceNet™

Page F.16



SAI-AU Pro Gateway for PROFIBUS-DP

Page F.22



SAI-AU Pro Gateway for DeviceNet™

Page F.24



SAI-AU Pro Gateway for Modbus ASCII

Page F.26



SAI-AU Pro subbus modules with digital inputs/outputs

Page F.28



SAI-AU Pro subbus modules with analogue input/outputs

Page F.29



SAI-AU Pro subbus modules "counter"

Page F.30



SAI-AU Pro subbus modules "thermo"

Page F.31



SAI-AU Pro subbus module "PT100"

Page F.32



SAI-AU Wireless for PROFIBUS-DP

Page F.36



## SAI empty housing

**SAI empty housing**

Page G.8



## JACKPAC® (IP 67)

**JACKPAC®**

Page H.3



**JACKPAC® test**

Page H.6



**Empty housing SAI JACKPAC®**





Page H.8



# Passive distributors

<b>M12</b> 	<b>M12 Line</b> 	<b>M12 DIP with DIP-switch</b> 	<b>M12 ECO</b> 
<b>M12 Push-Pull</b> 	<b>M12 CNOMO</b> 	<b>M12 bayonet joint</b> 	<b>M12 IDC</b> 
<b>M12 VA stainless steel</b> 	<b>M12 metal distributors</b> 	<b>M12 distributors 1:1</b> 	<b>M12 distributors, 8-pole</b> 
<b>M12 for NPN and PNP sensors</b> 	<b>M12 wall bushing</b> 	<b>M12 Pre-assembled hood version</b> 	<b>M8</b> 
<b>M8 Line</b> 	<b>M8 distributor with solder pins</b> 	<b>M5 Line</b> 	<b>M12 Ex Zone 1 and Zone 22</b> 

## M23 Connectors and cables

<b>Housings for signal transmission</b> Page J.12	<b>Built-in connectors for signal transmission</b> Page J.13	<b>Inserts for signal transmission</b> Page J.14	<b>Contacts for signal transmission</b> Page J.16
			
<b>Housings for power transmission</b> Page J.26	<b>Built-in connectors for power transmission</b> Page J.27	<b>Inserts for power transmission</b> Page J.28	<b>Contacts for power transmission</b> Page J.29
			
<b>Moulded M23 cables</b> Page J.30	<b>SAI distributor with M23</b> Page J.31		
			

## Tools and markers

<b>Screwy® for M8/M12/M23</b> Page K.5	<b>Cutting tools</b> Page K.7	<b>Sheathing and insulation stripping tools</b> Page K.8	<b>M23 crimping tools</b> Page K.12
			
<b>Identification systems</b> Page K.14			
			

# Sensor Actuator Interface

---

**Sensor Actuator Interface**

Introduction

A.2

**A**

# SAI M12 Line

## A The thin SAI M12 distributor with a single row linear design can be used in a variety of ways.

Machines are becoming more complex as they integrate new functionality and collect increasing amounts of information. But at the same time, there is less space available for these increasing requirements.

The SAI M12 line of distributors has been designed by Weidmüller to meet the requirements posed by this trend. Our existing SAI M8 line of distributors has been designed to save space while still maintaining their versatility. These features are also found in the new SAI M12 distributor line.

The distributors are versatile because every plug in location can be labelled. Thus they can be mounted from the side or from the top down. They are easy to handle and simple to mount to machine profiles because of their single row design.

The M12 distributors are available as 4-way and 6-way modules, with M12 combi-plugs, or as a fixed cable version.

### Versatile marking options

All plug in positions of the distributor can be labelled with markers so that all connection points are easily identified.



### Thin design

The M12 distributor has a single row linear design which allows it to be handled easily.



**The corresponding number of connections**

The M12 distributors are available as 4-way and 6-way modules.

**Multiple variants**

Depending on your application or preference, the M12 distributors can be used either with a fixed, attached cable or with a combi-plug.



# 7/8" connectors

A

## Rugged connector solution for supplying power

Weidmüller offers appropriate 7/8" connectors for a variety of different uses. They are available as customisable variants, built-in connectors with front-wall or rear-wall mounting, and as moulded (encapsulated) cables. The contact carriers are designed with 3, 4 or 5 poles. The contacts are gold plated to ensure a long lifespan.

The customisable variants of these products have compact dimensions, yet can still be fitted with a screw wire connection. The 3-pole version is rated for 12 A while the 4- and 5-pole versions are rated for 9 A. One pin is always designated as the PE contact.

The rated voltage is always at least 250 V. These features make the connector perfect for supplying power to devices.

### High dielectric strength

A high dielectric strength of at least 250 V is ensured by the wide contact gap. This allows the product to be used as a power supply.



### Excellent transmission reliability

The gold-plated contacts and the low insertion force both help to ensure excellent transmission reliability.




### Rugged design

Extra rugged, moulded cables are available for series production.



**Pluggable and safe device connectivity**  
 Receptacle connectors for front-wall and rear-wall mounting provide you with pluggable device connectivity and IP 67 protection.



**D-coded connectors made from stainless steel**

The D-coded connectors are made from 1.4404/316L stainless steel and feature a tension-clamp connection. They can be customised and are available with IP 69K protection.



**M8 patch cords for EtherCAT applications**

The industrial Ethernet cabling systems with M8 connectors are preferred for use with EtherCAT applications.



**M23 solder inserts**

The M23 solder versions are used for stand-alone soldering or for attaching to circuit boards.



**Easy to assemble**

For easy assembly, the customisable versions can be fitted with the widely used screw wire connection.



# High-quality M8 valve lines

## Now with all five valve plug versions

The miniaturisation trend in device design continues unabated. Sub-bus modules are being used increasingly, particularly with IP 67 I/O devices. These should take up as little space as possible when installed in the field. Users are relying more and more on space-saving M8 connectors to minimise the space taken up by the plug connection.

In support of this trend, we are offering the appropriate actuator cables in a variety of application-specific versions. Our product line includes cables with all five valve-connector types: types A, B industry, B DIN, C Industry and C DIN. The specifications for these products reveal a successful balance of space-saving size combined with quality and load resistance.

### Flexible lengths

The cables are available in different versions with a minimum length of only 15 cm.



### Compact yet durable

The encapsulated moulding of the M8 connector ensures that the connectors are not just compact, but also high-quality and durable.



**Round plugs for the circuit board**

We offer many versions of our round plugs for the circuit board – including straight/angled, male/female, M8/M12, and with A/B/D coding.

**M16 connectors**

We offer a wide line of M16 connectors for circuit boards and moulded connectors for field cabling.

**Shielded built-in round plugs**

Circular plugs with lead-out shields for wall installations result in significantly less interference in the device.



# SAI empty housing in IP 67

## Modular sensor actuator interface, empty housing

**A**

The sensor actuator interface (SAI) line of empty housings with IP 67 protection has been designed by Weidmüller without encapsulation so that they are easy to install. Thus the SAI empty housings are well suited for customer specific layouts which they can implement themselves.

The reflow compatible M12 PCB connectors can withstand continuous operating temperatures of up to 105 °C. They can be ordered separately for customer specific housing solutions.

The housing series includes three sizes: a 54 mm wide version and two 30 mm wide versions in a short or a long execution.

The housings are easy to install and production is simplified by the reflow-compatible M12 PCB connectors. They can be installed on the PCB directly from the tray.

### On site diagnostics

Illuminated arrow icons show the user the status of each.




### Designer option for laser labelling

Symbols, data, diagrams or text can be printed in detail on the housing parts using a laser labelling process.



**Easy to service during installation**

Installation with snap on lugs enables simple and quick trouble shooting during application; this is only possible without encapsulation.

**High protection class**

Designed for harsh outside environments with IP 67 protection.

# IP 67

**Power reserve for safety**

Due to the use of Pocan® insulating plastic, the SAI empty housings are especially sturdy and resistant.

**Wide variety of variants**

The M12 PCB connectors are available as A-coded, B-coded and also D-coded versions.

**100 % reflow-compatible**

The PCB connectors fulfil the high demands on the reflow process and are suitable for all other soldering processes.



## Are you already a Weidmüller customer?


**Then why not order your M12 or M8 cables from us!**

Weidmüller supplies an extremely wide range of M12 and M8 cables, naturally with our proven Weidmüller quality assurance.

To answer as many demands as possible, we offer:

- PVC cables
- PUR/halogen-free cables

Of course, with very short delivery times and best conditions.  
Please do not hesitate to contact us for a quote or to receive further information.



# M8, M12 Sensor and actuator cables

<b>M8, M12 Sensor and actuator cables</b>	
Introduction	B.2
Overview of sensor cables	B.4
Sensor cables	B.10
Power cables	B.42
Valve cables	B.46
Connecting cable for sensors and actuators	B.56
Connecting cables for Weidmüller distributors	B.57

## SAI cable

Weidmüller manufactures its own SAI cable. This ensures optimal versatility. We do not use fully automatic machines which are difficult to adapt. That is why Weidmüller is well known for delivering promptly with quick turnaround times, despite our wide variety of available options. We can also develop and produce solutions for specific customer requirements. We regularly produce cables, for example, with customer specific labels and logos.

We realise that the cost of having this increased flexibility can be the decisive factor. In order to meet your cost requirements, an additional production line has been specifically designed to keep costs down. This line produces top-selling products for exceptional efficiency and cost savings.



Sensor cables from Weidmüller: shown here with yellow and black cables, together with bus cables



### Easy to identify

The EAN number on each label can be scanned in.



### Resistant to vibration

M8 with vibration resistance




### High quality

Compatible for use in robots;  
with recyclable, halogen-free cables



### Versatile

Customised cables









## Overview of sensor cables

		One end free		M8 socket straight	
No. of poles					
<b>B</b>	One end free				
	M8 plug	1.5 m	PUR halogen-free	1824590150	1927240150
		3.0 m	PVC	1824590300	1927240300
		5.0 m		1824590500	1927240500
		10.0 m		1824591000	1927241000
		variable		1824590000	1927240000
	90°	1.5 m	PUR halogen-free	1824570150	1927150150
		3.0 m	PVC	1824570300	1927150300
		5.0 m		1824570500	1927150500
		10.0 m		1824571000	1927151000
		variable		1824570000	1927150000
<b>M12 plug</b>	straight	1.5 m	PUR halogen-free	1857550150	1927310150
		3.0 m	PVC	1857550300	1927310300
		5.0 m		1857550500	1927310500
		10.0 m		1857551000	1927311000
		variable		1857550000	1927310000
	90°	1.5 m	PUR halogen-free	1857560150	1927330150
		3.0 m	PVC	1857560300	1927330300
		5.0 m		1857560500	1927330500
		10.0 m		1857561000	1927331000
		variable		1857560000	1927330000
<b>M12 socket</b>	straight	1.5 m	PUR halogen-free	9457810150	1925430150
		3.0 m	PVC	9457810300	1925430300
		5.0 m		9457810500	1925430500
		10.0 m		9457811000	1925431000
		variable		9457810000	1925430000
	90°	1.5 m	PUR halogen-free	9456100150	1925440150
		3.0 m	PVC	9456100300	1925440300
		5.0 m		9456100500	1925440500
		10.0 m		9456101000	1925441000
		variable		9456100000	1925440000
<b>One end free</b>	straight	1.5 m	PUR halogen-free	9456770150	1938170150
		3.0 m	PVC	9456770300	1938170300
		5.0 m		9456770500	1938170500
		10.0 m		9456771000	1938171000
		variable		9456770000	1938170000
	90°	1.5 m	PUR halogen-free	***	***
		3.0 m	PVC	***	***
		5.0 m		***	***
		10.0 m		***	***
		variable		***	***

Preferred types / extracted from the complete line. Please make a separate enquiry for information about the M8 snap-on version, twin cabling and others.

M8 socket					
straight		90°		90° angle with 2 LEDs	
PUR halogen-free		PVC		PUR halogen-free	
9457850150	1927260150	9457380150	1927320150	9456150150	1927340150
9457850300	1927260300	9457380300	1927320300	9456150300	1927340300
9457850500	1927260500	9457380500	1927320500	9456150500	1927340500
9457851000	1927261000	9457381000	1927321000	9456151000	1927341000
		9457380000	1927320000	9456150000	1927340000
***		1824580150 1824580300 1824580500 1824581000 1824580000		1824580150 1824580300 1824580500 1824581000 1824580000	
1880470150 1880470300 1880470500 1880471000 1880470000		***		1857660150 1857660300 1857660500 1857661000 1857660000	
***		1857670150 1857670300 1857670500 1857671000 1857670000		1857680150 1857680300 1857680500 1857681000 1857680000	
On request		***		On request	
***		1906330150 1906330300 1906330500 1906331000 1906330000		1906340150 1906340300 1906340500 1906341000 1906340000	
***		1906330150 1906330300 1906330500 1906331000 1906330000		1906340150 1906340300 1906340500 1906341000 1906340000	
On request		***		***	
***		9457980150 9457980300 9457980500 9457981000 9457980000		9456670150 9456670300 9456670500 9456671000 9456670000	
9456660150 9456660300 9456660500 9456661000 9456660000		***		9456670150 9456670300 9456670500 9456671000 9456670000	
***		1906330150 1906330300 1906330500 1906331000 1906330000		1906340150 1906340300 1906340500 1906341000 1906340000	
On request		***		***	
***		1906330150 1906330300 1906330500 1906331000 1906330000		1906340150 1906340300 1906340500 1906341000 1906340000	

## Overview of sensor cables

		No. of poles
B	One end free	
		
M8 plug	straight	 
		 
M12 plug	90°	 
		 

M12 socket	
straight	
PUR halogen-free	PVC
	
1.5 m 3.0 m 5.0 m 10.0 m variable	19457820150 19457820300 19457820500 19457821000 19457820000
1.5 m 3.0 m 5.0 m 10.0 m variable	19457730150 19457730300 19457730500 19457731000 19457730000
1.5 m 3.0 m 5.0 m 10.0 m variable	1937950150 1937950300 1937950500 1937951000 1937950000
1.5 m 3.0 m 5.0 m 10.0 m variable	1937980150 1937980300 1937980500 1937981000 1937980000
1.5 m 3.0 m 5.0 m 10.0 m variable	On request On request
1.5 m 3.0 m 5.0 m 10.0 m variable	*** ***
1.5 m 3.0 m 5.0 m 10.0 m variable	9457230150 9457230300 9457230500 9457231000 9457230000
1.5 m 3.0 m 5.0 m 10.0 m variable	1906300150 1906300300 1906300500 1906301000 1906300000
1.5 m 3.0 m 5.0 m 10.0 m variable	1821050150 1821050300 1821050500 1821051000 1821050000
1.5 m 3.0 m 5.0 m 10.0 m variable	On request *** ***
1.5 m 3.0 m 5.0 m 10.0 m variable	*** *** ***
1.5 m 3.0 m 5.0 m 10.0 m variable	On request On request
1.5 m 3.0 m 5.0 m 10.0 m variable	*** *** ***

## M12 socket

straight



1(+) 2(0)  
4(S) 3(-)

PUR  
halogen-free

PVC

9457910150	1925590150
9457910300	1925590300
9457910500	1925590500
9457911000	1925591000
9457910000	1925590000

1(+) 2(0)  
4(S) 3(-)

PUR  
halogen-free

PVC

9457320150	1925630150
9457320300	1925630300
9457320500	1925630500
9457321000	1925631000
9457320000	1925630000

90°



1(+) 2(0)  
4(S) 3(-)

PUR  
halogen-free

PVC

9457740150	1925640150
9457740300	1925640300
9457740500	1925640500
9457741000	1925641000
9457740000	1925640000

1(+) 2(0)  
4(S) 3(-)

PUR  
halogen-free

PVC

9457690150	1925650150
9457690300	1925650300
9457690500	1925650500
9457691000	1925651000
9457690000	1925650000

\*\*\* \*\*\*

1937960150	1938240150
1937960300	1938240300
1937960500	1938240500
1937961000	1938241000
1937960000	1938240000

\*\*\* \*\*\*

\*\*\* \*\*\*

1937990150	1938270150
1937990300	1938270300
1937990500	1938270500
1937991000	1938271000
1937990000	1938270000

\*\*\* \*\*\*

\*\*\* \*\*\*

1937970150	1938250150
1937970300	1938250300
1937970500	1938250500
1937971000	1938251000
1937970000	1938250000

\*\*\* \*\*\*

\*\*\* \*\*\*

1938000150	1938280150
1938000300	1938280300
1938000500	1938280500
1938001000	1938281000
1938000000	1938280000

\*\*\* \*\*\*

\*\*\* \*\*\*

9457390150	1925340150
9457390300	1925340300
9457390500	1925340500
9457391000	1925341000
9457390000	1925340000

9457340150	1925320150
9457340300	1925320300
9457340500	1925320500
9457341000	1925321000
9457340000	1925320000

\*\*\* \*\*\*

1815670150	1925380150
1815670300	1925380300
1815670500	1925380500
1815671000	1925381000
1815670000	1925380000

\*\*\* \*\*\*

\*\*\* \*\*\*

9457310150	1925350150
9457310300	1925350300
9457310500	1925350500
9457311000	1925351000
9457310000	1925350000

\*\*\* \*\*\*

9457270150	1925360150
9457270300	1925360300
9457270500	1925360500
9457271000	1925361000
9457270000	1925360000

\*\*\* \*\*\*

1906310150	1925390150
1906310300	1925390300
1906310500	1925390500
1906311000	1925391000
1906310000	1925390000

\*\*\* \*\*\*

\*\*\* \*\*\*

9457900150	1925400150
9457900300	1925400300
9457900500	1925400500
9457901000	1925401000
9457900000	1925400000

\*\*\* \*\*\*

9456500150	
9456500300	
9456500500	On request
9456501000	
9456500000	

## Overview of sensor cables

		No. of poles
B	One end free	
	M8 plug	 
M12 plug	straight	 
	90°	 

		M12 socket	
		90° angle with 2 LEDs	
Cable material	PUR halogen-free	PVC	PUR halogen-free
1.5 m	9457800150	1925460150	9456380150
3.0 m	9457800300	1925460300	9456380300
5.0 m	9457800500	1925460500	9456380500
10.0 m	9457801000	1925461000	9456381000
variable	9457800000	1925460000	9456380000
1.5 m	***	***	***
3.0 m	***	***	***
5.0 m	***	***	***
10.0 m	***	***	***
variable	***	***	***
1.5 m	9457790150	1925410150	1906410150
3.0 m	9457790300	1925410300	1906410300
5.0 m	9457790500	1925410500	1906410500
10.0 m	9457791000	1925411000	1906411000
variable	9457790000	1925410000	1906410000
1.5 m	***	***	***
3.0 m	***	***	***
5.0 m	***	***	***
10.0 m	***	***	***
variable	***	***	***
1.5 m	On request	On request	On request
3.0 m	***	***	***
5.0 m	***	***	***
10.0 m	***	***	***
variable	***	***	***
1.5 m	***	***	***
3.0 m	***	***	***
5.0 m	***	***	***
10.0 m	***	***	***
variable	***	***	***



## Sensor cables with plug at one end only

M12



M8



M8 Snap connection



Twin cabling



M5



### Sensor/actuator cable pre-assembled with M8/M12 plug-in connector at one end

Machine designers frequently require individual cable lengths. Sensor cables, with a connector fitted at one end only, can be easily adapted to the corresponding situation. The cables are available in many different versions: straight, 90° and with all common pole numbers (3.4 and 5). Male plugs and Female sockets can be assembled to suit individual customer requirements for connecting cables. The cable sheathing is of PUR (polyurethane) and is suitable for use with cable carrier systems. Plugs and cables are in neutral black.


### Sensor cables

Weidmüller can supply various cable lengths as indicated in the following table:


### Typical cable lengths are:

- 1.5 m
- 3.0 m
- 5.0 m
- 10.0 m

### Example of designation



**M12 one end without connector  
A-coded**



#### Ordering data

<b>Male, straight</b>	
PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m
Resistant to welding beads	1.5 m
<b>Male, angled</b>	
PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m
Resistant to welding beads	1.5 m
<b>Female, straight</b>	
PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m
Resistant to welding beads	1.5 m
<b>Female, angled</b>	
PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m
Resistant to welding beads	1.5 m
<b>Note</b>	
Other versions on request	

<b>3-pole</b>	
Type	Order No.
SAIL-M12G-3-1.5V	1925430150
SAIL-M12G-3-1.5U	9457810150
SAIL-M12G-3-1.5UGE	1092980150
SAIL-M12G-3-1.5T	1021750150
SAIL-M12W-3-1.5V	1925510150
SAIL-M12W-3-1.5U	9456690150
SAIL-M12W-3-1.5UGE	1093160150
SAIL-M12W-3-1.5T	1021760150
SAIL-M12BG-3-1.5V	1925570150
SAIL-M12BG-3-1.5U	9457820150
SAIL-M12BG-3-1.5UGE	1092910150
SAIL-M12BG-3-1.5T	1968590150
SAIL-M12BW-3-1.5V	1925630150
SAIL-M12BW-3-1.5U	9457320150
SAIL-M12BW-3-1.5UGE	1092940150
SAIL-M12BW-3-1.5T	1968560150
Other versions on request	

<b>4-pole</b>	
Type	Order No.
SAIL-M12G-4-1.5V	1925440150
SAIL-M12G-4-1.5U	9456100150
SAIL-M12G-4-1.5UGE	1077750150
SAIL-M12G-4-1.5T	1021770150
SAIL-M12W-4-1.5V	1925520150
SAIL-M12W-4-1.5U	1906260150
SAIL-M12W-4-1.5UGE	1093170150
SAIL-M12W-4-1.5T	1021790150
SAIL-M12BG-4-1.5V	1925580150
SAIL-M12BG-4-1.5U	9457730150
SAIL-M12BG-4-1.5UGE	1092920150
SAIL-M12BG-4-1.5T	1968580150
SAIL-M12BW-4-1.5V	1925640150
SAIL-M12BW-4-1.5U	9457740150
SAIL-M12BW-4-1.5UGE	1092960150
SAIL-M12BW-4-1.5T	1968570150
Other versions on request	

<b>5-pole</b>	
Type	Order No.
SAIL-M12G-5-1.5V	1925450150
SAIL-M12G-5-1.5U	9457610150
SAIL-M12G-5-1.5UGE	1092990150
SAIL-M12G-5-1.5T	1021650150
SAIL-M12W-5-1.5V	1925530150
SAIL-M12W-5-1.5U	9457670150
SAIL-M12W-5-1.5UGE	1093180150
SAIL-M12W-5-1.5T	1021660150
SAIL-M12BG-5-1.5V	1925590150
SAIL-M12BG-5-1.5U	9457910150
SAIL-M12BG-5-1.5UGE	1092930150
SAIL-M12BG-5-1.5T	1021670150
SAIL-M12BW-5-1.5V	1925650150
SAIL-M12BW-5-1.5U	9457690150
SAIL-M12BW-5-1.5UGE	1092970150
SAIL-M12BW-5-1.5T	1021690150
Other versions on request	

#### Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m      xxxxxx0150
	3.0 m      xxxxxx0300
	5.0 m      xxxxxx0500
	10.0 m     xxxxxx1000

#### Technical data





Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	
Approvals	cULus; GOSTME25; ROHS

Chapter W includes additional technical specifications for the cable

#### Dimensioned drawing



**M12 one end without connector A-coded with plastic threaded ring**



#### Ordering data

<b>Male, straight</b>	
PUR halogen-free	1.5 m
<b>Male, angled</b>	
PUR halogen-free	1.5 m
<b>Female, straight</b>	
PUR halogen-free	1.5 m
<b>Female, angled</b>	
PUR halogen-free	1.5 m
<b>Note</b>	

Type	Order No.
SAIP-M12G-3-1.5U	1108800150
SAIP-M12W-3-1.5U	1108670150
SAIP-M12BG-3-1.5U	1108730150
SAIP-M12BW-3-1.5U	1108770150

Type	Order No.
SAIP-M12G-4-1.5U	1108810150
SAIP-M12W-4-1.5U	1108680150
SAIP-M12BG-4-1.5U	1108740150
SAIP-M12BW-4-1.5U	1108780150

Type	Order No.
SAIP-M12G-5-1.5U	1108820150
SAIP-M12W-5-1.5U	1108690150
SAIP-M12BG-5-1.5U	1108750150
SAIP-M12BW-5-1.5U	1108790150

#### Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

#### Technical data

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (3- and 4-pole) / 125 V (5-pole)
Approvals	




Chapter W includes additional technical specifications for the cable

#### Dimensioned drawing



**M12 one end without connector****A-coded**


with stainless-steel threaded ring

**1.4404/316L****Ordering data**

<b>Female, straight</b>	
PUR halogen-free	1.5 m
<b>Female, angled</b>	
PUR halogen-free	1.5 m
<b>Note</b>	

Type	Order No.
SAIV-M12BG-2/4-1.5U	1939410150
SAIV-M12BW-2/4-1.5U	1939370150

Type	Order No.
SAIV-M12BG-4-1.5U	9457950150
SAIV-M12BW-4-1.5U	9457960150


**Standard cable lengths**




All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.34 mm²
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V
Approvals	

Chapter W includes additional technical specifications for the cable


**Dimensioned drawing**

**M12 8 / 12-pole****A-coded****Ordering data**

<b>Male, straight</b>	
PUR halogen-free	1.5 m
<b>Male, angled</b>	
PUR halogen-free	1.5 m
<b>Female, straight</b>	
PUR halogen-free	1.5 m
<b>Female, angled</b>	
PUR halogen-free	1.5 m
<b>Male, straight - Socket, straight</b>	
PUR halogen-free	1.5 m
<b>Male, straight - Socket, angled</b>	
PUR halogen-free	1.5 m
<b>Note</b>	

Type	Order No.
SAIL-M12G-8-1.5U	1279410150
SAIL-M12W-8-1.5U	1279420150
SAIL-M12BG-8-1.5U	1865870150
SAIL-M12BW-8-1.5U	1883460150
SAIL-M12GM12G-8-1.5U	1279440150
SAIL-M12GM12W-8-1.5U	1279450150


Type	Order No.
SAIL-M12G-12-1.5U	1311700150
SAIL-M12W-12-1.5U	1311690150
SAIL-M12BG-12-1.5U	1879710150
SAIL-M12BW-12-1.5U	1898240150

**Standard cable lengths**


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Rated current	1 A
Protection degree	IP 67, IP 68
Core cross-section	0.25 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	30 V
Approvals	

**Dimensioned drawing**


**M12 8-pole**  
A-coded  
shielded



## Ordering data

<b>Male, straight</b>	
PUR halogen-free	1.5 m
<b>Male, angled</b>	
PUR halogen-free	1.5 m
<b>Female, straight</b>	
PUR halogen-free	1.5 m
<b>Female, angled</b>	
PUR halogen-free	1.5 m
<b>Male, straight - Socket, straight</b>	
PUR halogen-free	1.5 m
<b>Male, straight - Socket, angled</b>	
PUR halogen-free	1.5 m
<b>Note</b>	

<b>8-pole</b>	
Type	Order No.
SAIL-M12G-8S1.5U	1279430150
SAIL-M12W-8S1.5U	1276060150
SAIL-M12BG-8S1.5U	1890520150
SAIL-M12BW-8S1.5U	1275470150
SAIL-M12GM12G-8S1.5U	1279460150
SAIL-M12GM12W-8S1.5U	1279470150




## Standard cable lengths

All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000





## Technical data

Rated current	1 A
Protection degree	IP 67
Core cross-section	0.25 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	30 V
Approvals	

## Dimensioned drawing



**M12 one end without connector with LED A-coded female, angled**



#### Ordering data

Female, angled	
PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m
Resistant to welding beads	1.5 m

#### Note

#### 2 LEDs

Type	Order No.
SAIL-M12BW-3L1.5V	1925460150
SAIL-M12BW-3L1.5U	9457800150
SAIL-M12BW-3L1.5UGE	1114880150
SAIL-M12BW-3L1.5T	1004330150

#### 3-pole

#### 2 LEDs

Type	Order No.
SAIL-M12BW-4-2L1.5V	1925470150
SAIL-M12BW-4-2L1.5U	9456380150
SAIL-M12BW-4-2L1.5UGE	1092950150
SAIL-M12BW-4-2L1.5T	1007000150

#### 4-pole

#### 3 LEDs

Type	Order No.
SAIL-M12BW-4-3L1.5V	1963960150
SAIL-M12BW-4-3L1.5U	1963940150

#### 4-pole

Other versions on request

#### Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

#### Technical data

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (3- and 4-pole) / 125 V (5-pole)
Approvals	CSA; cURus; GOSTME25; ROHS



Chapter W includes additional technical specifications for the cable

#### Dimensioned drawing





**M12 one end without connector**  
shielded  
**A-coded**



#### Ordering data

<b>Male, straight</b>	
PUR halogen-free	1.5 m
<b>Male, angled</b>	
PUR halogen-free	1.5 m
<b>Female, straight</b>	
PUR halogen-free	1.5 m
<b>Female, angled</b>	
PUR halogen-free	1.5 m
<b>Note</b>	

Type	Order No.
SAIL-M12G-3S1.5U	1906470150
SAIL-M12W-3S1.5U	1906500150
SAIL-M12BG-3S1.5U	1867410150
SAIL-M12BW-3S1.5U	1906950150
Other versions on request	

Type	Order No.
SAIL-M12G-4S1.5U	1906480150
SAIL-M12W-4S1.5U	1059650150
SAIL-M12BG-4S1.5U	1812540150
SAIL-M12BW-4S1.5U	1808970150
Other versions on request	

Type	Order No.
SAIL-M12G-5S1.5U	1926690150
SAIL-M12W-5S1.5U	1906520150
SAIL-M12BG-5S1.5U	9456140150
SAIL-M12BW-5S1.5U	1906540150
Other versions on request	

#### Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000



#### Technical data

Rated current	4 A
Protection degree	IP 67
Core cross-section	mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (3- and 4-pole) / 125 V (5-pole)
Approvals	cULus; GOSTME25; ROHS

Chapter W includes additional technical specifications for the cable

#### Dimensioned drawing




**Sensor cables****Twin cabling****M12 one end without connector****Ordering data**

<b>Male straight - open ended</b>	
PUR halogen-free	1.5 m

**Note**

Type	Order No.
SAIL-ZW-3-1.5U	1964310150


**Standard cable lengths**




All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (3- and 4-pole) / 125 V (5-pole)
Approvals	CSA; cURus; GOSTME25; ROHS

Chapter W includes additional technical specifications for the cable

**Dimensioned drawing**

**M8 one end without connector**
**Ordering data****Male, straight**

PVC	1.5 m
PUR halogen-free	1.5 m

**Male, angled**

PVC	1.5 m
PUR halogen-free	1.5 m

**Female, straight**

PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m

**Female, angled**

PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m

**Note****3-pole**

Type	Order No.
SAIL-M8G-3-1.5V	1927230150
SAIL-M8G-3-1.5U	1824590150

Type	Order No.
SAIL-M8W-3-1.5V	1927310150
SAIL-M8W-3-1.5U	1857550150

Type	Order No.
SAIL-M8BG-3-1.5V	1927240150
SAIL-M8BG-3-1.5U	9457450150
SAIL-M8BG-3-1.5UGE	1093190150

Type	Order No.
SAIL-M8BW-3-1.5V	1927320150
SAIL-M8BW-3-1.5U	9457380150
SAIL-M8BW-3-1.5UGE	1093220150

**4-pole**

Type	Order No.
SAIL-M8G-4-1.5V	1927250150
SAIL-M8G-4-1.5U	1906270150

Type	Order No.
SAIL-M8W-4-1.5V	1927330150
SAIL-M8W-4-1.5U	1857560150

Type	Order No.
SAIL-M8BG-4-1.5V	1927260150
SAIL-M8BG-4-1.5U	9457850150
SAIL-M8BG-4-1.5UGE	1093200150

Type	Order No.
SAIL-M8BW-4-1.5V	1927340150
SAIL-M8BW-4-1.5U	9456150150
SAIL-M8BW-4-1.5UGE	1093240150


**Standard cable lengths**

All cables listed under the ordering data have a length of 1.5 m metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000




**Technical data**

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.25 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage	60 V (3-pole) / 30 V (4-pole) (acc. to VDE standard 0110 ISO group C)
Approvals	cURus; GOSTME25; ROHS

Chapter W includes additional technical specifications for the cable

**Dimensioned drawing**

**M8 one end without connector snap-on connection**



**Ordering data**

**Female, straight**

PVC	1.5 m
PUR halogen-free	1.5 m

**Female, angled**

PVC	1.5 m
PUR halogen-free	1.5 m

**Note**

**3-pole**

Type	Order No.
SAIL-M8BGR-3-1.5V	1948710150
SAIL-M8BGR-3-1.5U	1827020150

Type	Order No.
SAIL-M8BWR-3-1.5V	1948720150
SAIL-M8BWR-3-1.5U	1827010150

Other versions on request

**4-pole**

Type	Order No.
SAIL-M8BGR-4-1.5V	1948730150
SAIL-M8BGR-4-1.5U	1948530150

Type	Order No.
SAIL-M8BWR-4-1.5V	1948740150
SAIL-M8BWR-4-1.5U	1948540150

Other versions on request

**Standard cable lengths**


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000






**Technical data**

Rated current	4 A
Protection degree	IP 65
Core cross-section	0.25 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	60 V (3-pole) / 30 V (4-pole)
Approvals	

Chapter W includes additional technical specifications for the cable

**Dimensioned drawing**




**M8 one end without connector with LED**
**Female****3-pole****4-pole****Ordering data****Female, angled**

PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m

**Note**

Type	Order No.
SAIL-M8BW-3L1.5V	1927350150
SAIL-M8BW-3L1.5U	9457460150
SAIL-M8BW-3L1.5UGE	1093210150

Other versions on request

**3-pole**

Type	Order No.
SAIL-M8BW-4L1.5V	1927360150
SAIL-M8BW-4L1.5U	1906400150
SAIL-M8BW-4L1.5UGE	1093230150

Other versions on request


**4-pole****Standard cable lengths**




All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.25 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	60 V (3-pole) / 30 V (4-pole)
Approvals	CSA; cURus; GOSTME25; ROHS

Chapter W includes additional technical specifications for the cable


**Dimensioned drawing**

**M8 one end without connector shielded**
**Ordering data**

<b>Male, straight</b>	
PUR halogen-free	1.5 m
<b>Male, angled</b>	
PUR halogen-free	1.5 m
<b>Female, straight</b>	
PUR halogen-free	1.5 m
<b>Female, angled</b>	
PUR halogen-free	1.5 m
<b>Note</b>	

Type	Order No.
SAIL-M8G-3S1.5U	1906560150
SAIL-M8W-3S1.5U	1906580150
SAIL-M8BG-3S1.5U	1906600150
SAIL-M8BW-3S1.5U	1906620150
Other versions on request	

Type	Order No.
SAIL-M8G-4S1.5U	1906570150
SAIL-M8W-4S1.5U	1906590150
SAIL-M8BG-4S1.5U	1906610150
SAIL-M8BW-4S1.5U	1906630150
Other versions on request	


**Standard cable lengths**


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Rated current	4 A
Protection degree	IP 67
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	60 V (3-pole) / 30 V (4-pole)
Approvals	

Chapter W includes additional technical specifications for the cable


**Dimensioned drawing**

**M5 one end without connector**

**Ordering data**

<b>Male, straight</b>	
PUR halogen-free	1.5 m
<b>Male, angled</b>	
PUR halogen-free	1.5 m
<b>Female, straight</b>	
PUR halogen-free	1.5 m
<b>Female, angled</b>	
PUR halogen-free	1.5 m
<b>Note</b>	

Type	Order No.
SAIL-M5G-3P-1.5U	<b>1854060150</b>
SAIL-M5W-3P-1.5U	<b>1873280150</b>
SAIL-M5BG-3P-1.5U	<b>1873290150</b>
SAIL-M5BW-3P-1.5U	<b>1873260150</b>
Other versions on request	

Type	Order No.
SAIL-M5G-4P-1.5U	<b>1871700150</b>
SAIL-M5W-4P-1.5U	<b>1873240150</b>
SAIL-M5BG-4P-1.5U	<b>1873250150</b>
SAIL-M5BW-4P-1.5U	<b>1873270150</b>
Other versions on request	



**Standard cable lengths**

All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Rated current	1 A
Protection degree	IP 67
Core cross-section	0.25 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	60 V
Approvals	

Chapter W includes additional technical specifications for the cable

**Dimensioned drawing**


# Connecting cables

**M12****M8****M8 Snap connection****Twin cabling**

Many applications with sensors require suitable connecting cables. The connecting cables are available in different designs.

The M12/M8 plug-in connectors are available in straight and 90° versions and also with LEDs.

- When plugged in, the M12 connecting cables comply with IP 68 ingress protection class.
- The cable sheathing is black and made of polyurethane (PUR or PVC).
- The connecting cables are supplied with two marking sleeves.

Corresponding tags TM-I 18 for the marking sleeves can be found in chapter I.


## Sensor cables





Weidmüller can supply various cable lengths as indicated in the following table:

### Typical cable lengths are:

- 1.5 m
- 3.0 m
- 5.0 m
- 10.0 m

### Example of designation



**Connecting cables****M12 to M12****A-coded****Ordering data****Male, straight - Female, straight**

PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m
Resistant to welding beads	1.5 m

**Male, straight - Female, angled**

PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m
Resistant to welding beads	1.5 m

**Male, angled - Female, angled**

PVC	1.5 m
PUR halogen-free	1.5 m

**Note****3-pole**

Type	Order No.
SAIL-M12GM12G-3-1.5V	1925300150
SAIL-M12GM12G-3-1.5U	9457230150
SAIL-M12GM12G-3-1.5UGE	1093010150
SAIL-M12GM12G-3-1.5T	1021710150
SAIL-M12GM12W-3-1.5V	1925340150
SAIL-M12GM12W-3-1.5U	9457390150
SAIL-M12GM12W-3-1.5UGE	1093050150
SAIL-M12GM12W-3-1.5T	1021720150
SAIL-M12WM12W-3-1.5V	1925380150
SAIL-M12WM12W-3-1.5U	1815670150

Other versions on request

**4-pole**

Type	Order No.
SAIL-M12GM12G-4-1.5V	1925310150
SAIL-M12GM12G-4-1.5U	1906300150
SAIL-M12GM12G-4-1.5UGE	1093020150
SAIL-M12GM12G-4-1.5T	1021730150
SAIL-M12GM12W-4-1.5V	1925350150
SAIL-M12GM12W-4-1.5U	9457310150
SAIL-M12GM12W-4-1.5UGE	1093070150
SAIL-M12GM12W-4-1.5T	1021740150
SAIL-M12WM12W-4-1.5V	1925390150
SAIL-M12WM12W-4-1.5U	1906310150

Other versions on request

**5-pole**

Type	Order No.
SAIL-M12GM12G-5-1.5V	1925320150
SAIL-M12GM12G-5-1.5U	9457340150
SAIL-M12GM12G-5-1.5UGE	1093030150
SAIL-M12GM12G-5-1.5T	1011970150
SAIL-M12GM12W-5-1.5V	1925360150
SAIL-M12GM12W-5-1.5U	9457270150
SAIL-M12GM12W-5-1.5UGE	1093080150
SAIL-M12GM12W-5-1.5T	1011990150
SAIL-M12WM12W-5-1.5V	1925400150
SAIL-M12WM12W-5-1.5U	9457900150

Other versions on request


**Standard cable lengths**

All cables listed under the ordering data have a length of 1.5 m metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage	250 V (3- and 4-pole) / 125 V (5-pole) (acc. to VDE standard 0110 ISO group C)
Approvals	cULus; GOSTME25; ROHS



Chapter W includes additional technical specifications for the cable

**Dimensioned drawing**

## Connecting cables

M12 to M12

A-coded

Bridged between  
pins 2 and 4

## Ordering data

## Male, straight - Female, straight


PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m

## Male, straight - Female, angled

PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m

## Note

Type	Order No.
SAIL-M12GM12G-2/4-1.5V	1925330150
SAIL-M12GM12G-2/4-1.5U	9456990150
SAIL-M12GM12G-2/4-1.5UGE	1093000150
SAIL-M12GM12W-2/4-1.5V	1925370150
SAIL-M12GM12W-2/4-1.5U	9457890150
SAIL-M12GM12W-2/4-1.5UGE	1093040150



## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000


## Technical data

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.34 mm²
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (3- and 4-pole) / 125 V (5-pole)
Approvals	cULus; GOSTME25; ROHS


Chapter W includes additional technical specifications for the cable

## Dimensioned drawing




**Connecting cables****M12 to M12, LED****A-coded****male, straight - female, angled****Ordering data****Male, straight - Female, angled**

PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m
Resistant to welding beads	1.5 m

**Note****2 LEDs**


Type	Order No.
SAIL-M12GM12W-3L1.5V	1925410150
SAIL-M12GM12W-3L1.5U	9457790150
SAIL-M12GM12W-3L1.5T	1004320150

Other versions on request

**3-pole****2 LEDs**

Type	Order No.
SAIL-M12GM12W-4-2L1.5V	1925420150
SAIL-M12GM12W-4-2L1.5U	1906410150
SAIL-M12GM12W-4-2L1.5T	1004310150

Other versions on request

**3 LEDs**

Type	Order No.
SAIL-M12GM12W-4-3L1.5V	1963930150
SAIL-M12GM12W-4-3L1.5U	1963910150
SAIL-M12GM12W-4-3LW1.5UGE	1093060150
SAIL-M12GM12W-4-3LW1.5T	1020930150

Other versions on request


**Standard cable lengths**

All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**





Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.34 mm²
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (3- and 4-pole) / 125 V (5-pole)
Approvals	cURus; GOSTME25; ROHS

Chapter W includes additional technical specifications for the cable

**Dimensioned drawing**

**Sensor cables****Connecting cables****M12 to M12**

**A-coded**  
**shielded**

**Ordering data****Male, straight - Female, straight**

PUR halogen-free 1.5 m

**Male, straight - Female, angled**

PUR halogen-free 1.5 m

**Male, angled - Female, angled**

PUR halogen-free 1.5 m

**Note**

Type	Order No.
SAIL-M12GM12G-3S1.5U	<b>1058490150</b>
SAIL-M12GM12W-3S1.5U	<b>1059470150</b>
SAIL-M12WM12W-3S1.5U	<b>1059720150</b>
Other versions on request	

Type	Order No.
SAIL-M12GM12G-4S1.5U	<b>1058500150</b>
SAIL-M12GM12W-4S1.5U	<b>1059480150</b>
SAIL-M12WM12W-4S1.5U	<b>1059730150</b>
Other versions on request	

Type	Order No.
SAIL-M12GM12G-5S1.5U	<b>1058510150</b>
SAIL-M12GM12W-5S1.5U	<b>1059540150</b>
SAIL-M12WM12W-5S1.5U	<b>1059740150</b>
Other versions on request	


**Standard cable lengths**

All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m xxxxxx0150
	3.0 m xxxxxx0300
	5.0 m xxxxxx0500
	10.0 m xxxxxx1000

**Technical data**

Rated current	4 A
Protection degree	IP 67
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (3- and 4-pole) / 125 V (5-pole)
Approvals	cULus; GOSTME25; ROHS



Chapter W includes additional technical specifications for the cable

**Dimensioned drawing**



## Connecting cables

M12 to M8



## Ordering data

## Male, straight - Female, straight

PVC	1.5 m
PUR halogen-free	1.5 m

## Male, straight - Female, angled

PVC	1.5 m
PUR halogen-free	1.5 m

## Male, angled - Female, angled

PVC	1.5 m
PUR halogen-free	1.5 m

## Note

## 3-pole

Type	Order No.
SAIL-M12GM8G-3-1.5V	1938170150
SAIL-M12GM8G-3-1.5U	9457770150

Type	Order No.
SAIL-M12GM8W-3-1.5V	1938180150
SAIL-M12GM8W-3-1.5U	9457980150

Type	Order No.
SAIL-M12WM8W-3-1.5V	1938190150
SAIL-M12WM8W-3-1.5U	1906330150

Other versions on request

## 4-pole

Type	Order No.
SAIL-M12GM8G-4-1.5V	1938200150
SAIL-M12GM8G-4-1.5U	9456660150

Type	Order No.
SAIL-M12GM8W-4-1.5V	1938210150
SAIL-M12GM8W-4-1.5U	9456670150

Type	Order No.
SAIL-M12WM8W-4-1.5V	1938220150
SAIL-M12WM8W-4-1.5U	1906340150

Other versions on request

## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

## Technical data

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.25 mm²
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	60 V (3-pole) / 30 V (4-pole)
Approvals	cURus; GOSTME25; ROHS

Chapter W includes additional technical specifications for the cable



## Dimensioned drawing



## Connecting cables

M12 to M8

snap-on connection



## Ordering data

**Male, straight - Female, straight**

PUR halogen-free 1.5 m


**Male, straight - Female, angled**

PUR halogen-free 1.5 m

PUR halogen-free yellow 1.5 m

**Note**

3-pole	
Type	Order No.
SAIL-M12GM8GR-3-1.5U	1984530150
SAIL-M12GM8WR-3-1.5U	9457570150
SAIL-M12GM8WR-3-1.5UGE	1093150150
Other versions on request	



## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

## Technical data

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.25 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	60 V (3-pole) / 30 V (4-pole)
Approvals	


Chapter W includes additional technical specifications for the cable

## Dimensioned drawing



## Connecting cables

M12 to M8 LED



## Ordering data

Male, straight - Female, angled

PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m

## Note

## 2 LEDs


Type	Order No.
SAIL-M12GM8W-3L1.5V	1962290150
SAIL-M12GM8W-3L1.5U	9457760150
SAIL-M12GM8W-3L1.5UGE	1093110150

## 3-pole

## 2 LEDs

Type	Order No.
SAIL-M12GM8W-4L1.5V	1962300150
SAIL-M12GM8W-4L1.5U	1906430150
SAIL-M12GM8W-4L1.5UGE	1093130150

## 4-pole



## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

## Technical data

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.25 mm²
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	60 V (3-pole) / 30 V (4-pole)
Approvals	cURus; GOSTME25; ROHS




Chapter W includes additional technical specifications for the cable

## Dimensioned drawing



## Connecting cables

M8 to M8



## Ordering data

## Male, straight - Female, straight

PVC	1.5 m
PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m

## Male, straight - Female, angled

PVC	1.5 m
PUR halogen-free	1.5 m

## Male, angled - Female, angled

PVC	1.5 m
PUR halogen-free	1.5 m

## Note

Type	Order No.
SAIL-M8GM8G-3-1.5V	1927150150
SAIL-M8GM8G-3-1.5U	1824570150
SAIL-M8GM8G-3-1.5UGE	1104470150
SAIL-M8GM8W-3-1.5V	1927170150
SAIL-M8GM8W-3-1.5U	1824580150
SAIL-M8WM8W-3-1.5V	1927210150
SAIL-M8WM8W-3-1.5U	1857670150

Type	Order No.
SAIL-M8GM8G-4-1.5V	1927160150
SAIL-M8GM8G-4-1.5U	1880470150
SAIL-M8GM8W-4-1.5V	1927180150
SAIL-M8GM8W-4-1.5U	1857660150
SAIL-M8WM8W-4-1.5V	1927220150
SAIL-M8WM8W-4-1.5U	1857680150

Other versions on request

## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

## Technical data

Rated current	4 A
Protection degree	IP 67
Core cross-section	0.25 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	60 V (3-pole) / 30 V (4-pole)
Approvals	cURus; GOSTME25; ROHS




Chapter W includes additional technical specifications for the cable

## Dimensioned drawing



**Connecting cables****M8 to M8**

snap-on connection

**Ordering data****Male, straight - Female, straight**

PVC	1.5 m
PUR halogen-free	1.5 m

**Male, straight - Female, angled**

PVC	1.5 m
PUR halogen-free	1.5 m


**Male, angled - Female, angled**

PVC	1.5 m
PUR halogen-free	1.5 m

**Note**

Type	Order No.
SAIL-M8GM8GR-3-1.5V	1948650150
SAIL-M8GM8GR-3-1.5U	1948470150
SAIL-M8GM8WR-3-1.5V	1948660150
SAIL-M8GM8WR-3-1.5U	1948480150
SAIL-M8WM8WR-3-1.5V	1948670150
SAIL-M8WM8WR-3-1.5U	1948490150
Other versions on request	

Type	Order No.
SAIL-M8GM8GR-4-1.5V	1948680150
SAIL-M8GM8GR-4-1.5U	1948500150
SAIL-M8GM8WR-4-1.5V	1948690150
SAIL-M8GM8WR-4-1.5U	1948510150
SAIL-M8WM8WR-4-1.5V	1948700150
SAIL-M8WM8WR-4-1.5U	1948520150
Other versions on request	



**Standard cable lengths**

All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**


Rated current	4 A
Protection degree	IP 65
Core cross-section	0.25 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	60 V (3-pole) / 30 V (4-pole)
Approvals	

Chapter W includes additional technical specifications for the cable

**Dimensioned drawing**

## Connecting cables

## M8 to M8 LED



## Ordering data

## Male, straight - Female, angled

PVC	1.5 m
PUR halogen-free	1.5 m

## Note

## 2 LEDs

Type	Order No.
SAIL-M8GM8W-3L1.5V	1927190150
SAIL-M8GM8W-3L1.5U	1877250150



Other versions on request

## 3-pole

Type	Order No.
SAIL-M8GM8W-4L1.5V	1927200150
SAIL-M8GM8W-4L1.5U	1906450150

Other versions on request

## 4-pole

## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

## Technical data

Rated current	4 A
Protection degree	IP 67
Core cross-section	0.25 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	60 V (3-pole) / 30 V (4-pole)
Approvals	cURus; GOSTME25; ROHS

Chapter W includes additional technical specifications for the cable

## Dimensioned drawing





# Twin sensor cables with three plug-in connectors: M12/M8

## Twin sensor cables

B



In general, two sensor cables can be fed with an M12 connector to the distributor. A wide variety of wiring arrangements are possible with these cables. All M12 and M8 connections can be implemented.

Weidmüller has all the necessary components available. With mechanical engineering, this type of application is an exception.

### 4-pole connection


In the SAI distributor, the 4 pole socket is fitted with pins 1, 3, 4 and 5. The 4 pole SAI plug is fitted with pins 1, 2, 3 and 4. This corresponds to market standards.

Special care must be taken when wiring combinations of 4-pole plugs and distributors.




## Designation


Twin plug  
Bifurcation open for "1" and "2" ends



Twin plug  
Connecting cable



**Twin cabling**  
M12 to M12




**Ordering data**

Male straight - 2 females straight	
PUR halogen-free	1.5 m
Male straight - 2 females angled	
PUR halogen-free	1.5 m

**Note**

Type	Order No.
SAIL-ZW-M12BG-3-1.5U	1005460150
SAIL-ZW-M12BW-3-1.5U	1005270150

Type	Order No.
SAIL-ZW-M12BW-3L1.5U	1912110150



**Standard cable lengths**


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V
Approvals	CSA; cURus; GOSTME25; ROHS


Chapter W includes additional technical specifications for the cable

**Dimensioned drawing**



**Twin cabling**

**M12 to M12**  
bridge between  
pins 2 and 4

**Ordering data****Male straight - 2 females straight**

PUR halogen-free 1.5 m

**Male straight - 2 females angled**


PUR halogen-free 1.5 m

**Note**

Type	Order No.
SAIL-ZW-M12BG-2/4-1.5U	1812550150
SAIL-ZW-M12BW-2/4-1.5U	1964280150

**2 LEDs**

Type	Order No.
SAIL-ZW-M12BW-2/4L1.5U	1964290150


**3-pole****Standard cable lengths**

All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**


Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (3- and 4-pole) / 125 V (5-pole)
Approvals	

Chapter W includes additional technical specifications for the cable

**Dimensioned drawing**



## Twin cabling M12 to M8



### Ordering data

#### Male straight - 2 females straight

PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m

#### Male straight - 2 females angled

PUR halogen-free	1.5 m
PUR halogen-free yellow	1.5 m

#### Note

### 3-pole

Type	Order No.
SAIL-ZW-M8BG-3-1.5U	9457490150
SAIL-ZW-M8BG-3-1.5UGE	1093250150

Type	Order No.
SAIL-ZW-M8BW-3-1.5U	1964300150
SAIL-ZW-M8BW-3-1.5UGE	1093260150

Other versions on request

### 2 LEDs

Type	Order No.
SAIL-ZW-M8BW-3L1.5U	9457410150

Other versions on request

### 3-pole

Type	Order No.

Other versions on request

### Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

### Technical data

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.25 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	60 V (3-pole) / 30 V (4-pole)
Approvals	cURus; GOSTME25; ROHS

Chapter W includes additional technical specifications for the cable

### Dimensioned drawing




**M16 lines, moulded****One end without connector****Female****Ordering data**

PUR	1.5 m
<b>Note</b>	

**12-pole**


Type	Order No.
SAIL-M16BW-12-1.5U	<b>1259010150</b>

**Standard cable lengths**

All cables listed in the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Rated current	3 A
Protection degree	IP 67
Core cross-section	0.25 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25 ... +70 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	60 V

**Dimensioned drawing**







## B-coded M12 cables

**B**

Connector coding is very important to avoid the potential risk of damage due to connectors being incorrectly plugged together. This risk is particularly high when you need to plug in differing voltages. For example, it is not unusual to connect 110 or 230 V with a M12 plug-in connector. However if a 24 V electric potential is connected with a 110 or 230 V line, it will inevitably lead to destructive results. B-coding has been introduced for such cases. B-coded connectors are shaped so that they can not be fitted together unless extreme force is used. This coding makes it safe to use the standard M12 connector system in a single machine for different voltages which may exceeding 24 V. For the SAI Active Universal System, the power plug is A-coded since it only provides 24 V. The Profibus DP also takes advantage of this coding scheme. It is currently the only bus system using B-coded M12 plugs for IP 67-protected connections. In this case, special approved bulk stock cable is used instead of the power cables.

**M12 one end without connector**  
unshielded  
B-coded



#### Ordering data

<b>Male, straight</b>	
PUR halogen-free	1.5 m
<b>Male, angled</b>	
PUR halogen-free	1.5 m
<b>Female, straight</b>	
PUR halogen-free	1.5 m
<b>Female, angled</b>	
PUR halogen-free	1.5 m
<b>Note</b>	

Type	Order No.
SAIL-M12G-3B-1.5U	1057770150
SAIL-M12W-3B-1.5U	1057800150
SAIL-M12BG-3B-1.5U	1057740150
SAIL-M12BW-3B-1.5U	1061890150

Type	Order No.
SAIL-M12G-4B-1.5U	1057780150
SAIL-M12W-4B-1.5U	1057810150
SAIL-M12BG-4B-1.5U	1057750150
SAIL-M12BW-4B-1.5U	1061900150

Type	Order No.
SAIL-M12G-5B-1.5U	1057790150
SAIL-M12W-5B-1.5U	1057820150
SAIL-M12BG-5B-1.5U	1061880150
SAIL-M12BW-5B-1.5U	1057760150

#### Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

#### Technical data

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (3- and 4-pole) / 125 V (5-pole)
Approvals	

Chapter W includes additional technical specifications for the cable

#### Dimensioned drawing







## Power cables

## M12 connecting cable

unshielded

B-coded



## Ordering data

## Male, straight - Female, straight

PUR halogen-free 1.5 m

## Male, straight - Female, angled

PUR halogen-free 1.5 m

## Male, angled - Female, angled

PUR halogen-free 1.5 m

## Male, angled - female, straight

PUR halogen-free 1.5 m

## Note

Type	Order No.
SAIL-M12GM12G-3B-1.5U	1057830150
SAIL-M12GM12W-3B-1.5U	1057900150
SAIL-M12WM12W-3B-1.5U	1061910150
SAIL-M12WM12G-3B-1.5U	1057870150

Type	Order No.
SAIL-M12GM12G-4B-1.5U	1057840150
SAIL-M12GM12W-4B-1.5U	1057910150
SAIL-M12WM12W-4B-1.5U	1061920150
SAIL-M12WM12G-4B-1.5U	1057880150

Type	Order No.
SAIL-M12GM12G-5B-1.5U	1057850150
SAIL-M12GM12W-5B-1.5U	1057920150
SAIL-M12WM12W-5B-1.5U	1061930150
SAIL-M12WM12G-5B-1.5U	1057890150

## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 m.	1.5 m	xxxxxx0150
metres. The last four ordering digits must be changed when ordering other standard cable lengths.	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

## Technical data

Rated current	4 A
Protection degree	IP 65, IP 66, IP 67, IP 68
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (3- and 4-pole) / 125 V (5-pole)
Approvals	

Chapter W includes additional technical specifications for the cable

## Dimensioned drawing






# Valve plug, ISO 4400




**Valve plug  
Type A**



Contact gap 18 mm


Type: VSA

**Valve plug  
Type B**



Contact gap 11 mm  
Industry standard

Type: VSB



Contact gap 10 mm  
to DIN 43650 (ISO 6952)  
Type: VSBD

**Valve plug  
Type C**



Contact gap 9.4 mm  
Industry standard

Type: VSC



Contact gap 8 mm  
to DIN 43650 (ISO 6952)

Type: VSBD

Machine builders frequently need different cable lengths for valve plugs. Valve plugs with free cable ends can be used to adjust the cable exactly to the lengths required.

Weidmüller can also supply valve plugs as connecting cables with M12 plugs.

The status of the valve plug is shown by an LED. Every valve plug is fitted with a protective circuit.

The Weidmüller range includes valve plugs of type A, B and C to DIN and industry standards.

Weidmüller plugs comply with IP 67 ingress protection class when plugged in.

The outgoing direction is also crucial. Weidmüller can supply 0° versions, i.e. the outgoing direction of the cable is at the PE contact.

## Types

Type	Contact gap
Type A	18 mm
Type B industry standard	11 mm
Type B DIN	10 mm
Type C industry standard	9.4 mm
Type C DIN	8.0 mm

## Example of designation

Valve plug  
Connector at one end only

**SAIL-VSBD - 1.5 U**

Valve plug	Cable length	Cable
VSA	1.5 m	Q = PUR-TPE
VSB	3.0 m	V = PVC-PVC
VSBD	5.0 m	U = PUR-PVC
VSC	10 m	
VSBD	X m	

Valve plug  
Connecting cable

**SAIL-VSBD - M8W 1.5 U**

Valve plug	M12	Cable length	Cable
VSA	M8	1.5 m	Q = PUR-TPE
VSB		3.0 m	V = PVC-PVC
VSBD		5.0 m	U = PUR-PVC
VSC		10 m	
VSBD		X m	


G = straight      W = 90°

Cable length	Cable
1.5 m	Q = PUR-TPE
3.0 m	V = PVC-PVC
5.0 m	U = PUR-PVC
10 m	
X m	

**Design A****Ordering data**

<b>Open cable end - valve plug</b>	1.5 m
<b>Male straight - valve plug</b>	1.5 m
<b>Male angled - valve plug</b>	1.5 m
<b>Note</b>	Other versions on request

<b>A</b>	
Type	Order No.
SAIL-VSA-1.5U	9457710150
SAIL-VSA-M12G-1.5U	9457040000
SAIL-VSA-M12W-1.5U	1857690150
Other versions on request	


**Standard cable lengths**

All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed to order other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Sheathing colour	Grey
Sheath material	PUR
Rated current	4 A
Protection degree	IP 67
Core cross-section	0.75 mm <sup>2</sup>
Contact surface	tinned
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	24 V
Approvals	

L in the drawing is the cable length

**Dimensioned drawing**

## Valve cables

## Design B/BD

B = Industrial standard  
BD = DIN Standard


**B**

## Ordering data

<b>Open cable end - valve plug</b>	1.5 m
<b>Male straight - valve plug</b>	1.5 m
<b>Male angled - valve plug</b>	1.5 m
<b>Note</b>	Other versions on request

Type	Order No.
SAIL-VSB-1.5U	<b>9457930150</b>
SAIL-VSB-M12G-1.5U	<b>9457680150</b>
SAIL-VSB-M12W-1.5U	<b>1857700150</b>
Other versions on request	

Type	Order No.
SAIL-VSBD-1.5U	<b>9456070150</b>
SAIL-VSBD-M12G-1.5U	<b>9457780150</b>
SAIL-VSBD-M12W-1.5U	<b>1857710150</b>
Other versions on request	



## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed to order other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

## Technical data

Sheathing colour	Grey
Sheath material	PUR
Rated current	4 A
Protection degree	IP 67
Core cross-section	0.75 mm <sup>2</sup>
Contact surface	tinned
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	24 V
Approvals	

L in the drawing is the cable length

## Dimensioned drawing



**Design C/CD**


C = Industrial standard  
CD = DIN Standard

**Ordering data**

<b>Open cable end - valve plug</b>	1.5 m
<b>Male straight - valve plug</b>	1.5 m
<b>Male angled - valve plug</b>	1.5 m
<b>Note</b>	Other versions on request

<b>C</b>	
<b>Type</b>	<b>Order No.</b>
SAIL-VSC-1.5U	<b>9457920150</b>
SAIL-VSC-M12G-1.5U	<b>9457400150</b>
SAIL-VSC-M12W-1.5U	<b>1857720150</b>
Other versions on request	

<b>CD</b>	
<b>Type</b>	<b>Order No.</b>
SAIL-VSCD-1.5U	<b>9456240150</b>
SAIL-VSCD-M12G-1.5U	<b>9456170150</b>
SAIL-VSCD-M12W-1.5U	<b>1857730150</b>
Other versions on request	


**Standard cable lengths**

All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed to order other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Sheathing colour	Grey
Sheath material	PUR
Rated current	4 A
Protection degree	IP 67
Core cross-section	0.5 mm <sup>2</sup>
Contact surface	tinned
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	24 V
Approvals	

L in the drawing is the cable length

**Dimensioned drawing**

# Introduction

**Type A****Type B****Type C**

When building special machines, individual cable lengths are frequently required, which are then joined directly to Weidmüller's IDC distributors. Our product portfolio contains a corresponding valve plug for such applications.

This valve plug has a transparent enclosure with integral seal. In addition, a protective sleeve can be slipped over the cable to protect the connected line. The connection cross-section is 0.5 mm<sup>2</sup> for direct connection to our SAI IDC distributor.

The status of the valve plug is indicated by an LED. All valve plugs are fitted with protective circuits.

The Weidmüller range includes valve plug forms A, B and C to DIN and industry standards. The plug conforms to ingress protection class IP 67 when plugged in.

**Types**

Type	Contact gap
Type A	18 mm
Type B industry standard	11 mm
Type B DIN	10 mm
Type C industry standard	9.4 mm
Type C DIN	8.0 mm


**Design A**

Suitable for IDC  
plug-in connectors and protective hose  
connection

**Ordering data**

<b>Open cable end - valve plug</b>	1.5 m
<b>Note</b>	

A
SAIL-VSA-1.5U(0.5)
Supplied without protective hose


**Standard cable lengths**

All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed to order other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Sheathing colour	Black
Sheath material	PUR
Rated current	4 A
Protection degree	IP 67
Core cross-section	0.5 mm <sup>2</sup>
Contact surface	tinned
Temperature range of housing	-25...+85 °C
Rated voltage	24 V
(acc. to VDE standard 0110 ISO group C)	
Approvals	

L in the drawing is the cable length

**Dimensioned drawing**

**Valve cables****Design B/BD**

B = industry standard  
BD = DIN standard

Suitable for IDC  
plug-in connectors and protective hose  
connection

**B****Ordering data**

Open cable end - valve plug	1.5 m
<b>Note</b>	

Type	B	BD
SAIL-VSB-1.5U(0.5)	<b>1845140150</b>	<b>1845160150</b>

Supplied without protective hose

Type	Order No.
SAIL-VSBD-1.5U(0.5)	<b>1845160150</b>

Supplied without protective hose



**Standard cable lengths**


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed to order other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Sheathing colour	Black
Sheath material	PUR
Rated current	4 A
Protection degree	IP 67
Core cross-section	0.5 mm <sup>2</sup>
Contact surface	tinned
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	24 V
Approvals	

L in the drawing is the cable length

**Dimensioned drawing**

**Design A****Male****Ordering data**

<b>Male straight - valve plug</b>	1.5 m
<b>Note</b>	


A
SAIL-VSA-M8G-3-1.5U
1099760150

**Standard cable lengths**


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed to order other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Sheathing colour	Black
Sheath material	PUR
Rated current	4 A
Protection degree	IP 67 (when screwed in)
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	tinned
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	24 V
Approvals	

**Dimensioned drawing**

## Design B/BD



Male

## Ordering data

## Male straight - valve plug

1.5 m  
1.5 m

## Male straight - valve plug 180°

1.5 m

## Note



BD	
Type	Order No.
SAIL-VSB-M8G-3-0.15U	1271590015

B	
Type	Order No.
SAIL-VSBD-M8G-3-1.5U	1099770150
SAIL-VSBD180-M8G-3-1.5U	1276450150




## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed to order other standard cable lengths.	1.5 m      xxxxxx0150
	3.0 m      xxxxxx0300
	5.0 m      xxxxxx0500
	10.0 m      xxxxxx1000

## Technical data

Sheathing colour	Black
Sheath material	PUR
Rated current	4 A
Protection degree	IP 67 (when screwed in)
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	tinned
Temperature range of housing	-25...+85 °C
Rated voltage	24 V
(acc. to VDE standard 0110 ISO group C)	
Approvals	

## Dimensioned drawing



**Design C/CD****Male****Ordering data****Male straight - valve plug**1.5 m  
1.5 m**Note**

Type	CD	C
SAIL-VSCD-M8G-3-1.5U	1916700150	1309680015


Type	Order No.
SAIL-VSC-M8G-0.15U	1309680015

**Standard cable lengths**

All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed to order other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Sheathing colour	Black
Sheath material	PUR
Rated current	4 A
Protection degree	IP 67 (when screwed in)
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	tinned
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	24 V
Approvals	

**Dimensioned drawing**

## Cables 3, 4, 5 poles

**B**

Weidmüller can provide the following types of cables for connecting sensors and actuators:

- The outer sheathing of the cables is made from polyurethane and the inner stranded wires have PVC insulation.
- They are available with 3, 4 and 5 poles.
- In addition, the cables are also available with PVC outer sheathing and PVC insulation internally.

### Ordering data

PUR halogen-free	Qty.	Order No.
SAIH-SLL-3x0.34mm <sup>2</sup> (PUR)	100 m	1902110000
SAIH-SLL-4x0.25mm <sup>2</sup> (PUR)	100 m	1902120000
SAIH-SLL-4x0.34mm <sup>2</sup> (PUR)	100 m	1902130000
SAIH-SLL-3x0.25mm <sup>2</sup> (PUR)	100 m	1902140000

### PVC

SAIH-SLL-3x0.34mm <sup>2</sup> (PVC)	100 m	1902160000
SAIH-SLL-4x0.25mm <sup>2</sup> (PVC)	100 m	1902170000
SAIH-SLL-4x0.34mm <sup>2</sup> (PVC)	100 m	1902180000
SAIH-SLL-3x0.25mm <sup>2</sup> (PVC)	100 m	1902190000

### Note

### Ordering data

PUR halogen-free yellow	Qty.	Order No.
SAIH-SLL-3x0.34mm <sup>2</sup> (UGE)	100 m	1345520000
SAIH-SLL-4x0.34mm <sup>2</sup> (UGE)	100 m	1345530000
SAIH-SLL-5x0.34mm <sup>2</sup> (UGE)	100 m	1345540000

### PUR halogen-free shielded

SAIH-SLL-3x0.34mm <sup>2</sup> (SI PUR)	100 m	1357320000
SAIH-SLL-4x0.34mm <sup>2</sup> (SI PUR)	100 m	1357330000
SAIH-SLL-5x0.34mm <sup>2</sup> (SI PUR)	100 m	1357340000

### Note

### Technical data

Colour	black
Cross-section	0.25 ... 0.34 mm <sup>2</sup>
Qty.	100 Metre

### Note

### Technical data

Colour	black, yellow
Cross-section	0.34 mm <sup>2</sup>
Qty.	100 Metre

### Note

## Bus cables



Owing to their easy assembly and adaptability, Weidmüller distributors have become very popular among machine manufacturers. For such applications, Weidmüller can supply corresponding bus cables for custom assembly.

The bus cables are available in three different versions. All bus cables are suitable for moving cable carriers and are available by the metre. All three trunk cables can be ordered in individual lengths. A typical order quantity is a 500 metre drum. The colour coding of wires conforms to the standard in mechanical engineering.

The connection hoods of the M12 SAI distributors are always fitted with the same terminals so that only one type of cable is required.

### Advantages of bus cables supplied by the metre:

- Special lengths for bus cables
- No cable waste
- No storage space required for different cable lengths
- Bulk stock will be cut to desired length.

### Ordering data

Type	Qty.	Order No.
SAIH-SLL 3 x 0.75 – 16 x 0.34	1 m	9457560000
SAIH-SLL 5 x 0.75 – 16 x 0.34	1 m	9457970000
SAIH-SLL 3 x 0.75 – 8 x 0.34	1 m	9457420000
SAIH-SLL 3 x 1.0 – 16 x 0.5	1 m	1344720000



# M8, M12 Fieldbus, data cables and accessories

<b>M8, M12 Fieldbus, data cables and accessories</b>	
Introduction	C.2
Fieldbus distributor - Overview	C.4
PROFIBUS-DP - cables	C.6
PROFIBUS-DP - connectors (M12, Sub-D)	C.11
PROFIBUS-DP - FBCon T-distributor	C.22
PROFIBUS-PA - cables	C.26
PROFIBUS PA - connectors	C.31
PROFIBUS-PA - FBCon T-distributor	C.34
PROFIBUS-PA - FBCon T-distributor with surge protection	C.40
PROFIBUS-PA - FBCon T-distributor ATEX Ex(ia)	C.50
AS-Interface Line	C.58
ASI - Cables	C.60
ASI - T-piece	C.61
CANopen & DeviceNet™ - cables (M12, M8)	C.62
CANopen & DeviceNet™ - connectors	C.67
EtherCat - connectors (M8)	C.68
Ethernet cables	C.69
Ethernet plug-in connector	C.77
FOUNDATION Fieldbus - connector (7/8")	C.80
Accessories cable glands	C.81

## Bus cables

The bus system lies at the heart of automation engineering. High quality products are essential here, if you hope to achieve long term, smooth functionality. It's not only the slaves and controllers that play a significant role; the type of cables and connection mechanisms in use are also very important. Weidmüller bus cables are the ideal solution. The products, which we manufacture ourselves, (used, for example, in the Profibus, Industrial Ethernet and CANopen/DeviceNet™ sectors) have a 360 degree shielding

within the moulding. This provides effective protection for signal and data transmission.

Delivery times are another decisive factor. Our special production strategy allows us to quickly manufacture parts that are customised to a specific order. We have a dedicated department that is focussed on this strategy and which is located close to the Detmold central warehouse in order to keep delivery times to a minimum.



Bus cables: shown here in the standard colours:  
blue (Profibus-PA Ex i), black (CANopen/DeviceNet or Profibus-PA), magenta (Profibus-DP) and green (Industrial Ethernet) together with the sensor cables

	<b>Cables</b>
	<b>M12 plug-in connector</b>
	<b>Sub-D connector</b>
	<b>FBCon T-distributor</b>

# System description, fieldbus components


FBCon fieldbus distributors are available in industrial and Ex(ia) versions. They are used for coupling 1-8 field devices devices or sensors.

The connection is made via a spur. The spur is connected by an M12 plug in connector or directly via an EMC cable gland. The communication and device powering is handled by a common 2-core wire.

The distributors offer the following features irrespective of the version:

- Tension clamp connection technology
- Surge protection for the main line
- Current limiter for each stub line
- EMC cable gland
- M12 plug in connectors
- External earth stud
- Interruption-free bus operation
- Industrial specification
- Bus termination integrated (non EX)
- ATEX version
- Pressure equalising element
- IP 65, IP 66, IP 67 Ingress protection class
- Stainless steel versions
- PROFIBUS-PA compatible

## Typical PROFIBUS system layout



## Product coding

The FBCon family of distributors includes various forms. The product name indicates the respective features as follows:

FBCon	Field Bus Connection
PA	PROFIBUS-PA Process Automation
DP	PROFIBUS-DP Decentralised Periphery
SS	Stainless Steel
CG	Stainless steel cable gland on stainless steel housing. On standard aluminium housings, the cable gland is nickel-plated brass.
PCG	Plastic Cable Gland
CG/M12	M12 plug-in connector for the stub cables and cable gland for the trunk cable
1way	Number of outgoing stub lines
Limiter	Current limiter: protects the PROFIBUS-PA network in the event of an overload in the stub line
OVP	Surge protection: protects the system in the event of a voltage surge
EX	Approved for potentially explosive areas
ATEX	For explosive atmospheres

The standard distributors are grey. The Ex approved distributors are painted blue.

PROFIBUS-PA distributors are generally equipped with a switch in terminating resistor. In potentially explosive areas, the terminating resistor is manufactured with a separate box. This must be used instead of the right-hand cable gland. In the case of PROFIBUS-DP, an additional external 24 V DC power supply is required. This makes the terminator independent of the last station in the network.



FBCon PA CG/M12 1way Limiter




FBCon SS PCG 1way



FBCon PA CG 1way Ex


## PROFIBUS-DP cables

one end without connector



Male

Female



## Ordering data

## Male, straight

PUR halogen-free	1.5 m
PVC/PVC	1.5 m

## Male, angled

PUR halogen-free	1.5 m
PVC/PVC	1.5 m

## Female, straight

PUR halogen-free	1.5 m
PVC/PVC	1.5 m


## Female, angled

PUR halogen-free	1.5 m
PVC/PVC	1.5 m

## Note

Other versions on request

Type	Order No.
SAIL-M12G-PB-1.5D	1873300150
SAIL-M12G-PB-1.5E	1058530150
SAIL-M12W-PB-1.5D	1061970150
SAIL-M12W-PB-1.5E	1062340150
SAIL-M12BG-PB-1.5D	1873320150
SAIL-M12BG-PB-1.5E	1058540150
SAIL-M12BW-PB-1.5D	1062300150
SAIL-M12BW-PB-1.5E	1062370150



## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000



## Technical data

Sheathing colour	violet
Protection degree	IP 67
Wire cross section	PUR 0.24 mm <sup>2</sup> / PVC 0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C

Chapter W includes additional technical specifications for the cable

## Dimensioned drawing



**PROFIBUS-DP cables****Connecting cables****Ordering data****Male, straight - Female, straight**

PUR halogen-free	1.5 m
PVC/PVC	1.5 m

**Male, straight - Female, angled**


PUR halogen-free	1.5 m
PVC/PVC	1.5 m

**Male, angled - Female, angled**

PUR halogen-free	1.5 m
PVC/PVC	1.5 m

**Note****2-pole****Type** **Order No.**SAIL-M12GM12G-PB-1.5D **1873310150**SAIL-M12GM12G-PB-1.5E **1058570150**SAIL-M12GM12W-PB-1.5D **1062310150**SAIL-M12GM12W-PB-1.5E **1062380150**SAIL-M12WM12W-PB-1.5D **1062330150**SAIL-M12WM12W-PB-1.5E **1062400150**

Other versions on request


**Standard cable lengths**


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**


Sheathing colour	violet
Protection degree	IP 67
Wire cross section	PUR 0.24 mm <sup>2</sup> / PVC 0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C

Chapter W includes additional technical specifications for the cable

**Dimensioned drawing**



## PROFIBUS-DP bulk lengths



## Technical data

## Assembly

Wire

Conductor: 19-wire strands copper shiny, AWG 24,  
0.64 mm Ø nominal

Pair

Insulation: PE foam, 2.55 mm Ø nominal  
2 wires according to 3.2.1 (red, green) laid as a pair,  
5.1 mm Ø nominalInterior sheathing  
ShieldCoil-filling interior sheathing, 5.3 mm Ø nominal  
a) Overlapping aluminium film, 6.1 mm Ø nominal  
b) Braided tin-plated copper, coverage approx. 65%, 6.1 Ø nominal

Outer cladding

TPE-U free from halogens, 8.0 +/- 0.4 mm

## Electrical characteristics at 20 °C

Conductor resistance

&lt; 84.0 Ω/km

Insulation resistance

&gt; 1 GΩ ● km

Operational capacity

&lt; 35 nF/km

Characteristic impedance

9.6 KHz (RW) 300 Ω

38.4 KHz (RW) 185 +/- 20 Ω

3-20 Mhz 150 +/- 15 Ω

Attenuation

9.6 KHz 3 dB/km

38.4 KHz 5 dB/km

4 Mhz 26 dB/km

16 Mhz 55 dB/km

Test voltage (50 Hz, 1 min.)

Wire/wire 0.5 kV<sub>eff</sub>

Halogen-free

Wire/shield 0.5 kV<sub>eff</sub>

## Mechanical and thermal characteristics

Temperature range

Stationary -40 °C to +70 °C

Moving -20 °C to +60 °C

Min. permitted bending radius

Once 7.5 x d

Max. tensile load resistance

Multiple 15 x d

Suitable for dragline cable carriers

Static 50 N/mm<sup>2</sup>

Halogen-free

Dynamic 20 N/mm<sup>2</sup>

Yes

Yes



## Note

## Ordering data

Metre goods

Type  
SAIH-PB-2X0.24-PUROrder No.  
1232620000

## Note

**PROFIBUS-DP bulk lengths****Technical data****Assembly**

Wire

Conductor: copper wire, without insulation, AWG 22,  
0.64 mm Ø nominal

Pair

Insulation: PE foam, 2.55 mm Ø nominal  
2 wires according to 4.1 (red, green) to pair stranded,  
5.1 mm Ø nominalInterior sheathing  
ShieldPlastic foil, 5.2 mm Ø nominal  
a) AL foil, 5.4 mm Ø nominal  
b) Braiding tin-plated copper, coverage approx. 60 %, 6.0 mm Ø nominal

Outer cladding

PVC YM, 7.8 +/- 0.2 mm Ø nominal

**Electrical characteristics at 20 °C**

Conductor resistance

&lt; 55 Ω/km

Insulation resistance

&gt; 1 GΩ ● km

Operational capacity

30 pF/m nominal

Characteristic impedance

9.6 KHz (RW) 270 Ω

Attenuation

38.4 KHz (RW) 185 Ω

3-20 Mhz 150 +/- 15 Ω

9.6 KHz 2.2 dB/km

38.4 KHz 3.4 dB/km

100 KHz 4.5 dB/km

1 Mhz 11.5 dB/km

3 Mhz 18.2 dB/km

10 Mhz 33.2 dB/km

20 Mhz 48.0 dB/km

Test voltage (50 Hz, 1 min.)

Wire/wire 1.5 kV<sub>eff</sub>**Mechanical and thermal characteristics**

Temperature range

Stationary -40 °C to +70 °C

Min. permitted bending radius

Moving -20 °C to +70 °C

Max. tensile load resistance

Once 9 x d

Suitable for dragline cable carriers

Multiple 18 x d

Halogen-free

Static 50 N/mm<sup>2</sup>Dynamic 20 N/mm<sup>2</sup>

No

No


**Note****Ordering data**

Metre goods

Type SAIH-PB-2X0.34-PVC

Order No.  
1933640000**Note**

Mounts behind wall PROFIBUS DP  
B-coded, shielded




Male

Female


### M12 built-in connector

Male, straight



### M12 built-in connector

Female, straight



### Technical data

Cable gland
Housing base material
Contact socket diameter
Core cross-section
Rated current
Rated voltage
Temperature range of housing
Protection degree
Contact surface
Sheath material
Tightening torque

PG9, Mounts behind wall

Zinc diecast, nickel-plated

M12

0.25 mm<sup>2</sup>

4 A

250 V

-20...+60 °C

IP 68 (when screwed in)

gold-plated

PUR halogen-free

1 Nm (to housing)

PG9, Mounts behind wall

Zinc diecast, nickel-plated

M12

0.25 mm<sup>2</sup>

4 A

250 V

-20...+60 °C

IP 68 (when screwed in)

gold-plated

PUR halogen-free

1 Nm (to housing)

### Note

### Ordering data

PUR halogen-free	0.5 m
PUR halogen-free	1 m
PUR halogen-free	2 m
PUR halogen-free	5 m


### Note

### 2-pole

Type	Order No.
SAIE-M12S-PB-0.5U HW	1279490050
SAIE-M12S-PB-1.0U HW	1279490100
SAIE-M12S-PB-2.0U HW	1279490200
SAIE-M12S-PB-5.0U HW	1279490300

Other versions / Lengths on request

### Dimensioned drawing




Hexagon nut enclosed loose

### 2-pole

Type	Order No.
SAIE-M12B-PB-0.5U HW	1279480050
SAIE-M12B-PB-1.0U HW	1279480100
SAIE-M12B-PB-2.0U HW	1279480200
SAIE-M12B-PB-5.0U HW	1279480300

Other versions / Lengths on request

### Dimensioned drawing



Hexagon nut enclosed loose

**Tension clamp connection M12, stainless steel**  
**B-coded**

SAIS / SAIB VA

straight

**Ordering data**


<b>Male</b>	5-pole, PG 9
<b>Socket</b>	5-pole, PG 9
<b>Note</b>	

Type	QTY	Order No.
SAIS 5/9-VA-B-COD	1	1920720000
SAIB 5/9-VA-B-COD	1	1920730000

**Technical data**

Type of connection	Tension clamp connection
Housing main material	1.4404/316L
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 69K
Contact surface	Gold-plated
<b>Note</b>	PB = PROFIBUS (B-COD)Torque, see E.12

Type of connection	Tension clamp connection
Housing main material	1.4404/316L
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 69K
Contact surface	Gold-plated
<b>Note</b>	PB = PROFIBUS (B-COD)Torque, see E.12

**Dimensioned drawing**

PB = PROFIBUS (B-COD)Torque, see E.12

Screw connection M12, metal (EMC)  
B-coded



## Industrial Ethernet

C

### Ordering data

<b>Male</b>	5-pole, PG 9
<b>Socket</b>	5-pole, PG 9
<b>Note</b>	

### Technical data

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

### SAISM / SAIBM

straight



### SAISW / SAIBW

Angled




Type	Qty.	Order No.
SAISM 5/8S M12 5P B-COD	1	1784790000
SAIBM 5/8S M12 5P B-COD	1	1784780000

Type	Qty.	Order No.
SAISW-M-5/8 M12 B-COD	1	1944570000
SAIBW-M-5/8 M12 B-COD	1	1944580000


Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

### Dimensioned drawing



### Dimensioned drawing



Torque, see E.12

**IDC connection**  
B-coded



## Industrial Ethernet

### SAIS / SAIB

straight



### Ordering data

Male	3-pole, PG 9
Socket	3-pole, PG 9
Note	


Type	Qty.	Order No.
SAIS-3-IDC-M12B-COD	1	1864730000
SAIB-3-IDC-M12B-COD	1	1864740000

### Technical data

Type of connection	Insulation displacement connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	7...8.8 mm
Wire cross-section, min. / max.	0.34...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	32 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	tinned
Note	PB = PROFIBUS (B-COD) IE = Industrial Ethernet (D-COD)

Type of connection	Insulation displacement connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	7...8.8 mm
Wire cross-section, min. / max.	0.34...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	32 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	tinned
Note	PB = PROFIBUS (B-COD) IE = Industrial Ethernet (D-COD)

### Dimensioned drawing



PB = PROFIBUS (B-COD)  
IE = Industrial Ethernet (D-COD)

# Sub-D




This compact connector provides a convenient bus connection for all standardised PROFIBUS-DP devices. A data transmission rate of max. 12 Mbps is possible. An additional Sub-D connector on top of the plug enables analysis/programming devices to be connected without modifying the wiring.

The 9-pin sub-D connector is available in four versions:

1. without terminating resistor
  2. with built-in terminating resistor
  3. with switch in terminating resistor and connection for programming unit via IDC connection
  4. with switch in terminating resistor and connection for programming unit via tension clamp connection.
- T-piece functions
  - Good shield contact
  - Ample space for connecting the bus cable
  - Cable entry can be closed off with blanking panel
  - Fully insulated housing
  - Reliable strain relief



PB-DP SUB-D



## Technical data

Data transmission rate	max. 12 Mbps	
ESD	protection to IEC 801-2	
Operating temperature	°C	0 ... 60
Storage temperature	°C	-25 ... +80
Ingress protection class	IP 40	
Dimensions (LxWxH)	mm	64.6 x 47.5 x 16
Housing material	PC UL 94 V-1	
Plug-in connector	sub-D 9-pin	
Cable connection	2 No. horizontal	
Cable diameter mm	mm	4.5 ... 8
Single conductor cross-section	mm <sup>2</sup>	rigid max. 1.5 flexible max. 1.0
Type of connection	Screw IDC Tension clamp	8395500000 and 8460860000 1916980000 1934200000

## Note


## Ordering data

Type	Qty.	Order No.
PB-DP SUB-D	1	8395500000




# Sub-D

PB-DP SUB-D TERM



PB-DP SUB-D IDC/ZF TERM PS



## Ordering data

Type	Qty.	Order No.
PB-DP SUB-D TERM	1	8460860000

## Ordering data

Type	Qty.	Order No.
PB-DP SUB-D IDC TERM PS	1	1919680000
PB-DP SUB-D ZF TERM PS	1	1934200000

**PROFIBUS Sub-D connector with M12 (90°)**


Weidmüller's new Sub-D product line features fully shielded connector variants that enable direct tapping with M12 cables. This allows you to avoid the types or errors that often occur when installing similar connectors with screw connections. The increased contact reliability of the Sub-D connectors more than compensates for the cost of the extra M12 connectors.

**C Special features:**

- Complete shielded housing
- Compact housing for small places
- Connection without any mistakes because of the M12 connector
- 100 % certified components

**PB-DP SUB-D M12 TERM**

PROFIBUS-Connector 90° M12 with switch, without programming connector

**Technical data**


Data rate	acc. to PROFIBUS Specification, 12 Mbit/s
Connector pinning	acc. to PROFIBUS Specification
PROFIBUS DP connector	D-Sub 9-pole, male
PROFIBUS DP program connector	D-Sub 9-pole, female
PROFIBUS cable connector	M12 B coded, male + female, Pin 2 and 4, connected, Cable output: M12 female, Cable entry: M12 male
Mechanical lifetime	200 connections
Temperature range	-20 °C to +70 °C
Permissible humidity	Max. 75 % at +25 °C, non-condensing
Ingress protection class	IP 30
Housing material	ZnAl
D-Sub screw connection	UNC 4-40

**Note****Ordering data**

Type	Qty.	Order No.
PB-DP SUB-D M12 TERM	1	1140650000

**PROFIBUS Sub-D connector with M12 (90°)****PB-DP SUB-D M12 TERM PS**

PROFIBUS-Connector 90° M12 with switch, with programming connector

**C****Ordering data**

Type	Qty.	Order No.
PB-DP SUB-D M12 TERM PS	1	1140640000

**PROFIBUS-DP - connectors (M12, Sub-D)****PROFIBUS Sub-D Connector with tension clamp connection (35°)**


The new Sub-D Family from Weidmüller offers a fully shielded version.

**Special features:**

- Completely shielded housing
- Compact design for use in small spaces

**C****PB-DP SUB-D ZF35TERM**

PROFIBUS-Connector 35° with switch, without programming connector

**Technical data**

Data rate	acc. to PROFIBUS Specification, 12 Mbit/s
Connector pinning	acc. to PROFIBUS Specification
PROFIBUS DP connector	D-Sub 9-pole, male
PROFIBUS DP program connector	D-Sub 9-pole, female
PROFIBUS cable connector	Tension clamp
Mechanical lifetime	200 mating cycles
Temperature range	-20 °C to +70 °C
Permissible humidity	Max. 75 % at +25 °C, non-condensing
Ingress protection class	IP 30
Housing material	ZnAl
D-Sub screw connection	UNC 4-40


**Ordering data**

Type	Qty.	Order No.
PB-DP SUB-D ZF35TERM	1	1173220000

**Note**

**PROFIBUS Sub-D Connector with tension clamp connection (35°)****PB-DP SUB-D ZF35TERM PS**

PROFIBUS-Connector 35° with switch, with programming connector

**Ordering data**

Type	Qty.	Order No.
PB-DP SUB-D ZF35TERM PS	1	1173240000

**PROFIBUS Sub-D Connector with tension clamp connection (90°)**

The new Sub-D Family from Weidmüller offers a fully shielded Version.


**Special features:**

- Completely shielded housing
- Compact design for use in small spaces

C

**PB-DP SUB-D ZF**

PROFIBUS-Connector 90° without switch, without programming connector

**Technical data**

Data rate	acc. to PROFIBUS Specification, 12 Mbit/s
Connector pinning	acc. to PROFIBUS Specification
PROFIBUS DP connector	D-Sub 9-pole, male
PROFIBUS DP program connector	D-Sub 9-pole, female
PROFIBUS cable connector	Tension clamp
Mechanical lifetime	200 mating cycles
Temperature range	-20 °C to +70 °C
Permissible humidity	Max. 75 % at +25 °C, non-condensing
Ingress protection class	IP 30
Housing material	ZnAl
D-Sub screw connection	UNC 4-40


**Ordering data**

Type	Qty.	Order No.
PB-DP SUB-D ZF	1	1161890000

**Note**

**PROFIBUS Sub-D Connector with tension clamp connection (90°)****PB-DP SUB-D ZF TERM**


PROFIBUS-Connector 90° with switch, without programming connector

**Ordering data**

Type	Qty.	Order No.
PB-DP SUB-D ZF TERM	1	1161870000


**PB-DP SUB-D ZF TERM PS**

PROFIBUS-Connector 90° with switch, with programming connector

**Ordering data**

Type	Qty.	Order No.
PB-DP SUB-D ZF TERM PS	1	1161880000

# PROFIBUS-DP distributors



## PROFIBUS-DP

### Technical data

Operating temperature	-25 °C to 55 °C
Ingress protection class	IP 66
Enclosure material	High grade aluminium alloy (AL - SI 12)
Finish	Painted RAL 7001
PROFIBUS-DP connection	Tension clamp terminals 0.5 – 1.5 mm <sup>2</sup>
Cable entry	Cable gland M16
Cable gland clamping range	5.5 – 9.5 mm
Contact surface	M12 plug/socket CuZnAu
Transmission rate	Max. 1.5 MBaud
Power supply bus connection	Bus terminator 24 VDC +/-10 %
Trunk cable via cable gland	


### Installation advice

Torques	
M16 cable gland at enclosure	6.0 Nm
Union nut, M16 cable gland	4.0 Nm
Enclosure cover	1.8 – 2.0 N
External earthing cable	1.8 – 2.0 Nm
Adaptor/stud cable	0.5 Nm

### Pin assignment

Pin no.	Connection	Wire colour
Pin 1	unassigned	
Pin 2	RxDx/TxD-N / A-wire	green
Pin 3	unassigned	
Pin 4	RxDx/TxD-N / B-wire	red
Pin 5	shield	
Cable gland	shield	

### Socket B-coded



### PROFIBUS-DP distributor

The PROFIBUS-DP topology is a line structure. The spur (T-distributor) connects the individual field devices or remote I/Os to the bus cable. The length of the spur cable depends on the transmission rate and should be as short as possible. The total of all spur lengths for transmission rates up to 1.5 MBaud may not exceed max. 6.6 m. The trunk cable passes through an EMC cable gland into an aluminium or stainless steel enclosure where it is connected to a tension clamp terminal. The spur line to the device is connected using a B-coded M12 socket or an EMC cable gland. Terminating resistors must be wired onto the start and end of the PROFIBUS-DP network. The Terminator modules can take care of this task. The electrically isolated 24 V DC power supply for the bus terminator is routed into the cable gland on the right side. The housing features a pressure-compensation mechanism that counters the effects of climatic fluctuations. The guidelines issued by the PROFIBUS user organisation must be observed.

**1-channel distributor**



Cable gland

**Ordering data**


Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn DP CG 1way	branch line CG	1	<b>8564340000</b>

Type	Cable gland	QTY	Order No.
<b>Stainless steel enclosure</b>			
FBCOn SS DP PCG 1way	all connections PCG	1	<b>8714260000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****1-channel distributor**



M12 connection

**Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn DP M12 1way	branch line M12	1	<b>8564350000</b>

Type	Cable gland	QTY	Order No.
<b>Stainless steel enclosure</b>			
FBCOn SS DP M12 1way	branch line M12	1	<b>8714270000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**

**Terminator**

Cable gland

**Terminator**



M12 connection

**C****Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon DP CG Term 24V	branch line CG	1	<b>8564290000</b>



Type	Cable gland	QTY	Order No.
<b>Stainless steel enclosure</b>			
FBCon SS DP PCG Term 24V	all connections PCG	1	<b>8714240000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon DP M12 Term 24V	branch line M12	1	<b>8564330000</b>

Type	Cable gland	QTY	Order No.
<b>Stainless steel enclosure</b>			
FBCon SS DP M12 Term 24V	branch line M12	1	<b>8714250000</b>


**Dimensioned drawing****Wiring diagram**




# PROFIBUS-DP IP 20 T-distributor



## RS PB-DP T



## RS PB-DP T SUB-D



The distributor for PROFIBUS-DP enables the user to connect it conveniently in the electrical cabinet. It can be mounted on TS 32/35 rails and used to connect standardised PROFIBUS-DP lines. Spur cables can also be connected. Please note that spur cables should be kept as short as possible. Part No. 8788580000 has a 9-pin Sub-D socket for connecting analysis/programming devices.

- T-piece functions
- Good shield contact
- Ample space for connecting the bus cable
- TS 32/35 terminal rail mounting
- Standardised Sub-D connection for PROFIBUS-DP

## Technical data

Data transmission rate	max. 1.5 Mbps (with max. 6.6 m spur line) max. 12 Mbps (no spur lines)
Operating temperature	°C 0 ... 55
Storage temperature	°C -25 ... +70
Ingress protection class	IP 20
Dimensions (LxWxH)	mm 70 x 45 x 42
Plug-in connector	sub-D 9-pin
Cable diameter	mm 4.5 ... 8
Single conductor cross-section	mm <sup>2</sup> 0.5 ... 2.5
Type of connection	screw

## Note

## Ordering data

Type	Qty.	Order No.
RS PB-DP T	1	8800040000
RS PB-DP T SUB-D	1	8788580000

The **PROFIBUS-PA** is an open fieldbus standard (EN 50170, IEC 1158-2, DIN 19245). It was specifically designed for the requirements of process engineering, such as remote powering and intrinsic safety. The PROFIBUS-PA enables operation of several PA sensors and actuators on one bus line.

The devices are powered using twin cable technology, and the transmission of process data is digital.

Integration in the PROFIBUS-DP network is done by means of a segment coupler.



Specific advantages of PROFIBUS-PA:

- Low wiring costs
- Minimal planning costs for the process control system
- Remote interrogation or programming of the field device
- Further development and support by the PROFIBUS User Organisation

Whether for servicing or system modification, the PROFIBUS-PA FB connectors from Weidmüller enable connection or replacement of field devices without interrupting the bus system.

An extensive range of accessories, such as pre-assembled cables are also available.





**PROFIBUS-PA cables**





**PROFIBUS-PA connectors**



**Profibus PA distributors**

## PROFIBUS-PA cables

One end without connector



## Ordering data

Male, straight	
PVC blue	1.0 m
PVC black	1.0 m
Male, angled	
PVC blue	1.0 m
PVC black	1.0 m
Female, straight	
PVC blue	1.0 m
PVC black	1.0 m
Female, angled	
PVC blue	1.0 m
PVC black	1.0 m
Note	

Type	Order No.
FBC EX PA M12 M 1M	1785150100
FBC PA M12 M 1M	1785120100
FBC EX PA M12 MA 1M	1076580100
FBC PA M12 MA 1M	1076540100
FBC EX PA M12 FM 1M	1785140100
FBC PA M12 FM 1M	1785110100
FBC EX PA M12 FMA 1M	1076520100
FBC PA M12 FMA 1M	1076530100

## Wall bushing



## Ordering data

Type	Length	Qty.	Order No.
SAI-WDF-5P M12 60 mm	60 mm	1	1819450000

## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.0 m	xxxxxx0100
	2.0 m	xxxxxx0200
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

## Technical data

Sheathing colour	blue (RAL 5015)
Protection degree	IP 67
Core cross-section	1 mm <sup>2</sup>
Contact surface	gold-plated
Temperature range of housing	-25...+85 °C



Chapter W includes additional technical specifications for the cable

## Dimensioned drawing



## PROFIBUS-PAcables

### Connecting line



#### Ordering data

##### Male, straight - Female, straight

PVC blue	1.0 m
PVC black	1.0 m

##### Male, straight - Female, angled

PVC blue	1.0 m
PVC black	1.0 m

##### Male, angled - Female, angled

PVC blue	1.0 m
PVC black	1.0 m

##### Male, angled - female, straight

PVC blue	1.0 m
PVC black	1.0 m

##### Note

#### Type Order No.

FBCEX PA M12 M-FM 1M 1785130100

FBC PA M12 M-FM 1M 1785100100

FBCEX PA M12 M-FMA 1M 1075390100

FBC PA M12 M-FMA 1M 1075620100

FBCEX PA M12 MA-FMA 1M 1075410100

FBC PA M12 MA-FMA 1M 1076550100

FBCEX PA M12 MA-FM 1M 1075450100

FBC PA M12 MA-FM 1M 1075460100

#### Wall bushing



#### Ordering data

Type	Length	Qty.	Order No.
SAI-WDF-5P M12 60 mm	60 mm	1	1819450000

#### Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.0 m	xxxxxx0100
	2.0 m	xxxxxx0200
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000


#### Technical data

Sheathing colour	blue (RAL 5015)
Protection degree	IP 67
Core cross-section	1 mm <sup>2</sup>
Contact surface	gold-plated
Temperature range of housing	-25...+85 °C

Chapter W includes additional technical specifications for the cable

#### Dimensioned drawing



**PROFIBUS-PA bulk lengths****Technical data****PROFIBUS-PA bulk lengths**

Application

- Fieldbus cable for PROFIBUS-PA field networks in accordance with IEC 1158-2

- The cable is suitable for installation in both dry and humid spaces. When used with the black, UV-resistant cladding, it can also be installed outdoors.

General characteristics

None of the materials used for the cables during production are detrimental to paint adhesion (**they are LBS-free**).

**LBS** = Materials detrimental to paint adhesion

**Assembly**

Conductor

Copper wire, without insulation, 1.0 mm<sup>2</sup>, finely stranded

Insulating sleeve

Foam skin (02YS), wire Ø approx. 2.55 mm

Stranding

Wire colours: red and green

Wrapping

2 wires with 2 drain wires approx. 1.0 mm Ø stranded

Shield

1 layer insulation foil

Outer cladding

Braiding made from tin-plated copper wire,

Coverage 85 % ± 5

PVC, blue RAL 5015 or black

Outer diameter: 8.0 mm ± 0.4

**Electrical characteristics at 20 °C**

Wire resistance (loop)

max. 44 Ω/km

Insulation resistance

min. 5 GΩ x km

Working capacity at 800 Hz

nom. 52 nF/km

Inductance at 800 Hz

approx. 0.4 mH/km

Characteristic impedance

at 31.25 kHz

100 Ω ± 20 %

Wave attenuation

at ≥ 1 MHz

nom. 80 Ω

at 39 kHz

max. 0.3 dB/100 m

at 100 kHz

nom. 0.35 dB/100 m

at 1 MHz

nom. 1.2 dB/100 m

nom. 79 %

max. 250 mΩ/m

Peak value 100 V

Test voltage

U<sub>eff.</sub> 1500 V

U<sub>eff.</sub> 1500 V

**Mechanical and thermal characteristics**

Min. bending radius stationary installed / during installation

65 mm

Temperature range during installation

-5 °C to +60 °C

Temperature range stationary installed

-30 °C to +80 °C

Flammability

Flame retardant in accordance with VDE 0482,  
part 265-2-1 / IEC 60 332-1

**Note****Ordering data**

Type	Order No.
SAIH-PB-PA-2X1.0-PVC-BL	1232630000
SAIH-PB-PA-2X1.0-PVC-SW	1232640000

**Note**

**Tension clamp connection M12, stainless steel**  
**A-coded**

SAIS / SAIB VA

straight

**Ordering data**


<b>Male</b>	5-pole, PG 9
<b>Socket</b>	5-pole, PG 9
<b>Note</b>	

Type	QTY	Order No.
SAIS 5/9-VA	1	1920700000
SAIB 5/9-VA	1	1920710000

**Technical data**

Type of connection	Tension clamp connection
Housing main material	1.4404/316L
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 69K
Contact surface	Gold-plated
<b>Note</b>	PB = PROFIBUS (B-COD)Torque, see E.12

Type of connection	Tension clamp connection
Housing main material	1.4404/316L
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 69K
Contact surface	Gold-plated
<b>Note</b>	PB = PROFIBUS (B-COD)Torque, see E.12

**Dimensioned drawing**

PB = PROFIBUS (B-COD)Torque, see E.12

**M12 screw connection, metal (shielded)**  
**A-coded**

**FBCOn / SAIS**

straight

**SAISW / SAIBW**

Angled

**Ordering data**

Male	Type	Qty.	Order No.
	FBCOn M12 4P M EMC	1	9455640000
	SAIS-M-5/8S M12 5P A-COD	1	1784740000

Socket	Type	Qty.	Order No.
	FBCOn M12 4P FM EMC	1	8426220000
	SAIB-5/6S M12 5P A-COD	1	1191020000
	SAIB-M-5/8S M12 5P A-COD	1	1784750000

**Note**

Type	Qty.	Order No.
SAISW-M-4/8 M12	1	1803930000
SAISW-M-5/8 M12	1	1803940000
SAIBW-M-4/8 M12	1	1803910000

Type	Qty.	Order No.
SAIBW-M-5/8 M12	1	1803920000
Other versions on request		

**Technical data**



Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	4...6 mm (PG7) / 6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated

**Note**

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated

Torque, see E.12

**Dimensioned drawing****Dimensioned drawing**

**Positioning plug connector****Positioning plug connector****Technical data**

No. of poles	4
Version	pin
Temperature range	-40 °C ... 85 °C
Housing material	stainless steel (VA)
Connection thread	PG 9
Plug thread	M12
Strand cross-section	0.34 mm <sup>2</sup>
Housing class of protection to DIN 40050 IEC 529	IP 67
Strand length (fitted with wire-end ferrules)	500 mm
Nominal current per contact	4 A
Rated voltage	250 V
Contact surface	gold-plated
Type of connection	screw
Flammability class to UL-94	
Nominal voltage to VDE standard 0110/ISO Group C	
Resistance to creepage	
Contact resistance to IEC 512 Part 2	
Insulation resistance to IEC 512 Part 2	



**Note****Ordering data**

Positioning plug connector PG9 500 mm
Adapter PG9 / M20
Positioning plug connector PG 13.5 150 mm
Positioning plug connector PG 13.5 300 mm
Positioning plug connector M 20 150 mm
Positioning plug connector M 20 300 mm
Positioning plug connector M 20 300 mm B-coded

**Note**

Type	Qty.	Order No.
SAIE-M12S-4-0.5U-AEH-VA	1	1861220001
SAIE-EW-M20/PG9-SW24-VA	1	1950270000

Type	Qty.	Order No.
POS-4P M12 PG13.5 150mm	1	9455650000
POS-4P M12 PG13.5 300 mm	1	8425910000
POS-4P M12 M20 150mm	1	8425930000
POS-4P M12 M20 300mm	1	8425940000
POS-5P M12/M20 300MM	1	1795500000

**Dimensioned drawing****Dimensioned drawing****Fitting information**

Torque settings	
Set screw	1.8 - 2.0 Nm
Knurled ring	hand-tight
Lock-nut	6.25 Nm
If the device is exposed to vibration, we recommend using a stub cable to isolate the device from the vibration.	

## FBCon distributors for the industrial market



### **PROFIBUS-PA T-connector**

- for industrial applications
- standard

The **PROFIBUS-PA** installation products are increasingly used in the:

- food and beverage industry
- process industries and
- chemical industry

The product range offers a wide choice of customer solutions for use in harsh conditions. This includes standard and EX versions of single and multi-way design with M12 plug-in connection or cable glands. Weidmüller offers a solution for almost every application. If you cannot find your solution here, please contact the branch / sales office responsible for you.

### **PROFIBUS-PA T-connector**

#### **standard**

- 1, 2, 4, 8-way with EMC cable gland
- Industrial + EX / ATEX
- Optional surge protectio

The **PROFIBUS-PA T-connector** is intended for direct coupling of measuring devices, sensors, actuators, etc.

- IP 66 Ingress protection class
- Modular design
- Uninterruptible bus operation for service situations
- Simple handling
- Low installation costs
- External earth stud
- Pressure equalising element
- EMC cable gland



# FBCon Fieldbus distributor

## PROFIBUS-PA Fieldbus distributor: robust and well-tested

FBCon fieldbus distributors are available in industrial and Ex(ia) versions. They are used for coupling 1-8 field devices or sensors. The connection is made via a spur. The spur is connected by an M12 plug-in connector or directly via an EMC cable gland.

The communication and device powering is handled by a common 2-core wire.

The PROFIBUS-PA distributors normally feature a switchable terminating resistor. For the Ex zone, the terminating resistor is made with a separate box. Current limiting variants help to ensure that the facility can operate smoothly.

Weidmüller offers a comprehensive line of accessories including pre-assembled PROFIBUS-PA cables in the standard lengths, and plug in connectors for a wide variety of applications.


- Fieldbus distributor for PROFIBUS-PA and PROFIBUS-DP
- Standard distributor for use in the safe zone
- Aluminium housing for connecting from 1 to 8 field devices
- Stainless steel distributor for applications in the food processing industry, for connecting from 1 to 8 field devices
- Intrinsically safe (ia) Ex version in aluminium housing for connecting from 1 to 8 field devices
- EMC cable gland for a secure contact with the shielding

## Technical data for PROFIBUS-PA standard distributors

Temperature range	
Operating temperature	from -40 °C to 85 °C
Ingress protection class	IP 66
Housing material	High-quality aluminium alloy (AL-Si 12)
Surface	Stove-enamelled RAL 7001
PROFIBUS-PA connection	Tension clamp connection 0.5 - 1.5 mm <sup>2</sup>
Cable entry	Cable gland M16
Clamping range	5.5 - 9.5 mm
Measuring device connector M12 x 14-pin	Contacts MS, surface CUZnAu
<b>Note</b>	

## Handling information

Torques	
M16 gland to housing	6.25 Nm
M16 union nut on cable gland	4.5 Nm
Housing cover	1.8 - 2.0 Nm
External earth stud	1.8 - 2.0 Nm



**1-channel distributor**



Cable gland

**1-channel distributor**



M12 connection

**C****Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG 1way	branch line CG	1	<b>8564090000</b>
<b>Stainless steel enclosure</b>			
FBCOn SS CG 1way	branch line CG	1	<b>8703430000</b>
FBCOn SS PCG 1way	all connections PCG	1	<b>8613670000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG/M12 1way	branch line M12	1	<b>8564060000</b>
<b>Stainless steel enclosure</b>			
FBCOn SS CG/M12 1way	branch line M12	1	<b>8726020000</b>



CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**

**2-channel distributor**

Cable gland

**Ordering data**



Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG 2way	branch line CG	1	<b>8564100000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****2-channel distributor**

M12 connection


**Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG/M12 2way	branch line M12	1	<b>8564070000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**

**4-channel distributor**



Cable gland

**4-channel distributor**



M12 connection

**C****Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG 4way	branch line CG	1	<b>8564110000</b>
<b>Stainless steel enclosure</b>			
FBCOn SS CG 4way	branch line CG	1	<b>8703450000</b>
FBCOn SS PCG 4way	all connections PCG	1	<b>8613680000</b>


CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG/M12 4way	branch line M12	1	<b>8564080000</b>
<b>Stainless steel enclosure</b>			
FBCOn SS CG/M12 4way	branch line M12	1	<b>8726040000</b>



CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**

**8-channel distributor**

Cable gland

**Ordering data**



Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG 8way	branch line CG	1	<b>8564300000</b>
<b>Stainless steel enclosure</b>			
FBCon SS CG 8way	branch line CG	1	<b>8703470000</b>
FBCon SS PCG 8way	all connections PCG	1	<b>8640720000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****8-channel distributor**


M12 connection

**Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG/M12 8way	branch line M12	1	<b>8564310000</b>
<b>Stainless steel enclosure</b>			
FBCon SS CG/M12 8way	branch line M12	1	<b>8726050000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**

## Fieldbus components for industrial applications with surge protection or current limiter



## PROFIBUS-PA T-connectors

Fine surge protection or integrated current limiting mechanisms are designed for protecting connected measuring devices, sensors or actuators from surge voltages. Gas-discharge tubes and suppressor diodes are voltage-limiting protection mechanisms. If a rapidly rising voltage pulse reaches the input of a T-connector with surge protection, the gas discharge tube ignites and discharges a high current. The residual pulse is limited by a suppressor diode.

In the case of a slow rise in voltage, the pulse is processed by the diode alone. The housing is connected to the protective earth via an external earth stud. When using the connectors for current limiting, the PROFIBUS-PA network is protected against short circuits with protective circuitry. The current can be set to either 20 mA, 40 mA or 60 mA by means of two DIP switches.

### Surge protection

#### Technical data

Operating temperature	-40 °C to 85 °C
Ingress protection class	IP 67
Enclosure material	High grade aluminium alloy (AL - SI 12)
Finish	Painted RAL 7001
PROFIBUS-PA connection	Tension clamp terminals 0.5 - 1.5 mm <sup>2</sup>
Cable entry	Cable gland M16
Branch	M12 socket (4-pin)
Cable gland clamping range	5.5 - 9.5 mm
Nominal voltage DC/AC	UN = 24 V DC/18 V AC
Max. permissible operating voltage	UC = 30 V DC/21 V AC
Rated current at 30 °C	IN = 500 mA
Trip surge voltage (1 kV/μs)	< 600 V
Rated discharge surge current (8/20 μs)	ISN = 10 KA (wire-wire, wire-PE)
Output voltage limit (8/20 μs)	UP = 65 V
PROFIBUS-PA bus terminator	Via jumper

#### Installation advice

##### Torques

Screw terminals	0.4 Nm
M16 cable gland at enclosure	6.0 Nm
Union nut M16 cable gland	4.0 Nm
Enclosure cover	1.8 - 2.0 Nm
External earthing cable	1.8 - 2.0 Nm

### Limiter

#### Technical data

Operating temperature	-40 °C to 85 °C
Ingress protection class	IP 67
Enclosure material	High grade aluminium alloy (AL - SI 12)
Finish	Painted RAL 7001
PROFIBUS-PA connection	Tension clamp terminals 0.5 - 1.5 mm <sup>2</sup>
Cable entry	Cable gland M16
Branch	M12 socket (4-pin)
Cable gland clamping range	5.5 - 9.5 mm
Short-circuit protection per station	20, 40, 60 mA settings
PROFIBUS-PA bus terminator	Via jumper

#### Installation advice

##### Torques

Screw terminals	0.4 Nm
M16 cable gland at enclosure	6.0 Nm
Union nut M16 cable gland	4.0 Nm
Enclosure cover	1.8 - 2.0 Nm
External earthing cable	1.8 - 2.0 Nm

**1-channel distributor (OVP)**

Cable gland

**Ordering data**





Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG 1way OVP	branch line CG	1	<b>8714120000</b>

**Stainless steel enclosure**FBCOn SS PCG 1way OVP all connections PCG 1 **8715270000**CG = brass cable gland  
PCG = plastic cable gland**1-channel distributor (OVP)**

M12 connection

**Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG/M12 1way OVP	branch line M12	1	<b>8714080000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****Dimensioned drawing****Wiring diagram**

## PROFIBUS-PA - FBCon T-distributor with surge protection

## 2-channel distributor (OVP)

Cable gland



## 2-channel distributor (OVP)

M12 connection


**C**

## Ordering data


Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG 2way OVP	branch line CG	1	<b>8714130000</b>

CG = brass cable gland  
PCG = plastic cable gland

## Dimensioned drawing



## Wiring diagram




## Ordering data


Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG/M12 2way OVP	branch line M12	1	<b>8714090000</b>

CG = brass cable gland  
PCG = plastic cable gland

## Dimensioned drawing



## Wiring diagram





**4-channel distributor (OVP)**

Cable gland

**Ordering data**



Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG 4way OVP	branch line CG	1	<b>8714140000</b>
<b>Stainless steel enclosure</b>			
FBCOn SS PCG 4way OVP	all connections PCG	1	<b>8726080000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****4-channel distributor (OVP)**

M12 connection

**Ordering data**


Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG/M12 4way OVP	branch line M12	1	<b>8714100000</b>
<b>Stainless steel enclosure</b>			

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**

## PROFIBUS-PA - FBCon T-distributor with surge protection

## 8-channel distributor (OVP)

Cable gland



## 8-channel distributor (OVP)

M12 connection


**C**

## Ordering data


Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG 8way OVP	branch line CG	1	<b>8714150000</b>
<b>Stainless steel enclosure</b>			
FBCon SS PCG 8way OVP	all connections PCG	1	<b>8726090000</b>

CG = brass cable gland  
PCG = plastic cable gland

## Dimensioned drawing



## Wiring diagram




## Ordering data


Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG/M12 8way OVP	branch line M12	1	<b>8714110000</b>
<b>Stainless steel enclosure</b>			

CG = brass cable gland  
PCG = plastic cable gland

## Dimensioned drawing



## Wiring diagram



**1-channel distributor (limiter)**



Cable gland

**Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG 1way Limiter	branch line CG	1	<b>8714200000</b>



Type	Cable gland	QTY	Order No.
<b>Stainless steel enclosure</b>			
FBCOn SS PCG 1way Limiter	all connections PCG	1	<b>8726110000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****1-channel distributor (limiter)**

M12 connection

**Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG/M12 1way Limiter	branch line M12	1	<b>8714160000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**

## PROFIBUS-PA - FBCon T-distributor with surge protection

## 2-channel distributor (limiter)

Cable gland



## 2-channel distributor (limiter)

M12 connection


**C**

## Ordering data


Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG 2way Limiter	branch line CG	1	<b>8714210000</b>

CG = brass cable gland  
PCG = plastic cable gland

## Dimensioned drawing



## Wiring diagram




## Ordering data


Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG/M12 2way Limiter	branch line M12	1	<b>8714170000</b>

CG = brass cable gland  
PCG = plastic cable gland

## Dimensioned drawing



## Wiring diagram





**4-channel distributor (limiter)**

Cable gland

**Ordering data**



Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG 4way Limiter	branch line CG	1	<b>8714220000</b>
<b>Stainless steel enclosure</b>			
FBCOn SS PCG 4way Limiter	all connections PCG	1	<b>8715260000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****4-channel distributor (limiter)**

M12 connection

**Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCOn PA CG/M12 4way Limiter	branch line M12	1	<b>8714180000</b>
<b>Stainless steel enclosure</b>			


CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**

**8-channel distributor (limiter)**



Cable gland

**8-channel distributor (limiter)**



M12 connection

**C****Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG 8way Limiter	branch line CG	1	<b>8714230000</b>
<b>Stainless steel enclosure</b>			
FBCon SS PCG 8way Limiter	all connections PCG	1	<b>8726160000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG/M12 8way Limiter	branch line M12	1	<b>8714190000</b>
<b>Stainless steel enclosure</b>			

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**



## FBCon distributors for Ex areas



### PROFIBUS-PA T-connector

- Ex(ia)

The PROFIBUS-PA installation products are increasingly used in the

- food industry
- basic industries and
- chemical industry.

The product range offers a wide choice of customer solutions for use in harsh conditions. This includes standard and EX versions of single and multi-way design with M12 plug in connection or cable glands. Weidmüller offers a solution for almost every application. If you cannot find your solution here, please contact the branch / sales office responsible for you.

### PROFIBUS-PA T-connector

- Ex(ia)

- 1-way
- 2-way
- 4-way
- 8-way

The PROFIBUS-PA T connector Ex(ia) specification is intended for direct coupling of measuring devices, sensors, actuators, etc. in potentially explosive areas.

- Approval for intrinsically safe use ATEX approval
- IP 66 Ingress Protection Class
- Modular design
- Uninterruptible bus operation
- Simple handling
- External earth terminal
- External bus terminator



# Approvals

**Weidmüller** 

**Bus Terminator 8556460000**

Datum: 27.11.00, Seite: 1/2

**Technische Beschreibung /Einsatzgebiete:**

Busabschlusselemente wie zum Beispiel der Bus Terminator 8556460000 werden in Feldbusystemen eingesetzt. Die Feldbussysteme nutzten man von Leitlinien, Automatisierungssystemen und Fertigungssystemen, andere den Bus-Terminator wie Automatisierungssysteme zusammen mit Anwendungen, die über einen Bus Terminator in Feldbusprozessen, die mit einer Frequenz von 31,25 KHz arbeiten, integriert werden. Hierbei ist jedoch zu beachten, dass der Abschlusswiderstand entsprechend dem verwendeten System gewählt werden muss.

Der Bus Terminator kann in allen durch Isolation (Sicherung) eingesetzten werden, die auf den gleichen physikalischen Grundlagen basieren. Er dient zur Angleichung des Sicherheitsstandes des Busleitfadens an den Schwellenstand der Bushalbwelle (EN 60 170).

Mögliche Einsatzgebiete können FOUNDATION Fieldbus (FF) oder PROFIBUS sein.

Der Foundation Fieldbus ist ein Z-Löcher-Bus, bei dem die Bushalbwelle über die Bushaltung mit Hinterwiderstand gespeist werden. Der Bus sollte die Bushalbwelle mindestens in der Zündschutz-Sicherheit einschließen. Darauf kann auch dieses System an dieses Prinzip zur bestimmung a2G mit Stromkreis mit geschlossenem Schaltkreis.

PROFIBUS-PA ist das Kommunikationssystem, um den Anforderungen in den Profibus-Klausuren (Certierte Protokolle) zu entsprechen. Die Komunikation im Feldbusnetz wird durch die Verbindung von Prozessdaten, Steuerung, Regelung, Steuerung, Zentralelektronik, Druckausgleich, Temperaturfühler etc. als auch herkömmliche Geräte wie Steuerungsgeräte zu können. Das Durchdringungsprinzip von FF2DP/FF zu PA ist konkurrenzlos gewährleistet. Gestellte Angaben zu PMS, DP und PA können direkt aus dem DIN 19248 entnommen.

In nicht-sicherungspflichtigen Bereichen nutzt PA die durch DP und PMS definierte RS-485-Schnittstelle als Übertragungsschnittstelle. Explorationspflichtige Bereiche in der Zündschutz-Sicherheit können über Signaleinstellung bestimmen, dass das PA-Zulassen untersagt. In das meschestrustionsysteme signiert nach IEC 1138-2 untersucht.

Die Dateneinspektion und die Ereignisverarbeitung der Festigkeit erfolgt über das gleiche Kabel. Jedes Segment erhält bei Belegung der Festigkeit einen Konzentrator von 10 ms auf. Die Signale werden durch Aufmodulieren eines Stroms von - 1mA erzeugt.

Die wesentlichen Aufgaben eines Systems in explosionsgefährdeten Bereichen sind:

- die energetische Detektionsberichtigung sicherzustellen,
- eine schnelle und sichere Auskunft über ein Fehlverhalten zu geben und
- die Anpassung der Protokollregeln während des Prozesses zu garantieren.



Seite: 1 von 2

**Weidmüller** 

**Bus Terminator 8556460000**

Datum: 27.11.00, Seite: 2/2

Spezialisiert auf den FBCon Bus Terminator 8556460000 für den eigensicheren Bereich Exia ist und für Zündschutz Exia eingesetzt werden. Der Bus Terminator darf in Verbindung mit einem Bus-Terminator wie einem Bus Terminator in Feldbusprozessen, die mit einer Frequenz von 31,25 KHz arbeiten, integriert werden. (Exia d nur in entsprechendem Containern). Bei Anwendung mit in einem Kabeldurchgang wird der Bus Terminator mit einem zusätzlichen Erdverbinder versehen (Zeichnung 855646 Blatt 7).

**Anwendungsbeispiel für ein Kommunikationssystem mit Bus Terminator**



Seite: 2 von 2

**EC-TYPE EXAMINATION CERTIFICATE**

1. Drawing No.: 855646, rev. 2 (Articles 2, 3, 4, 5 and 6)  
Drawing 842505.

2. EC-Type Examination-Certificate Number: KEMA STATEX0000 X

3. Function or product name: Bus Terminator Module Type Terminator Ex

4. Manufacturer: Weidmüller Interface GmbH & Co.

5. Address: Klingenbergstraße 16, 33758 Bielefeld, Germany

6. This equipment or protective system and any acceptable variation thereof is specified in the enclosure in the certificate and the documents which reference it.

7. CE Marking, notified body number: 2024 in accordance with Article 5 of the Council Directive 93/46/EEC of 22 March 1993, certifies that this equipment or protective system has been designed and built in accordance with the essential requirements of the following Directives relating to the design and manufacture of measurement and protection systems intended for use in potentially explosive atmospheres given in Annex II to the Directive.


8. The manufacturer and how results are determined in conformance regard see 2002/17/EC

9. Conformity with the Essential Health and Safety Requirements has been assured by manufacturer.

10. If the step 'X' is present after the certificate number, it indicates that the equipment or protective system is subject to special conditions for safe use specified in the certificate or certificate of conformity.

11. This EC-Type Examination-Certificate relates only to the design, construction and tests of the specified equipment or protective system to the requirements of the corresponding Directives. Furthermore, the following statements apply to the manufacturer's process and mode of use as specified in product data sheets. These are not covered by this certificate.

12. The drawing of this equipment or protective system is given in the file number



Amherst, 20 April 2001  
By order of the Board of Directors of N.V. KEMA

Page 1/5

**AMENDMENT 1**

**II EC-Type Examination-Certificate KEMA STATEX0000 X**

**Manufacturer:** Weidmüller Interface GmbH & Co.  
**Address:** Klingenbergstraße 16, 33758 Bielefeld, Germany

**Description:**

In future, the range of Fieldbus-Distribution is extended with a Bus Termination Module with an integrated memory function and with the integrated safe Profibus Distribution Modules Type FBCon PA CO 1 way Ex, 2 way Ex, and 4 way Ex, and Type FBCon PA CS4H2 1 way Ex, 2 way Ex and 4 way Ex.

The following non-certified connectors and couplers may be used for the connection of intrinsically safe fieldbus systems:

Connectors: Male Type 842504 and female Type 842502 and loading plug-in connectors Type 842505, 842501, 842503 and 842504.


The distribution modules, connectors and couplers are passive components, which do not influence the properties of the intrinsically safe fieldbus system.

All other data remain unchanged.

**Test documentation**

1. Drawing No.: 855646, rev. 2 (Articles 2, 3, 4, 5 and 6)	17.08.2001
855647, rev. 0 (Articles 2, 3, 4, 5 and 6)	17.08.2001
855619, rev. 0 (Articles 2, 3, 4, 5 and 6)	17.08.2001
855620, rev. 0 (Articles 2, 3, 4, 5 and 6)	17.08.2001
855618, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855617, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855616, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855615, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855614, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855613, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855612, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855611, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855610, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855609, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855608, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855607, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855606, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855605, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855604, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855603, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855602, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855601, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855600, rev. 0 (Articles 2, 3, 4 and 5)	17.08.2001
855609, rev. 1 (Article 2)	23.12.1997
845504, rev. 1 (Article 2 and 5)	23.12.1997
845503, rev. 1 (Article 2 and 5)	23.12.1997
845502, rev. 1 (Article 2 and 5)	23.12.1997
845501, rev. 1 (Article 2 and 5)	23.12.1997
845500, rev. 1 (Article 2)	23.12.1997
845505, rev. 2 (Article 2)	27.06.2001
845504, rev. 2 (Article 2)	27.06.2001
845503, rev. 2 (Article 2)	27.06.2001
845502, rev. 2 (Article 2)	27.06.2001
845501, rev. 2 (Article 2)	27.06.2001
845500, rev. 2 (Article 2)	27.06.2001
845506, rev. 1 (Article 2)	23.12.1997
2. Technical delivery condition No.: 8203	23.09.2001

**Amherst, 9 October 2001**  
KEMA Quality B.V.



T. Pijper  
Certification Manager

**Date:**  Ex ia II 2001  
**CE-Protection class:** IIa  
**CE-Approval:** This certificate may be reproduced in identity and without any change.

(01/2014)

Page 1/1

ISO 9001 ATEX

1366750000 - 2013/2014

Weidmüller  C.51

**1-channel distributor Ex**



Cable gland

**1-channel distributor Ex**



M12 connection

**C****Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG 1way Ex	branch line CG	1	<b>8564180000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG/M12 1way Ex	branch line M12	1	<b>8564150000</b>



CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**

**2-channel distributor Ex**

Cable gland

**Ordering data**



Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG 2way Ex	branch line CG	1	<b>8564190000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****2-channel distributor Ex**

M12 connection

**Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG/M12 2way Ex	branch line M12	1	<b>8564160000</b>

CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**

**4-channel distributor Ex**



Cable gland

**4-channel distributor Ex**



M12 connection

**C****Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG 4way Ex	branch line CG	1	<b>8564200000</b>


CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG/M12 4way Ex	branch line M12	1	<b>8564170000</b>



CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**

**8-channel distributor Ex**


Cable gland

**Ordering data**



Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG 8way Ex	branch line CG	1	<b>8564240000</b>


CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram****8-channel distributor Ex**

M12 connection

**Ordering data**

Type	Cable gland	QTY	Order No.
<b>Aluminium housing</b>			
FBCon PA CG/M12 8way Ex	branch line M12	1	<b>8564250000</b>



CG = brass cable gland  
PCG = plastic cable gland**Dimensioned drawing****Wiring diagram**

**FBCon bus terminator****FBCon bus terminator without earth connection****C****Technical data**

Operating temperature	-40 °C to 80 °C
Ingress protection class	IP 66
Enclosure material	High grade aluminium alloy (Al - Si 12)
Finish	Black powder-coated
Connection lead	2 x 0.14 mm <sup>2</sup>
Cable entry	Bus adapter M16

**Ordering data**



Type	Qty.	Order No.
FBCon Bus Terminator EEx with locking clip, without earth connection	1	8556460000
FBCon Bus Terminator EEx without locking clip, without earth connection	1	8606190000

**Wiring diagram****FBCon Bus Terminator with earth connection****Technical data**

Operating temperature	-40 °C to 80 °C
Ingress protection class	IP 66
Enclosure material	High grade aluminium alloy (Al - Si 12)
Finish	Black powder-coated
Connection lead	2 x 0.14 mm <sup>2</sup>
Cable entry	Bus adapter M16

**Ordering data**

Type	Qty.	Order No.
FBCon Bus Terminator EEx with locking clip, with earth connection	1	8606180000
FBCon Bus Terminator EEx without locking clip, with earth connection	1	8606200000

**Housing cover without clip-on foot****Housing cover with clip-on foot**



# Actuator-Sensor Interface Line




The new space-saving SAI AS-Interface family makes new applications possible. The narrow 24 mm form of the modules means that they can fit into a very small installation space. The length is also remarkable, since the M8 module with 4 connections is only 123 mm long.

The ribbon cable locks into the base part, while the coded cable rules out the possibility of misconnection. The piercing connectors make the module easy to connect with the help of a screwdriver. Pure input modules only require the yellow ribbon cable. The additional voltage for the outputs is fed to the module via the black cable.

The implementation of the new AS-Interface specification 3.0 means that modules with 8 inputs on one address with 62 slaves are possible in one network. Also modules with 4 inputs and 4 outputs with 62 slaves are now available. These modules require an M4 master.

All modules are certified by the AS-Interface Association and conform to the AS-Interface specifications.

The outputs, as well as the supply for sensors, are protected against short circuits and overload. These faults are signalled to the master using the peripheral bit. At the same time, the AS-I and fault LEDs blink alternately red/green in accordance with the AS-Interface specification.



All outputs can be simultaneously operated at the maximum current capacity of 0.5 A.

The housing has IP 67 class of protection, which guarantees resistance to water and dust. The addressing is performed via the infrared adapter with the user-friendly hand programming tool.

With the Weidmüller MultiCard markers, each I/O point can be individually marked, while a further marker is available for the complete module.

There are eight module versions, with four different I/O configurations available:

- 4 inputs
- 8 inputs
- 4 outputs
- 4 inputs and 4 outputs

Each I/O variant is available in two connection versions. The sensors or actuators can be connected with 5-pole M12 or 3-pole M8 plug-in connectors.



**SAI-ASI Line V3****SAI-ASI Line**

M8

**SAI-ASI Line**

M12

**Ordering data****I0 variants**

4 inputs
4 outputs
4 inputs / 4 outputs
8 inputs

**Note****Technical specifications of bus system**

Bus user	Slave
No. of subscribers	62
Transmission rate	167 kbit/s
Diagnosis indication	red
Station addresses	Infrared
AS interface spezifikation	V3.0

**Note****Accessories****Miscellaneous accessories**

M12 protective cap
M8 protective cap

**Note****SAI-ASI Line**

M8

Type	Qty.	Order No.
SAI-ASI-L-M8-4I V3	1	1962640000
SAI-ASI-L-M8-4O V3	1	1962660000
SAI-ASI-L-M8-4I/4O V3	1	1962670000
SAI-ASI-L-M8-8I V3	1	1962650000

Type	Qty.	Order No.
SAI-ASI-L-M12-4I V3	1	1962680000
SAI-ASI-L-M12-4O V3	1	1962700000
SAI-ASI-L-M12-4I/4O V3	1	1962710000
SAI-ASI-L-M12-8I V3	1	1962690000

**Technical data****General data**

Insulation material of housing	PBT
Flammability class UL 94	V-0
Operating temperature	-25 °C ... 60 °C
Storage temperature	-25 °C ... 85 °C
Protection class	IP 67

**Electrical data**

Rated voltage	26.5 ... 31.6 V
max. current-carrying capacity per output signal	0.5 A
Output level	Short-circuit-protected
Total current max.	2 A
Digital input type	TYPE 1 to EN 61131-2
E/A function indicator	LED yellow
Sensor voltage indicator	LED green

Type	Qty.	Order No.
SAI-SK-M12	30	9456050000
SAI-SK M8	50	1802760000

# AS-Interface ribbon cables

AS-Interface ribbon cable, rubber



## Technical data

Use	AS-Interface
Colour	yellow, black
Type of cable	profiled cable
Conductor cross-section	2 x 1.5 mm <sup>2</sup>
Material	EPDM (rubber)
Halogen-free	yes
Temperature range (at rest)	-40 °C ... +85 °C
Temperature range (moving)	-25 °C ... +85 °C
Flammability class	flammable
Ozone/weather-resistant	partially resistant
Minimum bending radii	fixed: 12 mm movable: 24 mm
Flexural properties	no break after 30,000 backward and forward movements

Coupling module single from ribbon cable to round cable



## Technical data

Connection AS-Interface	ribbon cable
No. connectable cables	1
Type of cable	ribbon cable, yellow + black
Flexible lead cross-section	1.5 mm <sup>2</sup>
Connection type	piercing technology
<b>Outlet line</b>	PUR
Type of cable	0.34 mm <sup>2</sup>
Conductor cross-section	2 m
Cable length	≤ 40 V
Operating voltage	≤ 4 A
Operating current	3
<b>General data</b>	-25 °C ... +75 °C
Pollution severity DIN EN 0110	-40 °C ... +85 °C
Ambient temperature	PA 6-GF-FR
Storage temperature	30 g/11 ms
Housing material	10 ... 55 Hz; 1.0 mm amplitude
Shock resistance	IP 67
Vibration resistance	20 g
<b>Specific data</b>	AS-Interface „+“ blue
Ingress protection class DIN 40050	AS-Interface „-“ brown
Weight	
M12 Pin assignment	
Pin 1: blue	
Pin 3: brown	

## Ordering data

Type	Designation	Qty.	Order No.
AS-KG-ge	Ribbon cable yellow	100 m	9455110000
AS-KG-sw	Ribbon cable black	100 m	9455120000

## Ordering data

Type	Qty.	Order No.
SAI-ASI T FR	1	1925010000

**Bridge module ribbon cable****Technical data**

Connection AS-Interface	ribbon cable
No. connectable cables	2
Type of cable	ribbon cable, yellow + black
Flexible lead cross-section	1.5 mm <sup>2</sup>
Connection type	piercing technology
<b>Outlet line</b>	
Type of cable	PUR solid
Operating voltage	≤ 40 V
Operating current	≤ 4 A
<b>General data</b>	
Pollution severity DIN EN 0110	3
Ambient temperature	-25 °C ... +75 °C
Storage temperature	-40 °C ... +85 °C
Housing material	PA 6-GF-FR
Shock resistance	30 g/11 ms
Vibration resistance	10 ... 55 Hz; 1.0 mm amplitude
<b>Specific data</b>	
Ingress protection class DIN 40050	IP 65
Weight	20 g without cable

**Coupling module ribbon cable  
to round cable / yellow + black (2 m)****Technical data**

Connection AS-Interface	ribbon cable
No. connectable cables	2
Type of cable	ribbon cable, yellow + black
Flexible lead cross-section	1.5 mm <sup>2</sup>
Connection type	piercing technology
<b>Outlet line</b>	
Type of cable	PUR
Conductor cross-section	0.34 mm <sup>2</sup>
Cable length	2 m
Operating voltage	≤ 40 V
Operating current	≤ 4 A
<b>General data</b>	
Pollution severity DIN EN 0110	3
Ambient temperature	-25 °C ... +75 °C
Storage temperature	-40 °C ... +85 °C
Housing material	PA 6-GF-FR
Shock resistance	30 g/11 ms
Vibration resistance	10 ... 55 Hz; 1.0 mm amplitude
<b>Specific data</b>	
Ingress protection class DIN 40050	IP 65 / IP 67
Weight	50 g without cable
M12 Pin assignment	
Pin 1: brown	AS-Interface „+“
Pin 2: white	ext. power supply „-“
Pin 3: blue	AS-Interface „-“
Pin 4: black	ext. power supply „+“



**Ordering data**

Type	Qty.	Order No.
SAI-ASI T FF small	1	1026090000

**Ordering data**

Type	Qty.	Order No.
SAI-ASI T FFR	1	1924980000

## CANopen &amp; DeviceNet™ cables (M12, M8)

CAN/DeviceNet™ cables  
one end without connector

## Ordering data

## Male, straight

PUR/TPE 1.5 m  
PVC/PVC 1.5 m

## Male, angled

PUR/TPE 1.5 m  
PVC/PVC 1.5 m

## Female, straight

PUR/TPE 1.5 m  
PVC/PVC 1.5 m


## Female, angled

PUR/TPE 1.5 m  
PVC/PVC 1.5 m

## Note

## 5-pole

Type	Order No.
SAIL-M12G-CD-1.5A	1964700150
SAIL-M12G-CD-1.5B	1060110150
SAIL-M12W-CD-1.5A	1062220150
SAIL-M12W-CD-1.5B	1062170150
SAIL-M12BG-CD-1.5A	1964690150
SAIL-M12BG-CD-1.5B	1060120150
SAIL-M12BW-CD-1.5A	1061980150
SAIL-M12BW-CD-1.5B	1062180150
Other versions on request	



## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000


## Technical data

Sheathing colour	Black
Protection degree	IP 67
Wire cross section	2 x 0.34 + 2 x 0.22 mm²
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C

Chapter W includes additional technical specifications for the cable

## Dimensioned drawing



**CAN/DeviceNet™ cables**  
**connecting cables**
**Ordering data****Male, straight - Female, straight**

PUR/TPE	1.5 m
PVC/PVC	1.5 m

**Male, straight - Female, angled**

PUR/TPE	1.5 m
PVC/PVC	1.5 m

**Male, angled - Female, angled**

PUR/TPE	1.5 m
PVC/PVC	1.5 m

**Note****5-pole****Type**

Type	Order No.
SAIL-M12GM12G-CD-1.5A	1964710150
SAIL-M12GM12G-CD-1.5B	1060130150
SAIL-M12GM12W-CD-1.5A	1061990150
SAIL-M12GM12W-CD-1.5B	1062190150
SAIL-M12WM12W-CD-1.5A	1062150150
SAIL-M12WM12W-CD-1.5B	1062210150

Other versions on request


**Standard cable lengths**


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

**Technical data**

Sheathing colour	Black
Protection degree	IP 67
Wire cross section	2 x 0.34 + 2 x 0.22 mm²
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C

Chapter W includes additional technical specifications for the cable

**Dimensioned drawing**



## CAN/DeviceNet™ cables Connecting cables



### Technical data

Operating voltage

Wire

Quad

Stranding sequence

Wrapping

Shield

Outer cladding

#### Electrical properties

Conductor resistance (at 20 °C)

Insulation resistance

Dielectric strength (50 Hz 1 min.)

Characteristic impedance 1-1000 KHz

Operational capacity

#### Mechanical characteristics

Min. permitted bending radius

Max. permitted tensile load

Weight

#### Thermal characteristics

moving

Stationary

Max. 300 V peak

Conductor: copper wire, without insulation, AWG 24,  
7-wire Insulation: PE 2Y

4 wires according to 3.1 are stranded in group of four

Brown, green, white, yellow

Plastic foil

Braiding tin-plated copper, opt. Coverage ≥ 85 %

PVC, YM

≤ 87 Ω/km

≤ 1 GΩ x km

Wire/wire 1000 V

nom. 100-120 Ω

nom. 56 pF/m

One time: 7.5 x cable diameter

Multiple times: 15 x cable diameter


Static: 50 N/mm<sup>2</sup>Dynamic: 20 N/mm<sup>2</sup>

Approx. 78 kg/km

-20 °C to 70 °C

-40 °C to 70 °C

### Dimensioned drawing



L in the drawing is the cable length


### Note

### Ordering data

Type	Qty.	2-pole
SAIL-M8GM8G-4S-0.2-CAN		1216820020
SAIL-M8GM8G-4S-0.25-CAN		1216820025
SAIL-M8GM8G-4S-0.3-CAN		1216820030
SAIL-M8GM8G-4S-0.5-CAN		1216820050
SAIL-M8GM8G-4S-0.8-CAN		1216820080
SAIL-M8GM8G-4S-1.0-CAN		1216820100
SAIL-M8GM8G-4S-1.5-CAN		1216820150
SAIL-M8GM8G-4S-3.0-CAN		1216820300
SAIL-M8GM8G-4S-3.5-CAN		1216820350
SAIL-M8GM8G-4S-5.0-CAN		1216820500
SAIL-M8GM8G-4S-7.0-CAN		1216820700
SAIL-M8GM8G-4S-10-CAN		1216821000

### Note

The four-pole Standard M8 sensor cables are especially well suited for the Universal Pro system. With their diameter of 0.34 mm<sup>2</sup>, these cables allow a system to be expanded up to 50 meters. The 360° shielding guarantees that signal transmission is error-free.



### Universal Pro cables



### Terminating resistor



### Technical data

#### Cable construction

No. of poles	4
Sheathing colour	grey
Material	PUR/PUR
Core cross-section	0.34 mm <sup>2</sup>
Contact surface	Gold-plated
Nominal voltage	30 V
Rated current	4 A
Protection class	IP 67
Ambient temperature, min.	-30 °C
Ambient temperature, max.	90 °C

#### Note

### Ordering data

#### Male, straight - female, straight

0.3 m
1.0 m
1.5 m
3.0 m
5.0 m
10.0 m
15.0 m
20.0 m

Type	Qty.	Order No.
SAIL-M8GM8G-4S-0.30-SB	1	1981900030
SAIL-M8GM8G-4S-1.00-SB	1	1981900100
SAIL-M8GM8G-4S-1.5U-SB	1	1981900150
SAIL-M8GM8G-4S-3.00-SB	1	1981900300
SAIL-M8GM8G-4S-5.00-SB	1	1981900500
SAIL-M8GM8G-4S-100-SB	1	1981901000
SAIL-M8GM8G-4S-150-SB	1	1981901500
SAIL-M8GM8G-4S-200-SB	1	1981902000

#### Female, straight - open end

1.5 m
3.0 m
5.0 m
10.0 m

Type	Qty.	Order No.
SAIL-M8BG-4S-1.5U-SB	1	1981910150
SAIL-M8BG-4S-3.00-SB	1	1981910300
SAIL-M8BG-4S-5.00-SB	1	1981910500
SAIL-M8BG-4S-100-SB	1	1981911000


#### Note

Other versions on request


### Ordering data – Terminating resistor

#### Note

### Dimensioned drawing



L in the drawing is the cable length

**CANopen****CAN / DeviceNet™ bulk lengths****Technical data****Component A (1x2x0.34) ST**

Conductor

Tin-plated copper 0.34 mm<sup>2</sup> (19 wires) according to UL 1581 Tab 20.1

Insulation

Polyolefine mixture according to UL Style 80 °C 30 V colour code: 2 conductor red/black  
Diameter: 1.6 ±0.1 mm

Assembly

Two twisted conductors + aluminium-polyester band (Ai exterior)

**Element B (1x2x0.22) ST**

Conductor

Tin-plated copper 0.22 mm<sup>2</sup> (19 wires) according to UL 1581 Tab 20.1

Insulation

Polyethylene foam skin  
Colour code: 2 conductors white/blue  
Diameter: approx. 2.0 mm

Assembly

Two twisted conductors + aluminium-polyester band (Ai exterior)

Complete assembly

Element A + Element B drilled

Drain wire

Tin-plated copper 0.34 mm<sup>2</sup> (19 wires) according to UL 1581 Tab 20.1

Shield

Tin-plated copper braiding, coverage 85 ± 5 %

Band

Fibre band

Outer cladding

Polyurethane mixture according to UL Style 80 °C 30 V

Marking

Colour code: black RAL 9005

**General characteristics**

Nom. impedance 0.3-20 MHz

(pair 2 x 0.22 mm<sup>2</sup>) - 120 ±10 % Ω

Nominal power rating 800 Hz

(pair 2 x 0.22 mm<sup>2</sup>) - 39 pF/mt

Operating voltage

Low-voltage computer cable

Test voltage

1000 V

Conductor resistance

Conductor A: max. 55 Ω/km at 20 °C  
Conductor B: max. 90 Ω/km at 20 °C

Min. bending radius

5 x D (during installation)  
10 x D (during operations)

Temperature range

-40 °C...+80 °C (during installation)  
-10 °C ... +80 °C (during operations)

Reference

UL 1581

Attenuation (max.)

0.5 MHz ... 1.64 bd/100 mt

(pair 0.22 mm<sup>2</sup>)

1.0 MHz ... 2.30 db/100 mt

Max. speed

180 mt/min

Max. acceleration

5 mt/s<sup>2</sup>

Copper weight

33.6 kg/km (approx.)

Total weight

79 kg/km (approx.)

**Note****Ordering data**

4-pole

Type	Order No.
SAIH-CD-2x0.34/2x0.22-PURs	1058630000

**Note**

## Screw connection M12, metal (EMC)



## SAIS / SAIB

straight



## SAISW / SAIBW

Angled



## Ordering data

<b>Male</b>	5-pole, PG 9
<b>Socket</b>	5-pole, PG 9
<b>Note</b>	

Type	Qty.	Order No.
SAIS-M-5/8S M12 5P A-COD	1	1784740000
SAIB-M-5/8S M12 5P A-COD	1	1784750000
Other versions on request		

Type	Qty.	Order No.
SAISW-M-5/8 M12	1	1803940000
SAIBW-M-5/8 M12	1	1803920000
Other versions on request		


## Technical data

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	4...6 mm (PG7) / 6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12


Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

## Dimensioned drawing




Torque, see E.12

## Dimensioned drawing



## EtherCAT - lines (M8)

## EtherCAT lines



Male

RJ45



C

## Ordering data

	M8 Male-Open-Ended	4-pole
0.1 m	SAIL-M8G-4S0.1UIE	1160820010
0.3 m	SAIL-M8G-4S0.3UIE	1160820030
0.5 m	SAIL-M8G-4S0.5UIE	1160820050
1.0 m	SAIL-M8G-4S1.0UIE	1160820100
2.0 m	SAIL-M8G-4S2.0UIE	1160820200
3.0 m	SAIL-M8G-4S3.0UIE	1160820300
4.0 m	SAIL-M8G-4S4.0UIE	1160820400
5.0 m	SAIL-M8G-4S5.0UIE	1160820500
7.5 m	SAIL-M8G-4S7.5UIE	1160820750
10.0 m	SAIL-M8G-4S10UIE	1160821000
15.0 m		
20.0 m		
30.0 m		
40.0 m		
50.0 m		

## Note

Type	Order No.
SAIL-M8GM8SG-4S0.1UIE	1160930010
SAIL-M8GM8SG-4S0.3UIE	1160930030
SAIL-M8GM8SG-4S0.5UIE	1160930050
SAIL-M8GM8SG-4S1.0UIE	1160930100
SAIL-M8GM8SG-4S2.0UIE	1160930200
SAIL-M8GM8SG-4S3.0UIE	1160930300
SAIL-M8GM8SG-4S4.0UIE	1160930400
SAIL-M8GM8SG-4S5.0UIE	1160930500
SAIL-M8GM8SG-4S7.5UIE	1160930750
SAIL-M8GM8SG-4S15UIE	1160931500
SAIL-M8GM8SG-4S20UIE	1160932000
SAIL-M8GM8SG-4S30UIE	1160933000
SAIL-M8GM8SG-4S40UIE	1160934000
SAIL-M8GM8SG-4S50UIE	1160935000

Type	Order No.
SAIL-M8GM8SG-4S0.1UIE	1160930010
SAIL-M8GM8SG-4S0.3UIE	1160930030
SAIL-M8GM8SG-4S0.5UIE	1160930050
SAIL-M8GM8SG-4S1.0UIE	1160930100
SAIL-M8GM8SG-4S2.0UIE	1160930200
SAIL-M8GM8SG-4S3.0UIE	1160930300
SAIL-M8GM8SG-4S4.0UIE	1160930400
SAIL-M8GM8SG-4S5.0UIE	1160930500
SAIL-M8GM8SG-4S7.5UIE	1160930750
SAIL-M8GM8SG-4S15UIE	1160931500
SAIL-M8GM8SG-4S20UIE	1160932000
SAIL-M8GM8SG-4S30UIE	1160933000
SAIL-M8GM8SG-4S40UIE	1160934000
SAIL-M8GM8SG-4S50UIE	1160935000

Type	Order No.
SAIL-M8GRJ45-4S2.0UIE	1201210200
SAIL-M8GRJ45-4S5.0UIE	1201210500
SAIL-M8GRJ45-4S7.5UIE	1201210750
SAIL-M8GRJ45-4S10UIE	1201211000

## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000

## Technical data

Protection degree	IP 67
Contact surface	Gold-plated
Sheathing colour	Green
Temperature range of housing	-25...+85 °C
Core cross-section	0.15

Chapter W includes additional technical specifications for the cable

## Dimensioned drawing



**Assembled cable - dragline cable M12**

- Cat.5
- PUR
- D-coded
- PROFINET type C

**M12 / M12****M12 / M12**

M12		M12
1	yellow	1
2	white	2
3	orange	3
4	blue	4

M12		M12
1	yellow	1
2	white	2
3	orange	3
4	blue	4

**Technical data**

Product type  
Category  
Shielding

Version connector left / Version connector right

Cross-section

Sheath diameter, max.

Material sheath

Sheathing colour

Insulation cross-section

Min. bending radius, repetitive

Min. bending radius, once only

Bending cycles

Speed

Acceleration

Pulling force

Ambient temperature (operational)

Installation temperature

Storage temperature

Abrasion resistance

Halogen

Resistance to spread of flame

Resistance to oils

Note

Dragline cable  
Cat.5 (ISO/IEC 11801) / Cat.5e (TIA T568-B)  
SF/UTP

M12 IP 67 straight male / M12 IP 67 straight male

4\*AWG 22/7 - 0.36 mm<sup>2</sup>

6.7 mm

PUR

green (RAL 6018)

1.5 mm

7.5 \*diameter

5 \*diameter

3 Mio

180 m/min

4 m/s<sup>2</sup>

≤ 150 N

-40 °C...+70 °C

-20 °C...+60 °C

-50 °C...+70 °C

very good

in accordance with IEC 60754-2

in accordance with IEC 60332-1

in accordance with IEC 60811-2-1

Dragline cable  
Cat.5 (ISO/IEC 11801) / Cat.5e (TIA T568-B)  
SF/UTP

M12 IP 67 straight male / M12 IP 67 straight socket

4\*AWG 22/7 - 0.36 mm<sup>2</sup>

6.7 mm

PUR

green (RAL 6018)

1.5 mm

7.5 \*diameter

5 \*diameter

3 Mio

180 m/min

4 m/s<sup>2</sup>

≤ 150 N

-40 °C...+70 °C

-20 °C...+60 °C

-50 °C...+70 °C

very good

in accordance with IEC 60754-2

in accordance with IEC 60332-1

in accordance with IEC 60811-2-1

**Ordering data**

0,5 m  
1,5 m  
3 m  
5 m  
10 m

Type	QTY	Order No.
IE-C5DD4UG0005MCSMCS-E	1	1025950005
IE-C5DD4UG0015MCSMCS-E	1	1025950015
IE-C5DD4UG0030MCSMCS-E	1	1025950030
IE-C5DD4UG0050MCSMCS-E	1	1025950050
IE-C5DD4UG0100MCSMCS-E	1	1025950100

Type	QTY	Order No.
IE-C5DD4UG0015MSSMCS-E	1	1059330015
IE-C5DD4UG0030MSSMCS-E	1	1059330030
IE-C5DD4UG0050MSSMCS-E	1	1059330050
IE-C5DD4UG0100MSSMCS-E	1	1059330100

Note

**Accessories****Sheathing stripper**

For UTP and STP data cables  
For coaxial and round data cables

Type	QTY	Order No.
AM 12	1	9030060000
IE-CST	1	9204350000

Type	QTY	Order No.
AM 12	1	9030060000
IE-CST	1	9204350000

**Markers**

Insertion label, yellow, 12 mm  
Insertion label, yellow, 18 mm  
Transparent sleeves, 12-mm length  
Transparent sleeves, 18-mm length  
Wire and cable marker, ø 4,7 - 7,4 mm  
Wire and cable marker, ø 5,8 - 7,8 mm


TM-12 NEUTRAL GE	320	1718411687
TM-18 NEUTRAL GE	320	1718431687
TM 4/12 HF/HB	500	1719840000
TM 4/18 HF/HB	500	1719850000
VT SF 5/21 NEUTRAL WS VO	160	1689470001
VT SF 6/21 NEUTRAL WS VO	160	1730560001

TM-12 NEUTRAL GE	320	1718411687
TM-18 NEUTRAL GE	320	1718431687
TM 4/12 HF/HB	500	1719840000
TM 4/18 HF/HB	500	1719850000
VT SF 5/21 NEUTRAL WS VO	160	1689470001
VT SF 6/21 NEUTRAL WS VO	160	1730560001

Note

**Assembled cable -  
dragline cable M12**

- Cat.5
- PUR
- D-coded
- PROFINET type C

**M12 / open****M12 / RJ45**

	M12
yellow	1
white	2
orange	3
blue	4

RJ45	M12
yellow	1
white	2
orange	3
blue	4

**Technical data**

Product type  
Category  
Shielding

Version connector left / Version connector right

Cross-section

Sheath diameter, max.

Material sheath

Sheathing colour

Insulation cross-section

Min. bending radius, repetitive

Min. bending radius, once only

Bending cycles

Speed

Acceleration

Pulling force

Ambient temperature (operational)

Installation temperature

Storage temperature

Abrasion resistance

Halogen

Resistance to spread of flame

Resistance to oils

Note

Dragline cable  
Cat.5 (ISO/IEC 11801) / Cat.5e (TIA T568-B)  
SF/UTP

M12 IP 67 straight male / Open

4\*AWG 22/7 - 0.36 mm<sup>2</sup>

6.7 mm

PUR

green (RAL 6018)

1.5 mm

7.5 \*diameter

5 \*diameter

3 Mio

180 m/min

4 m/s<sup>2</sup>

≤ 150 N

-40 °C...+70 °C

-20 °C...+60 °C

-50 °C...+70 °C

very good

in accordance with IEC 60754-2

in accordance with IEC 60332-1

in accordance with IEC 60811-2-1

Dragline cable  
Cat.5 (ISO/IEC 11801) / Cat.5e (TIA T568-B)  
SF/UTP

M12 IP 67 straight male / RJ45 IP 20

4\*AWG 22/7 - 0.36 mm<sup>2</sup>

6.7 mm

PUR

green (RAL 6018)

1.5 mm

7.5 \*diameter

5 \*diameter

3 Mio

180 m/min

4 m/s<sup>2</sup>

≤ 150 N

-40 °C...+70 °C

-20 °C...+60 °C

-50 °C...+70 °C

very good

in accordance with IEC 60754-2

in accordance with IEC 60332-1

in accordance with IEC 60811-2-1

**Ordering data**

1 m  
1,5 m  
3 m  
5 m  
10 m

Type	QTY	Order No.
IE-C5DD4UG0015MCSXXX-X	1	<b>1025940015</b>
IE-C5DD4UG0030MCSXXX-X	1	<b>1025940030</b>
IE-C5DD4UG0050MCSXXX-X	1	<b>1025940050</b>
IE-C5DD4UG0100MCSXXX-X	1	<b>1025940100</b>

Type	QTY	Order No.
IE-C5DD4UG0010MCSA20-E	1	<b>1044470010</b>
IE-C5DD4UG0015MCSA20-E	1	<b>1044470015</b>
IE-C5DD4UG0030MCSA20-E	1	<b>1044470030</b>
IE-C5DD4UG0050MCSA20-E	1	<b>1044470050</b>
IE-C5DD4UG0100MCSA20-E	1	<b>1044470100</b>

Note

**Accessories****Sheathing stripper**

For UTP and STP data cables  
For coaxial and round data cables

Type	QTY	Order No.
AM 12	1	<b>9030060000</b>
IE-CST	1	<b>9204350000</b>

Type	QTY	Order No.
AM 12	1	<b>9030060000</b>
IE-CST	1	<b>9204350000</b>

**Markers**

Insertion label, yellow, 12 mm  
Insertion label, yellow, 18 mm  
Transparent sleeves, 12-mm length  
Transparent sleeves, 18-mm length  
Wire and cable marker, ø 4,7 - 7,4 mm  
Wire and cable marker, ø 5,8 - 7,8 mm



TM-H 12 NEUTRAL GE	320	<b>1718411687</b>
TM-H 18 NEUTRAL GE	320	<b>1718431687</b>
TM 4/12 HF/HB	500	<b>1719840000</b>
TM 4/18 HF/HB	500	<b>1719850000</b>
VT SF 5/21 NEUTRAL WS VO	160	<b>1689470001</b>
VT SF 6/21 NEUTRAL WS VO	160	<b>1730560001</b>

TM-H 12 NEUTRAL GE	320	<b>1718411687</b>
TM-H 18 NEUTRAL GE	320	<b>1718431687</b>
TM 4/12 HF/HB	500	<b>1719840000</b>
TM 4/18 HF/HB	500	<b>1719850000</b>
VT SF 5/21 NEUTRAL WS VO	160	<b>1689470001</b>
VT SF 6/21 NEUTRAL WS VO	160	<b>1730560001</b>

Note

**Assembled cable -****M12 dragline cable, angled**

- Cat.5
- PUR
- D-coded
- PROFINET type C

**M12 / M12****M12 / M12****Technical data**

Product type
Category
Shielding
Version connector left / Version connector right
Cross-section
Sheath diameter, max.
Material sheath
Sheathing colour
Insulation cross-section
Min. bending radius, repetitive
Ambient temperature (operational)
Installation temperature
Storage temperature
Abrasion resistance
Halogen
Resistance to oils
Fire safety for railway vehicles

Dragline cable
Cat.5 (ISO/IEC 11801) / Cat.5e (TIA T568-B)
SF/UTP
M12 IP 67 straight male / M12 IP 67 angled male
4*AWG 22/7 - 0.36 mm <sup>2</sup>
6.7 mm
PUR
green (RAL 6018)
1.5 mm
7.5 *diameter
-40 °C...+70 °C
-20 °C...+60 °C
-50 °C...+70 °C
very good
in accordance with IEC 60754-2
in accordance with IEC 60811-2-1

Dragline cable
Cat.5 (ISO/IEC 11801) / Cat.5e (TIA T568-B)
SF/UTP
M12 IP 67 angled male / M12 IP 67 angled male
4*AWG 22/7 - 0.36 mm <sup>2</sup>
6.7 mm
PUR
green (RAL 6018)
1.5 mm
7.5 *diameter
-40 °C...+70 °C
-20 °C...+60 °C
-50 °C...+70 °C
very good
in accordance with IEC 60754-2
in accordance with IEC 60811-2-1

**Note****Ordering data****Cat.5 PROFINET, PUR, M12 straight-M12 angled**

1,5 m
3,0 m
5,0 m
10,0 m

**Cat.5 PROFINET, PUR, M12 angled-M12 angled**

1,5 m
3,0 m
5,0 m
10,0 m

**Cat.5, PUR, M12 angled-open**

1,5 m
3,0 m
5,0 m
10,0 m

**Note****Accessories****Markers**

Insertion label, yellow, 12 mm
Insertion label, yellow, 18 mm
Transparent sleeves, 12-mm length
Transparent sleeves, 18-mm length



Type	QTY	Order No.
TM-12 NEUTRAL GE	320	1718411687
TM-18 NEUTRAL GE	320	1718431687
TM 4/12 HF/HB	500	1719840000
TM 4/18 HF/HB	500	1719850000

Type	QTY	Order No.
TM-12 NEUTRAL GE	320	1718411687
TM-18 NEUTRAL GE	320	1718431687
TM 4/12 HF/HB	500	1719840000
TM 4/18 HF/HB	500	1719850000

**Note**

**Assembled cable -****M12 dragline cable, angled**

- Cat.5
- PUR
- D-coded
- PROFINET type C

**M12 / open****Technical data**

Product type
Category
Shielding
Version connector left / Version connector right
Cross-section
Sheath diameter, max.
Material sheath
Sheathing colour
Insulation cross-section
Min. bending radius, repetitive
Ambient temperature (operational)
Installation temperature
Storage temperature
Abrasion resistance
Halogen
Resistance to oils
Fire safety for railway vehicles

Dragline cable
Cat.5 (ISO/IEC 11801) / Cat.5e (TIA T568-B)
SF/UTP
M12 IP 67 angled male / Open
4*AWG 22/7 - 0.36 mm <sup>2</sup>
6.7 mm
PUR
green (RAL 6018)
1.5 mm
7.5 *diameter
-40 °C...+70 °C
-20 °C...+60 °C
-50 °C...+70 °C
very good
in accordance with IEC 60754-2
in accordance with IEC 60811-2-1

**Note****Ordering data****Cat.5 PROFINET, PUR, M12 straight-M12 angled**

1,5 m  
3,0 m  
5,0 m  
10,0 m

**Cat.5 PROFINET, PUR, M12 angled-M12 angled**

1,5 m  
3,0 m  
5,0 m  
10,0 m

**Cat.5, PUR, M12 angled-open**

1,5 m  
3,0 m  
5,0 m  
10,0 m

Type	QTY	Order No.
IE-C5DD4UG0015MCAXXX-X	1	<b>1059750015</b>
IE-C5DD4UG0030MCAXXX-X	1	<b>1059750030</b>
IE-C5DD4UG0050MCAXXX-X	1	<b>1059750050</b>
IE-C5DD4UG0100MCAXXX-X	1	<b>1059750100</b>

**Note****Accessories****Markers**

Insertion label, yellow, 12 mm  
Insertion label, yellow, 18 mm  
Transparent sleeves, 12-mm length  
Transparent sleeves, 18-mm length

Type	QTY	Order No.
TM-12 NEUTRAL GE	320	<b>1718411687</b>
TM-18 NEUTRAL GE	320	<b>1718431687</b>
TM 4/12 HF/HB	500	<b>1719840000</b>
TM 4/18 HF/HB	500	<b>1719850000</b>

**Note**

**Assembled cable - railway cable M12**

- Cat.5
- Radox
- D-coded

**M12 / M12****M12 / M12**

M12		M12
1	yellow	1
2	white	2
3	orange	3
4	blue	4

M12		M12
1	yellow	1
2	white	2
3	orange	3
4	blue	4

**Technical data**

Product type	
Category	
Shielding	
Version connector left / Version connector right	
Cross-section	
Sheath diameter, max.	
Material sheath	Radox GKW S
Sheathing colour	Black
Insulation cross-section	1.95 mm
Min. bending radius, repetitive	6 *diameter
Ambient temperature (operational)	-40 °C...+90 °C
Installation temperature	-25 °C...+90 °C
Storage temperature	40 °C...+90 °C
Abrasion resistance	very good
Halogen	in accordance with IEC 60754-2
Resistance to oils	in accordance with EN 50306-3
Fire safety for railway vehicles	According to DIN 5510-2 fire safety levels 1,2,3,4, According to BS 6853, According to EN50288-2-2

**Note****Ordering data**

1,5 m  
3 m  
5 m  
10 m

System cable	
Cat.5 (ISO/IEC 11801) / Cat.5e (TIA T568-B)	
SF/UTP	
M12 IP 67 straight male / M12 IP 67 straight male	
2*2*AWG 22/7 - 2*2*0.36 mm <sup>2</sup>	
7.55 mm	
Radox GKW S	
Black	
1.95 mm	
6 *diameter	
-40 °C...+90 °C	
-25 °C...+90 °C	
40 °C...+90 °C	
very good	
in accordance with IEC 60754-2	
in accordance with EN 50306-3	
According to DIN 5510-2 fire safety levels 1,2,3,4, According to BS 6853, According to EN50288-2-2	

**Note****Accessories**

<b>Sheathing stripper</b>	For UTP and STP data cables
	For coaxial and round data cables

<b>Markers</b>	Insertion label, yellow, 12 mm
	Insertion label, yellow, 18 mm
	Transparent sleeves, 12-mm length
	Transparent sleeves, 18-mm length
	Wire and cable marker, ø 4,7 - 7,4 mm
	Wire and cable marker, ø 5,8 - 7,8 mm

Type	QTY	Order No.
IE-C5DB4RE0015MCSMCS-E	1	1010850015
IE-C5DB4RE0030MCSMCS-E	1	1010850030
IE-C5DB4RE0050MCSMCS-E	1	1010850050
IE-C5DB4RE0100MCSMCS-E	1	1010850100

Type	QTY	Order No.
IE-C5DB4RE0015MSSMCS-E	1	1059340015
IE-C5DB4RE0030MSSMCS-E	1	1059340030
IE-C5DB4RE0050MSSMCS-E	1	1059340050
IE-C5DB4RE0100MSSMCS-E	1	1059340100


**Note**

<b>Type</b>	<b>QTY</b>	<b>Order No.</b>
AM 12	1	9030060000
IE-CST	1	9204350000

<b>Type</b>	<b>QTY</b>	<b>Order No.</b>
AM 12	1	9030060000
IE-CST	1	9204350000

**Assembled cable - railway cable M12**

- Cat.5
- Radox
- D-coded

**M12 / open**

M12	
yellow	1
white	2
orange	3
blue	4

**Technical data**

Product type	System cable
Category	Cat.5 (ISO/IEC 11801) / Cat.5e (TIA T568-B)
Shielding	SF/UTP
Version connector left / Version connector right	M12 IP 67 straight male / Open
Cross-section	2*2*AWG 22/7 - 2*2*0.36 mm <sup>2</sup>
Sheath diameter, max.	7.55 mm
Material sheath	Radox GKW S
Sheathing colour	Black
Insulation cross-section	1.95 mm
Min. bending radius, repetitive	6 *diameter
Ambient temperature (operational)	-40 °C...+90 °C
Installation temperature	-25 °C...+90 °C
Storage temperature	-40 °C...+90 °C
Abrasion resistance	very good
Halogen	in accordance with IEC 60754-2
Resistance to oils	in accordance with EN 50306-3
Fire safety for railway vehicles	According to DIN 5510-2 fire safety levels 1,2,3,4, According to BS 6853, According to EN50288-2-2

**Note****Ordering data**

Type	QTY	Order No.
IE-C5DB4RE0015MCSXXX-X	1	1010840015
IE-C5DB4RE0030MCSXXX-X	1	1010840030
IE-C5DB4RE0050MCSXXX-X	1	1010840050
IE-C5DB4RE0100MCSXXX-X	1	1010840100

**Note****Accessories**

<b>Sheathing stripper</b>	For UTP and STP data cables
	For coaxial and round data cables




<b>Markers</b>	Insertion label, yellow, 12 mm	320	1718411687
	Insertion label, yellow, 18 mm	320	1718431687
	Transparent sleeves, 12-mm length	500	1719840000
	Transparent sleeves, 18-mm length	500	1719850000
	Wire and cable marker, ø 4,7 - 7,4 mm	160	1689470001
	Wire and cable marker, ø 5,8 - 7,8 mm	160	1730560001

Type	QTY	Order No.
AM 12	1	9030060000
IE-CST	1	9204350000
TM-I 12 NEUTRAL GE	320	1718411687
TM-I 18 NEUTRAL GE	320	1718431687
TM 4/12 HF/HB	500	1719840000
TM 4/18 HF/HB	500	1719850000
VT SF 5/21 NEUTRAL WS VO	160	1689470001
VT SF 6/21 NEUTRAL WS VO	160	1730560001

**Note**

**Assembled cable - railway cable M12**

- Cat.5
- Radox
- D-coded

**M12 / M12****M12 / M12****Technical data**

Product type
Category
Shielding
Version connector left / Version connector right
Cross-section
Sheath diameter, max.
Material sheath
Sheathing colour
Insulation cross-section
Min. bending radius, repetitive
Ambient temperature (operational)
Installation temperature
Storage temperature
Abrasion resistance
Halogen
Resistance to oils
Fire safety for railway vehicles

System cable
Cat.5 (ISO/IEC 11801) / Cat.5e (TIA T568-B)
SF/UTP
M12 IP 67 straight male / M12 IP 67 angled male
2*2*AWG 22/7 - 2*2*0.36 mm <sup>2</sup>
7.55 mm
Radox GKW S
Black
1.95 mm
6 *diameter
-40 °C...+90 °C
-25 °C...+90 °C
40 °C...+90 °C
very good
in accordance with IEC 60754-2
in accordance with EN 50306-3
According to DIN 5510-2 fire safety levels 1,2,3,4, According to BS 6853, According to EN50288-2-2

System cable
Cat.5 (ISO/IEC 11801) / Cat.5e (TIA T568-B)
SF/UTP
M12 IP 67 angled male / M12 IP 67 angled male
2*2*AWG 22/7 - 2*2*0.36 mm <sup>2</sup>
7.55 mm
Radox GKW S
Black
1.95 mm
6 *diameter
-40 °C...+90 °C
-25 °C...+90 °C
40 °C...+90 °C
very good
in accordance with IEC 60754-2
in accordance with EN 50306-3
According to DIN 5510-2 fire safety levels 1,2,3,4, According to BS 6853, According to EN50288-2-2

**Note****Ordering data**

1,5 m
3 m
5 m
10 m

Type	QTY	Order No.
IE-C5DB4RE0015MCSMCA-E	1	1059940015
IE-C5DB4RE0030MCSMCA-E	1	1059940030
IE-C5DB4RE0050MCSMCA-E	1	1059940050
IE-C5DB4RE0100MCSMCA-E	1	1059940100

Type	QTY	Order No.
IE-C5DB4RE0015MCAMCA-E	1	1059970015
IE-C5DB4RE0030MCAMCA-E	1	1059970030
IE-C5DB4RE0050MCAMCA-E	1	1059970050
IE-C5DB4RE0100MCAMCA-E	1	1059970100

**Note****Accessories**

Markers
Insertion label, yellow, 12 mm
Insertion label, yellow, 18 mm
Transparent sleeves, 12-mm length
Transparent sleeves, 18-mm length



Type	QTY	Order No.
TM-12 NEUTRAL GE	320	1718411687
TM-18 NEUTRAL GE	320	1718431687
TM 4/12 HF/HB	500	1719840000
TM 4/18 HF/HB	500	1719850000

Type	QTY	Order No.
TM-12 NEUTRAL GE	320	1718411687
TM-18 NEUTRAL GE	320	1718431687
TM 4/12 HF/HB	500	1719840000
TM 4/18 HF/HB	500	1719850000

**Note**

**Assembled cable - railway cable M12**

- Cat.5
- Radox
- D-coded

**M12 / open****Technical data**

Product type	System cable
Category	Cat.5 (ISO/IEC 11801) / Cat.5e (TIA T568-B)
Shielding	SF/UTP
Version connector left / Version connector right	M12 IP 67 angled male / Open
Cross-section	2*2*AWG 22/7 - 2*2*0.36 mm <sup>2</sup>
Sheath diameter, max.	7.55 mm
Material sheath	Radox GKW S
Sheathing colour	Black
Insulation cross-section	1.95 mm
Min. bending radius, repetitive	6 *diameter
Ambient temperature (operational)	-40 °C...+90 °C
Installation temperature	-25 °C...+90 °C
Storage temperature	-40 °C...+90 °C
Abrasion resistance	very good
Halogen	in accordance with IEC 60754-2
Resistance to oils	in accordance with EN 50306-3
Fire safety for railway vehicles	According to DIN 5510-2 fire safety levels 1,2,3,4, According to BS 6853, According to EN50288-2-2

**Note****Ordering data**

1,5 m  
3 m  
5 m  
10 m

Type	QTY	Order No.
IE-C5DB4RE0015MCAXXX-X	1	1059900015
IE-C5DB4RE0030MCAXXX-X	1	1059900030
IE-C5DB4RE0050MCAXXX-X	1	1059900050
IE-C5DB4RE0100MCAXXX-X	1	1059900100

**Note****Accessories****Markers**

Insertion label, yellow, 12 mm  
Insertion label, yellow, 18 mm  
Transparent sleeves, 12-mm length  
Transparent sleeves, 18-mm length

Type	QTY	Order No.
TM-12 NEUTRAL GE	320	1718411687
TM-18 NEUTRAL GE	320	1718431687
TM 4/12 HF/HB	500	1719840000
TM 4/18 HF/HB	500	1719850000

**Note**

Screw connection M12, metal (EMC)  
D-coded

**SAISM / SAIBM**

straight

**SAISW**

angled

**Industrial Ethernet****Ordering data**

<b>Male</b>	4-pole, PG 9
<b>Socket</b>	4-pole, PG 9
<b>Note</b>	

Type	Qty.	Order No.
SAISM-4/8S-M12-4P D-COD	1	1892120000
SAIBM-4/8S-M12-4P D-COD	1	1892130000



Type	Qty.	Order No.
SAISW-4/8S-M12-4P D-COD	1	1160550000

**Technical data**

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

**Dimensioned drawing****Dimensioned drawing**

Torque, see E.12

**M12 tension-clamp connection, stainless steel**  
**D-coded**

**SAIS / SAIB VA**

## Industrial Ethernet



### Ordering data

Male	Type	Qty.	Order No.
Tension-clamp connection, straight, stainless steel 5-pole, PG 9	SAIS 5/9-VA D-COD	1	<b>1920700001</b>


#### Note

### Technical data




Type of connection	Tension clamp connection
Housing main material	1.4404/316L
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 69K
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

Type of connection	Tension clamp connection
Housing main material	1.4404/316L
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 69K
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

### Dimensioned drawing



Torque, see E.12

**M12 connector / PCB socket****M12 X-type cat. 6<sub>A</sub>****Plug****PCB socket****Technical data**

Category	Cat.6 <sub>A</sub> / Class E <sub>A</sub> (ISO/IEC 11801 2010)
Protection degree	IP 65, IP 67
Connection 1	M12
Housing main material	Zinc diecast
Contact holder materials	PA
Contact tube diameter	M12
Contact material / Contact surface	CuZn / Gold-plated
Ambient temperature (operational)	-25 / +85 °C
Connector standard	IEC 61076-2-109
Current-carrying capacity at 50 °C	0.5 A @ 40 °C
Rated voltage	48 V
Insulation resistance	100 MΩ
Plugging cycles	≥ 100
Configuration	360° all-round enclosure
Shielding	0.48 / 0.76 mm
Conductor diameter, finely stranded min./max.	AWG 26 / AWG 22
Wire cross-section, finely stranded, min. (AWG)	0.4 / 0.64 mm
Conductor diameter, solid min./max.	AWG 24 / AWG 22
Wire cross-section, solid, min. (AWG)	1.6 mm
Insulation cross-section, max.	5 / 9.7 mm
Sheath diameter, min. / Sheath diameter, max.	/ mm

**Note****Ordering data**

pre-assembled 2-piece design	Type	QTY	Order No.
	IE-PS-M12X-P-FH	10	1324020000

Type	QTY	Order No.
IE-PS-M12X-S-180	10	1324010000
IE-PCB2-M12X-S-180	10	1393080000

**Note****Accessories**

	Type	QTY	Order No.


Type	QTY	Order No.
IE-PS-M12X-P-FH	10	1324020000

**Note**

## FOUNDATION Fieldbus - connector (7/8")

## Plug-in connector FBCon 7/8"


## Plug-in connector straight (plug)



## Ordering data

Type	Qty.	Order No.
FBCon 7/8" 4P M	1	1808840000

## Plug-in connector 90° (plug)



## Ordering data

Type	Qty.	Order No.
FBCon 7/8" 4P M (A)	1	1808830000

## Technical data

No. of poles	4
Lock	Screw 7/8" UNF
Cable gland	PG 9
Connection	Screw
Connection cross-section	max. 1,5 mm <sup>2</sup>
Connection cross-section	16 AWG
Enclosure protection class	IP 67
Mechanical service life	> 500 plugging cycles
Upper limit temperature	+ 85 °C
Lower limit temperature	- 40 °C


## Electrical data

Rated voltage	250 V
Rated surge voltage	4000 V
Polution severity	3
Surge category	II
Insulation material group	III
Test surge voltage	4800 V
Rated current	9 A (40°)
Volume resistivity	≤ 5 mΩ
Insulation resistance	> 10 <sup>10</sup> Ω

## Materials

Contact pins	CuZn (brass)
Contact surface	Au (gold)
Socket body	PUR/PA (UL 94 HB)
Enclosure cable plug	PBT (UL 94 V-0)
Threaded ring	Anodised aluminium

## Plug-in connector straight (socket)




## Ordering data

Type	Qty.	Order No.
FBCon 7/8" 4P FM	1	1812480000

Note: refer also to chapter 7/8"

## Plug-in connector 90° (socket)



## Ordering data

Type	Qty.	Order No.
FBCon 7/8" 4P FM (A)	1	1812470000

## Accessories for fieldbus distributors

## Cable glands - plastic - IP 68



## Ordering data

Type	Qty.	Order No.
VG M16-1/K68	50	1909860000

## Cable glands - brass - IP 68



## Ordering data

Type	Qty.	Order No.
VG M16-1/MS68	50	1909910000

## Cable glands - brass - 1/EMC



## Ordering data

Type	Qty.	Order No.
VG M16-MS 1/EMV	50	1909500000

## Cable glands - brass - EEx e, IP 68



## Ordering data

Type	Qty.	Order No.
VG M16-EEx MS	50	1737210000

## Sealing rings - 9005



## Ordering data

Type	Qty.	Order No.
GWDR M16-NP	50	1736230000

## Blanking plugs - brass



## Ordering data

Type	Qty.	Order No.
VP M16-MS65	100	1777730000

## Blanking plugs - plastic - EEx e



## Ordering data

Type	Qty.	Order No.
VG M16-EEx SW	50	1737070000

## Pressure compensation element - plastic - DAE



## Ordering data

Type	Qty.	Order No.
DAE M12 PA short	10	1868560000

For technical data, refer to Catalogue 5 - Enclosures and Cable Glands



# M8, M12 Plug in connectors and protective caps

<b>M8, M12 Plug in connectors and protective caps</b>	
SAI connectors	D.2
Customisable connectors	D.4
Connectors - accessories	D.28
Built-in plugs	D.32
Valve plugs for custom assembly	D.40
Protective sleeve adapter	D.42

## SAI connectors

Self assembled M8 and M12 connectors are integral and essential connectivity components. They are available with a wide variety of different wire connection methods. Weidmüller offers all of the secure connection methods, which include screw, tension clamp, IDC or solder connection mechanisms.

One highlight in this line is the shielded, D-coded M-12 connectors. They are available in male and female versions and with tension clamp connection.

The eight pole screw connection connectors are a special favourite. These are available in shielded or unshielded versions.

D



**Fast**

The M12 connectors can also come with the tension clamp conductor connection method, either shielded or unshielded.

**Versatile**

Eight-pole M12 connectors, shielded, with screw connection and a cable outer insulation diameter of 8 – 10 mm.

**Proven**

M8 connectors with screw connections for the conductor are much easier to assemble compared to connectors which require soldering.

**Safe**

M8 connectors with shield connections are in increasing demand as the trend towards miniaturisation continues.

**M12 connectors**

Screw and tension clamp connection

**M8 connectors**

Screw and solder connection

**M8 and M12 connectors**

Insulation displacement connection (IDC)

**M8 and M12 connectors**

T distributor

**Protective caps for SAI distributors****M12/M8/M5**

Built in connectors

**Customisable valve connectors**

## Overview of M8 and M12 screw connections

**M8**

Plugs and sockets (screw connection) for custom assembly to make up M8 and M12 connections.

**M12****M12 Metal**

Machine builders frequently need individual cable lengths. To meet this demand, Weidmüller can supply M8 and M12 plug in connectors for custom assembly.

The plug in connectors are available with different cable gland diameters. In the 90° versions, the outgoing direction of the cable can be changed in 90° steps. The connected plug in connectors comply with IP 67 ingress protection classification. There are also plug in connectors available for double assignment of distributors.

**Screwy®**

This is the perfect tool for all common cable glands on sensor and actuator cables.

The Screwy® fits M12 and M8 round plugs. Both types can be used for the plugs and sockets on custom cables.

The handle of every Screwy® has a conventional 1/4 inch fitting and can be used for all sizes. Simply turn the tool to tighten or release a round plug.

The Screwy® is also available with a torque fitting. This adjustable attachment can be used for all sizes. The torque can be infinitely adjusted between 0.5 and 1.7 Nm.

**IDC-Tool**

Weidmüller offers various products with insulation displacement connection for M12 connectors. These include the IDC connection elements, which can be directly screwed to a distributor, such as part nos. 9457720000 and 1766810000.

In addition, there are two M12 IDC adapters with part nos. 1781550001 and 1781540001. All four elements can be fitted by hand with no additional tools. When there are many connections to be made in a day, however, use of the copyright protected IDC tool is recommended. This tool works like a knurled screw on the terminal.

# Overview of SAI connector M12

## Plastic

Screw connection	straight			angled		
	3-pole	4-pole	5-pole	3-pole	4-pole	5-pole
PG7 Male	1021470000	9457550000	9456940000	1021280000	9457290000	9456950000
PG7 Female	1021490000	9457240000	9457250000	1021310000	9457700000	9457260000
Screw connection						
PG9 Male	1021480000	1807340000	1807350000	1021280000	1807360000	1807370000
PG9 Female	1021510000	1807230000	1807250000	1021310000	1807240000	1807330000
Screw connection	8-pole	12-pole (Solder connection)				
PG 9 Male	1836970000	1924950000				
PG9 Female	1836960000	1924960000				
IDC connection	(0.14 - 0.34 mm <sup>2</sup> )	(0.34 - 0.75 mm <sup>2</sup> )				
Male	4-pole	4-pole				
Female	1781550001	1852740000				
Tension clamp connection			5-pole			
Male			1906390000			
Female			1924970000			

## Metal

A-coded	straight			angled		
	3-pole	4-pole	5-pole	3-pole	4-pole	5-pole
Screw connection						
PG7 Male			1191030000			
PG7 Female			1191020000			
PG9 Male		9455640000	1784740000		1803930000	1803940000
PG9 Female		8426220000	1784750000		1803910000	1803920000
Tension clamp connection						
PG9 Male						
PG9 Female		1784740002				1275750000
B-coded						
Screw connection						
PG9 Male			1784790000			1944570000
PG9 Female			1784780000			1944580000
D-coded						
Screw connection						
PG9 Male		1892120000				
PG9 Female		1892130000				
D-coded						
Screw connection						
PG9 Male		1892120001			1803930001	
PG9 Female		1892130001			1139330000	

# Overview of M8 connectors

## Plastic

Screw connection	straight			angled		
	3-pole	4-pole	5-pole	3-pole	4-pole	5-pole
Male screw connection	1803860000	1803850000				
Female screw connection	1803870000	1803880000				
Male IDC connection	1784040001	1784060001				
Female IDC connection	1784030001	1784050001				
Male solder connection				1920990000	1921000000	
Female solder connection				1920970000	1920980000	

## Metal

	straight			angled		
	3-pole	4-pole	5-pole	3-pole	4-pole	5-pole
Male screw connection	1010060000	1010070000				
Female screw connection	1010080000	1010090000				
Male solder connection	1921030000	1921040000				
Female solder connection	1921010000	1921020000				

**Screw connection M12, A-coded****SAIS / SAIB**

straight

**SAISW / SAIBW**

Angled

**Ordering data**

Male	Type	Qty.	Order No.
3-pole, PG 7	SAIS-3/7	1	1021470000
3-pole, PG 9	SAIS-3/9	1	1021480000
4-pole, PG 7	SAIS-4/7	1	9457550000
4-pole, PG 9	SAIS-4/9	1	1807340000

Socket	Type	Qty.	Order No.
3-pole, PG 7	SAIB-3/7	1	1021490000
3-pole, PG 9	SAIB-3/9	1	1021510000
4-pole, PG 7	SAIB-4/7	1	9457240000
4-pole, PG 9	SAIB-4/9	1	1807230000

**Note**

Other versions on request
---------------------------

Type	Qty.	Order No.
SAISW-3/7	1	1021280000
SAISW-3/9	1	1021290000
SAISW-4/7	1	9457290000
SAISW-4/9	1	1807360000

SAIBW-3/7	1	1021310000
SAIBW-3/9	1	1021320000
SAIBW-4/7	1	9457700000
SAIBW-4/9	1	1807240000



**Note****Technical data**

Type of connection	Screw connection
Housing main material	PA
Contact tube diameter	M12
Cable diameter	4...6 mm (PG7) / 6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	CuSnZn

**Note**

Torque, see E.12
------------------

Torque, see E.12
------------------

**Dimensioned drawing****Dimensioned drawing**

Torque, see E.12

## Screw connection M12, A-coded

## SAIS / SAIB

straight



## SAISW / SAIBW

Angled



## Ordering data

Male	Type	Qty.	Order No.
5-pole, PG 7	SAIS-5/7	1	9456940000
5-pole, PG 9	SAIS-5/9	1	1807350000
8-pole, PG 9	SAIS-8/9	1	1836970000
Socket			
5-pole, PG 7	SAIB-5/7	1	9457250000
5-pole, PG 9	SAIB-5/9	1	1807250000
8-pole, PG 9	SAIB-8/9	1	1836960000
Note	Other versions on request		

Type	Qty.	Order No.
SAISW-5/7	1	9456950000
SAISW-5/9	1	1807370000
SAIBW-5/7	1	9457260000
SAIBW-5/9	1	1807330000
Other versions on request		

Type	Qty.	Order No.
SAISW-5/7	1	9456950000
SAISW-5/9	1	1807370000
SAIBW-5/7	1	9457260000
SAIBW-5/9	1	1807330000
Other versions on request		


## Technical data

Type of connection	Screw connection
Housing main material	PA
Contact tube diameter	M12
Cable diameter	4...6 mm (PG7) / 6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V (5-pole) / 60 V (8-pole)
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	CuSnZn
Note	Torque, see E.12


Type of connection	Screw connection
Housing main material	PA
Contact tube diameter	M12
Cable diameter	4...6 mm (PG7) / 6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	CuSnZn
Note	Torque, see E.12

Type of connection	Screw connection
Housing main material	PA
Contact tube diameter	M12
Cable diameter	4...6 mm (PG7) / 6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	CuSnZn
Note	Torque, see E.12

## Dimensioned drawing



## Dimensioned drawing



Torque, see E.12

## Screw connection M12, A-coded

## SAIS / SAIB



## Ordering data

## Male

4-pole. PG 11  
5-pole. PG 11

## Socket

4-pole. PG 11  
5-pole. PG 11

## Note

## Technical data


Type of connection  
Housing main material  
Contact tube diameter  
Cable diameter  
Wire cross-section, min. / max.  
Rated current  
Rated voltage (acc. to VDE standard 0110 ISO group C)  
Temperature range of housing  
Protection degree  
Contact surface

## Note

Type	Qty.	Order No.
SAIS-4/11-1.5	1	1353700000
SAIS-5/11-1.5	1	1353740000
SAIB-4/11-1.5	1	1353730000
SAIB-5/11-1.5	1	1353750000

Screw connection
PA
M12
8...10 mm (PG11)
0.14...1.5 mm <sup>2</sup>
Contacts 1-4 8A, contact 5 2A
250 V
-25...+85 °C
IP 67
Gold-plated
Torque, see E.12

## Dimensioned drawing



Torque, see E.12

## Screw connection M12, A-coded

## SAIS / SAIB

straight



## SAISW / SAIBW

Angled



## Ordering data

Male	Type	Qty.	Order No.
4-pole, PG 7	SAIS-4/7-(KV)	1	1921060000
5-pole, PG 7	SAIS-5/7-(KV)	1	1921050000
Socket	Type	Qty.	Order No.
4-pole, PG 7	SAIB-4/7-(KV)	1	1921080000
5-pole, PG 7	SAIB-5/7-(KV)	1	1921070000

Note	Other versions on request
------	---------------------------

## Technical data

Type of connection	Screw connection
Housing main material	PA
Contact tube diameter	M12
Cable diameter	4...6 mm (PG7) / 6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	CuSnZn

Note	KV = plastic cable glandTorque, see E.12
------	--


Screw connection	PA
PA	M12
4...6 mm (PG7) / 6...8 mm (PG9)	4...6 mm (PG7) / 6...8 mm (PG9)
0.14...0.75 mm <sup>2</sup>	0.14...0.75 mm <sup>2</sup>
4 A	4 A
250 V	125 V
-25...+85 °C	-25...+85 °C
IP 67	IP 67
CuSnZn	CuSnZn

KV = plastic cable glandTorque, see E.12
--

Screw connection	PA
PA	M12
4...6 mm (PG7) / 6...8 mm (PG9)	4...6 mm (PG7) / 6...8 mm (PG9)
0.14...0.75 mm <sup>2</sup>	0.14...0.75 mm <sup>2</sup>
4 A	4 A
125 V	125 V
-25...+85 °C	-25...+85 °C
IP 67	IP 67
CuSnZn	CuSnZn


KV = plastic cable glandTorque, see E.12
--

## Dimensioned drawing



KV = plastic cable glandTorque, see E.12

## Dimensioned drawing



**Solder connection M12, A-coded****SAIS / SAIB**

Straight

**SAIBW**

Angled

**Ordering data**

<b>Male</b>	12-pole, PG 9
<b>Socket</b>	12-pole, PG 9
<b>Note</b>	

Type	Qty.	Order No.
SAIS-12/9-(TL)	1	1924950000
SAIB-12/9-(TL)	1	1924960000



Type	Qty.	Order No.
SAIBW-12/9-(TL)	1	1925870000

**Technical data**

Type of connection	Solder connection
Housing main material	PA
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.25 mm <sup>2</sup>
Rated current	1 A
Rated voltage	30 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

Type of connection	Solder connection
Housing main material	PA
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.25 mm <sup>2</sup>
Rated current	1 A
Rated voltage	30 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

Type of connection	Solder connection
Housing main material	PA
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.25 mm <sup>2</sup>
Rated current	1 A
Rated voltage	30 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

**Dimensioned drawing****Dimensioned drawing**

Torque, see E.12

**M12 tension-clamp connection, stainless steel,  
shielded**  
**A-coded**  
**B-coded**

**SAIS / SAIB VA**

straight

**Ordering data**

Male	Type	QTY	Order No.
	SAIS 5/9-VA	1	1920700000
	SAIS 5/9-VA-B-COD	1	1920720000

Socket	Type	QTY	Order No.
	SAIB 5/9-VA	1	1920710000
	SAIB 5/9-VA-B-COD	1	1920730000


**Note****Technical data**

Type of connection	Tension clamp connection
Housing main material	1.4404/316L
Contact tube diameter	M12
Cable diameter	6..8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 69K
Contact surface	Gold-plated

**Note**

Type	QTY	Order No.
SAIS 5/9-VA	1	1920700000
SAIS 5/9-VA-B-COD	1	1920720000

Type of connection	Tension clamp connection
Housing main material	1.4404/316L
Contact tube diameter	M12
Cable diameter	6..8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 69K
Contact surface	Gold-plated

**Dimensioned drawing**

PB = PROFIBUS (B-COD)Torque, see E.12



**SAI M12 plug, shielded**  
**With shield connection**
**SAISM / SAISB 8/11**

straight

**Ordering data**


Male	Type	Qty.	Order No.
8-pole, PG 9	SAISM-8/9S-M12	1	1258940000
8-pole, PG 11	SAISM-8/11S-M12	1	1118910000
Socket	Type	Qty.	Order No.
8-pole, PG 9	SAIBM-8/9S-M12	1	1258930000
8-pole, PG 11	SAIBM-8/11S-M12	1	1118920000

**Note****Technical data**

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9) / 8...10 mm (PG11)
Wire cross-section, min. / max.	0.14...0.5 mm <sup>2</sup>
Rated current	2 A
Rated voltage	60 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated

**Note**

Torque, see E.12
------------------

**Dimensioned drawing**

Torque, see E.12

**M12 screw connection, metal (shielded)****A-coded****FBCOn / SAIS**

straight

**SAISW / SAIBW**

Angled

**Ordering data**

Male	Type	Qty.	Order No.
	FBCOn M12 4P M EMC	1	9455640000
	SAIS-M-5/8S M12 5P A-COD	1	1784740000

Socket	Type	Qty.	Order No.
	FBCOn M12 4P FM EMC	1	8426220000
	SAIB-5/6S M12 5P A-COD	1	1191020000
	SAIB-M-5/8S M12 5P A-COD	1	1784750000

**Note**

Type	Qty.	Order No.
SAISW-M-4/8 M12	1	1803930000
SAISW-M-5/8 M12	1	1803940000
SAIBW-M-4/8 M12	1	1803910000
SAIBW-M-5/8 M12	1	1803920000

Type	Qty.	Order No.
Other versions on request		
Other versions on request		

**Technical data**



Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	4...6 mm (PG7) / 6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V (4-pole) / 125 V (5-pole)
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated

**Note**

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V (4-pole) / 125 V (5-pole)
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V (4-pole) / 125 V (5-pole)
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated

Torque, see E.12

**Dimensioned drawing****Dimensioned drawing**

**M12 screw connection, metal (shielded)**

**B-coded**  
**D-coded**

**Industrial Ethernet****SAISM / SAIBM**

straight

**SAIS / SAIB**

straight

**Ordering data**

Male	Type	Qty.	Order No.
Straight	3-pole, PG 9	1	1892120000
	4-pole, PG 9	1	1784790000
	5-pole, PG 9	1	
Socket			
Straight	3-pole, PG 9	1	1892130000
	4-pole, PG 9	1	1784780000
	5-pole, PG 9	1	
Note			

Type	Qty.	Order No.
SAISM-4/8S-M12-4P D-COD	1	1892120000
SAISM 5/8S M12 5P B-COD	1	1784790000
SAIBM-4/8S-M12-4P D-COD	1	1892130000
SAIBM 5/8S M12 5P B-COD	1	1784780000

Type	Qty.	Order No.
SAIS-3-IDC-M12B-COD	1	1864730000
SAIB-3-IDC-M12B-COD	1	1864740000



**Technical data**

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Cross-section for connected wire, min./max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V (4-pole) / 125 V / (5-pole)
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

Screw connection	Insulation displacement connection
CuZn	CuZn
M12	M12
6...8 mm (PG9)	7...8.8 mm
0.14...0.75 mm <sup>2</sup>	0.34...0.75 mm <sup>2</sup>
4 A	4 A
250 V (4-pole) / 125 V / (5-pole)	32 V
-25...+85 °C	-25...+85 °C
IP 67	IP 67
Gold-plated	tinned
Torque, see E.12	PB = PROFIBUS (B-COD) IE = Industrial Ethernet (D-COD)

Insulation displacement connection
CuZn
M12
7...8.8 mm
0.34...0.75 mm <sup>2</sup>
4 A
32 V
-25...+85 °C
IP 67
tinned

Torque, see E.12

**Dimensioned drawing****Dimensioned drawing**

**M12 screw connection, metal (shielded)**  
**B-coded**

### SAISW / SAIBW

Angled



### Ordering data

<b>Male</b>	5-pole, PG 9
<b>Socket</b>	5-pole, PG 9
<b>Note</b>	


Type	Qty.	Order No.
SAISW-M-5/8 M12 B-COD	1	1944570000
SAIBW-M-5/8 M12 B-COD	1	1944580000

### Technical data

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

### Dimensioned drawing



Torque, see E.12

Tension-clamp connection, metal (shielded)  
D-coded

**SAISM / SAIBM**

straight

**SAISW / SAIBW**

angled

**Industrial Ethernet****Ordering data**

Male	Type	Qty.	Order No.
Straight	SAIBM-4/8S-M12 4P D-ZF	1	1892130001
Socket	SAISM-4/8S-M12 4P D-ZF	1	1892120001
Straight			
Note			



Type	Qty.	Order No.
SAISW-4/8S-M12 4P D-ZF	1	1803930001
SAIBW-4/8S-M12 4P D-ZF	1	1139330000

**Technical data**

Type of connection	Tension clamp connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Note	Torque, see E.12

Type of connection	Tension clamp connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Note	Torque, see E.12

Type of connection	Tension clamp connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Note	Torque, see E.12

**Dimensioned drawing****Dimensioned drawing**

Torque, see E.12

**Tension clamp connection M12****A-coded****SAIS-ZF**

straight

**Ordering data**


<b>Male</b>	5-pole, PG 7
<b>Socket</b>	5-pole, PG 7
<b>Note</b>	

Type	Qty.	Order No.
SAIS-5/7-ZF	1	1906390000
SAIB-5/7-ZF	1	1924970000

**Technical data**

Type of connection	Tension clamp connection
Housing main material	PA
Contact tube diameter	M12
Cable diameter	4...6 mm
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

Type of connection	Tension clamp connection
Housing main material	PA
Contact tube diameter	M12
Cable diameter	4...6 mm
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

**D****Dimensioned drawing**

Torque, see E.12

**M8 screw connection****SAIS / SAIB**

straight

**Ordering data**

Male	Type	Qty.	Order No.
	SAIS-M8-3P	1	1803860000
	SAIS-M8-4P	1	1803850000

Socket	Type	Qty.	Order No.
	SAIB-M8-3P	1	1803870000
	SAIB-M8-4P	1	1803880000


Note Other versions on request

**Technical data**

Type of connection	Screw connection
Housing main material	PA
Contact tube diameter	M8
Cable diameter	3.5...5 mm
Wire cross-section, min. / max.	0.14...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	30 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated

Note

Torque, see E.12
------------------

**Dimensioned drawing**

Torque, see E.12

**Solder connection M8, shielded  
screw connection M8, shielded**

**SAISM / SAIBM**

straight



**SAISM / SAIBM**

straight



**Ordering data**

Male	Type	Qty.	Order No.
	SAISM-M8-3P(TL)	1	1921030000
	SAISM-M8-4P(TL)	1	1921040000

Socket	Type	Qty.	Order No.
	SAIBM-M8-3P(TL)	1	1921010000
	SAIBM-M8-4P(TL)	1	1921020000

Note	Type	Qty.	Order No.


**Technical data**

Type of connection	Solder connection
Housing main material	CuZn
Contact tube diameter	M8
Cable diameter	3.5...5.5 mm
Wire cross-section, min. / max.	0.25...0.25 mm <sup>2</sup>
Rated current	4 A
Rated voltage	30 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12


Type of connection	Solder connection
Housing main material	CuZn
Contact tube diameter	M8
Cable diameter	3.5...5.5 mm
Wire cross-section, min. / max.	0.25...0.25 mm <sup>2</sup>
Rated current	4 A
Rated voltage	30 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	IF = Iris-type springTorque, see E.12

Type of connection	Screw connection
Housing main material	CuZn
Contact tube diameter	M8
Cable diameter	3.5...5.5 mm
Wire cross-section, min. / max.	0.14...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	30 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	IF = Iris-type springTorque, see E.12

**Dimensioned drawing**



**Dimensioned drawing**



Torque, see E.12

**Solder connection M8****SAISW / SAIBW**

Angled

**Ordering data**

Male	Type	Qty.	Order No.
	SAISW-M8-3P(TL)	1	1920990000
	SAISW-M8-4P(TL)	1	1921000000


Socket	Type	Qty.	Order No.
	SAIBW-M8-3P(TL)	1	1920970000
	SAIBW-M8-4P(TL)	1	1920980000

Note	

**Technical data**

Type of connection	Solder connection
Housing main material	CuZn
Contact tube diameter	M8
Cable diameter	3.5...5.5 mm
Wire cross-section, min. / max.	0.25...0.25 mm <sup>2</sup>
Rated current	4 A
Rated voltage	30 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	Torque, see E.12

Solder connection	
CuZn	
M8	
3.5...5.5 mm	
0.25...0.25 mm <sup>2</sup>	
4 A	
30 V	
-25...+85 °C	
IP 67	
Gold-plated	
Torque, see E.12	

**Dimensioned drawing**

Torque, see E.12

## M8 and M12 insulation displacement connection (IDC)

**M8**

The assembly of round plugs is very time consuming.  
The cable has to be stripped and possibly, also fitted with a wire end ferrule.

Weidmüllers IDC plug in connector systems offers a quick fit connection system that saves both time and money.

The IDC quick fit, quick connection system is available for M12 and M8 connectors.

**M12****Screwty®**

This is the perfect tool for all common cable glands on sensor and actuator cables.

The Screwty® fits M12 and M8 round plugs. Both types can be used for plugs and sockets on custom cables.

The handle of every Screwty® has a conventional 1/4 inch fitting and can be used for all sizes. Simply turn the tool to tighten or release a round plug.

The Screwty® is also available with a torque fitting. This adjustable attachment can be used for all sizes.

The torque can be infinitely adjusted between 0.5 and 1.7 Nm.

**Insulation-displacement connection M12****A-coded****SAIS IDC / SAIB IDC**

straight

**SAISW IDC / SAIBW IDC**

Angled

**Ordering data**

<b>Male</b>	4-pole
<b>Socket</b>	4-pole
<b>Note</b>	Other versions on request

Type	Qty.	Order No.
SAIS-4-IDC M12 small	1	1781550001
SAIB-4-IDC-M12 small	1	1781540001



Type	Qty.	Order No.
SAISW-4-IDC M12	1	1812870000
SAIBW-4-IDC M12	1	1812890000

**Technical data**

Type of connection	Insulation displacement connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	4...5.1 mm
Wire cross-section, min. / max.	0.14...0.34 mm <sup>2</sup>
Rated current	4 A
Rated voltage	32 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	tinned
<b>Note</b>	Torque, see E.12

Type of connection	Insulation displacement connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	4...5.1 mm
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	32 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	tinned
<b>Note</b>	Torque, see E.12

Type of connection	Insulation displacement connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	4...5.1 mm
Wire cross-section, min. / max.	0.14...0.34 mm <sup>2</sup>
Rated current	4 A
Rated voltage	32 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	tinned
<b>Note</b>	Torque, see E.12

**Dimensioned drawing****Dimensioned drawing**

Torque, see E.12

**Insulation-displacement connection M12 (0.75)****A-coded****SAIS IDC / SAIB IDC (0.75)**

straight

**Ordering data**

Male	Type	Qty.	Order No.
	SAIS-3-IDC (0,75) M12	1	1852720000
	SAIS-4-IDC (0,75) M12	1	1852740000

Socket	Type	Qty.	Order No.
	SAIB-3-IDC (0,75) M12	1	1852730000
	SAIB-4-IDC (0,75) M12	1	1852750000

**Note**


Other versions on request
---------------------------

**Technical data**

Type of connection	Insulation displacement connection
Housing main material	CuZn
Contact tube diameter	M12
Cable diameter	5.5...8 mm
Wire cross-section, min. / max.	0.34...0.75 mm <sup>2</sup>
Rated current	6 A
Rated voltage	50 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	tinned

**Note**

Torque, see E.12
------------------

**D****Dimensioned drawing**

Torque, see E.12

**Insulation-displacement connection M8****SAIS IDC / SAIB IDC**

straight

**Ordering data**

Male	Type	Qty.	Order No.
	SAIS-3-IDC M8 small	1	<b>1784040001</b>
	SAIS-4-IDC M8 small	1	<b>1784060001</b>

Socket	Type	Qty.	Order No.
	SAIB-3-IDC-M8 small	1	<b>1784030001</b>
	SAIB-4-IDC-M8 small	1	<b>1784050001</b>

**Note**


Other versions on request
---------------------------

**Technical data**


Type of connection	Insulation displacement connection
Housing main material	CuZn
Contact tube diameter	M8
Cable diameter	3.2...5.4 mm
Wire cross-section, min. / max.	0.14...0.34 mm <sup>2</sup>
Rated current	4 A
Rated voltage	32 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	tinned

**Note**

Torque, see E.12
------------------

**Dimensioned drawing**

Torque, see E.12

**M16 plug-in connector**  
**Solder connection**
**SAIS****Male****Ordering data**


Male	Type	Qty.	Order No.
4-pole. PG 9	SAIS-M16-4/9	1	1117970000
5-pole. PG 9	SAIS-M16-5/9	1	1117990000
8-pole. PG 9	SAIS-M16-8/9	1	1304430000
2-pole. PG 9	SAIS-M16-2/9	1	1321700000
6-pole. PG 9	SAIS-M16-6/9	1	1304390000
7-pole. PG 9	SAIS-M16-7/9	1	1118010000

**Note****Technical data**

Type of connection	Solder connection
Housing main material	PA
Contact tube diameter	M12
Wire cross-section, min. / max.	0.14...0.75 mm <sup>2</sup>
Rated current	7 A
Rated voltage	250 V
Temperature range of housing	-40 ... +85 °C
Protection degree	IP 40
Contact surface	Ag (silver)

**Note**

Torque, see E.12
------------------

**Dimensioned drawing**

Torque, see E.12



# T distributor



## M12/M12

CANopen



## M12/M12

PROFIBUS



### Ordering data

Type	Qty.	Order No.
SAI-T-5S-PARA	1	1009370000

### Ordering data

Type	Qty.	Order No.
SAI-T-5-M12/M12 B-COD	1	1057940000

# Twin plugs and wall bushings

**D**


## Miniature twin plugs

Purpose-built machines often require individual cable lengths for the initiator cables. In some cases, two cables have to be of different lengths even when going to the same connector position.

To resolve this difficulty, we offer male and female connectors with two cable outlets that you can fabricate as you wish. The miniature twin plug is available with a 90° outlet and a straight outgoing cable direction. The 90° version can be twisted as you wish in steps of 90°.

## Ordering data

Type	Qty.	Order No.
SAIS-ZW-5 (straight)	1	9457540000
SAIS-ZWW (90°)	1	1837560000



## Wall bushing

In general machine building, it is common to have cables passing through the walls of control cabinets. To meet the need for a wall penetration with M12 plug in connectors, the M12 bushing is included in the range. The wall bushing is available as 5 pole.

In addition, a bushing for PROFIBUS plug in connectors (PB) is available

## Ordering data


Type	Length	Coding	Qty.	Order No.
SAI-WDF-5P M12 60 mm	60 mm	A	1	1819450000
SAI-WDF-5PB M12 60 mm	60 mm	B	1	1820690000

## M12/M12

Mounting screw M4



1. Female M12      2. Female M12



## Ordering data

Type	Qty.	Order No.
SAI-Y-5S M12/M12 2 BO	1	1881710000

# Protective caps for SAI distributors

## Protective cap M5

For SAI M5 distributors.



### Ordering data

Type	Qty.	Order No.
SAI-SK-M5	50	1855310000

## Protective cap M8

For SAI M8 distributors.



### Ordering data

Type	Qty.	Order No.
SAI-SK-M8	50	1802760000

## Protective cap M12

For SAI M12 distributors.



### Ordering data

Type	Qty.	Order No.
SAI-SK-M12	30	9456050000

## Protective cap M12

For SAI metal distributors.



### Ordering data

Type	Qty.	Order No.
SAI-SK-M12-M	30	1802750000

## Protective cap M12 IDC

For SAI distributors with IDC connection.



### Ordering data

Type	Qty.	Order No.
SAI-SK IDC	10	1794850000

## Protective cap M12 Universal

Suitable for SAI M12 - universal distributor and appropriate M12 cables.



### Ordering data

Type	Qty.	Order No.
SAI-SK-M12-UNI	20	2330260000

## Protective cap M12 connector

Protection from external influences. For open plugs.  
For attaching to cable.



### Ordering data

Type	Qty.	Order No.
SAI-SK-M12 BU	1	8425960000

## Protective cap M12 connector

Protects against external effects. For open plugs or sockets.



### Ordering data

Type	Qty.	Order No.
Protective cap connector (yellow)	50	1781520000



## M12, M8, M5 built-in plugs

For connection of cables to sensors and actuators, different built-in connectors are needed at the device end.

### M12



M12 plug in connectors are available with the following numbers of poles: 4 to 5-pole and 8-pole. Built-in connectors for M12 connections are all A-coded and have individual leads of 0.5 m. Fixing of the FP version is achieved with the supplied locknut. Also available are built-in connectors that can be screwed in from the front.

### M8



M8 connector requirements are covered by the 3 and 4 pole built-in male and female connectors. Like the M12 built-in connectors, these have a locknut for fastening into a housing wall. These connectors have 0.5m long leads attached.

### M5



Weidmüller also offers corresponding built-in connectors for the smallest of the plug in connectors, the M5. The M5 built-in connector is available in 3 and 4 pole versions. This plug in connector also has a locknut. The individual lead length with M5 built-in connectors is 0.2 m.

The cross sections of the individually attached leads are available from the technical data of the various families of plug in connectors.

**M12 (M16)**

SAIE-M12

**M12 (M16)**

SAIE-M12 FP

**Ordering data****Male**

Type	Qty.	Order No.
SAIE-M12S-4-0.5U-M16	1	1861090000
SAIE-M12S-5-0.5U-M16	1	1861230000
SAIE-M12S-8-0.5U-M16	1	1861110000

**Socket**

Type	Qty.	Order No.
SAIE-M12B-4-0.5U-M16	1	1861120000
SAIE-M12B-5-0.5U-M16	1	1836910000
SAIE-M12B-8-0.5U-M16	1	1861140000



**Note**

Other versions on request

**Technical data**

Cable gland	M16
Housing main material	CuZn, nickel-plated
Contact tube diameter	M12
Core cross-section	0.34 mm <sup>2</sup>
Rated current	4 A
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (4-pole) / 60 V (5-pole) / 30 V (8-pole)
Temperature range of housing	-30...+90 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	

Cable gland	M16
Housing main material	CuZn, nickel-plated
Contact tube diameter	M12
Core cross-section	0.25 mm <sup>2</sup>
Rated current	2 A
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (4-pole) / 60 V (5-pole) / 30 V (8 and 12-pole)
Temperature range of housing	-30...+90 °C
Protection degree	IP 67
Contact surface	Gold-plated
<b>Note</b>	

**Dimensioned drawing****Dimensioned drawing**

**M12****Ordering data**


<b>Male</b>	4-pole
<b>Socket</b>	5-pole
<b>Note</b>	

Type	Qty.	Order No.
SAIE-M12S-4-0.5U P9 1.5	1	1353770000
SAIE-M12B-4-0.5U P9 1.5	1	1353780000

**Technical data**

Cable gland
Housing main material
Contact tube diameter
Core cross-section
Rated current
Rated voltage (acc. to VDE standard 0110 ISO group C)
Temperature range of housing
Protection degree
Contact surface
<b>Note</b>

PG 9
CuZn, nickel-plated
M12
1.5 mm <sup>2</sup>
A
60 V
-30...+90 °C
IP 67
Gold-plated

**Dimensioned drawing**

**M12 (PG 9)**

SAIE-M12 PG

**M8**

SAIE-M8 FP

**Ordering data****Male**

Type	Qty.	Order No.
3-pole		
4-pole	1	1861220000
5-pole	1	1856120000
8-pole	1	1861240000

**Socket**

4-pole	1	1861250000
5-pole	1	1814890000
8-pole	1	1861270000

**Note**

with PG cable gland

**Technical data**

Cable gland	PG 9
Housing main material	CuZn, nickel-plated
Contact tube diameter	M12
Core cross-section	0.25 mm <sup>2</sup>
Rated current	A
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (4-pole) / 125 V (5-pole) / 60 V (8-pole)
Temperature range of housing	-30...+90 °C
Protection degree	IP 67
Contact surface	Gold-plated
Approvals	cURus; GOSTME25



**Note**

Cable gland	PG 9
Housing main material	CuZn, nickel-plated
Contact tube diameter	M12
Core cross-section	0.25 mm <sup>2</sup>
Rated current	A
Rated voltage (acc. to VDE standard 0110 ISO group C)	250 V (3-pole) / 30 V (4-pole)
Temperature range of housing	-30...+90 °C
Protection degree	IP 67
Contact surface	Gold-plated
Approvals	cURus; GOSTME25

Type	Qty.	Order No.
SAIE-M8R-3-0.5U-FP-M8	1	1861280000
SAIE-M8R-4-0.5U-FP-M8	1	1861290000

Fixing nut included
FP = can be positioned as required

M8	CuZn, nickel-plated
M8	0.25 mm <sup>2</sup>
4 A	60 V (3-pole) / 30 V (4-pole)
4 A	-30...+90 °C
IP 67	IP 67
Gold-plated	Gold-plated
cURus; GOSTME25	cURus; GOSTME25

**Dimensioned drawing****Dimensioned drawing**

**M8**

SAIE-M8 FP

**M5**

SAIE-M5

**Ordering data**

Male	Type	Qty.	Order No.
3-pole	SAIE-M8S-3-0.5U-FP-M8	1	1078730000
4-pole	SAIE-M8S-4-0.5U-FP-M8	1	1078720000
Socket	Type	Qty.	Order No.
3-pole	SAIE-M8B-3-0.5U-FP-M8	1	1856130000
4-pole	SAIE-M8B-4-0.5U-FP-M8	1	1856140000

**Note**

Fixing nut included
FP = can be positioned as required

Type	Qty.	Order No.
SAIE-M5S-3-0.2U	1	1873050000
SAIE-M5S-4-0.2U	1	1873030000
Type	Qty.	Order No.
SAIE-M5B-3-0.2U	1	1873060000
SAIE-M5B-4-0.2U	1	1873040000



**Technical data**


Cable gland  
Housing main material  
Contact tube diameter  
Core cross-section  
Rated current  
Rated voltage (acc. to VDE standard 0110 ISO group C)  
Temperature range of housing  
Protection degree  
Contact surface  
Approvals

**Note**

M8
CuZn, nickel-plated
M8
0.25 mm <sup>2</sup>
4 A
60 V (3-pole) / 30 V (4-pole)
-30...+90 °C
IP 67
Gold-plated

M5
CuZn, nickel-plated
M5
0.14 mm <sup>2</sup>
1 A
60 V
-25...+80 °C
IP 67
Gold-plated

**Dimensioned drawing****Dimensioned drawing**

**M12**

Male

Female

**Ordering data**


<b>Male</b>	5-pole
<b>Socket</b>	5-pole
<b>Note</b>	




Type	QTY	Order No.
SAIE-M12S-5-LP	500	1312980000
SAIE-M12B-5-LP	500	1312970000

**Technical data**

Housing main material	Zinc diecast
Contact tube diameter	M12
Rated current	4 A
Rated voltage	30 V
Temperature range of housing	-20 ... +90 °C
Protection degree	IP 68
Contact surface	Gold-plated
Approvals	
<b>Note</b>	

Rated current	4 A
Rated voltage	30 V
Temperature range of housing	-20 ... +90 °C
Protection degree	IP 68
Contact surface	Gold-plated

**Dimensioned drawing**

**M12 built-in connector,  
mounts behind wall****A-coded****Shielded****Ordering data****Male, straight**

PUR	0.5 m
PUR	2.0 m


**Female, straight**

PUR	0.5 m
PUR	2.0 m

**Note**

Type	Order No.
SAIE-M12S-5S0.5U HW	1341230050
SAIE-M12S-5S2.0U HW	1341230200



Type	Order No.
SAIE-M12S-8S0.5U HW	1341240050
SAIE-M12S-8S2.0U HW	1341240200
SAIE-M12B-5S0.5U HW	1222270050
SAIE-M12B-5S2.0U HW	1222270000
SAIE-M12B-8S0.5U HW	1223650050
SAIE-M12B-8S2.0U HW	1223650000

**Standard cable lengths**

All cables listed in the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000


**Technical data**

Cable gland	PG 9
Housing main material	Zinc diecast, nickel-plated
Contact tube diameter	M12
Core cross-section	0.25 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-5 ... +70 °C
Protection degree	IP 68
Contact surface	Gold-plated

**Dimensioned drawing**

SAIE

SAIE



Male

Female

**Ordering data**

<b>Male</b>	5-pole, PG 9
<b>Socket</b>	
	4-pole

Note

Type	QTY	Order No.
SAIE-M16S-5-HWM	1	1269790000

Type	QTY	Order No.
SAIE-M16B-4-L	20	1326720000
SAIE-M16B-5-L	1	1326730000
SAIE-M16B-7-L	1	1326740000



**Technical data**

Type of connection  
Housing main material  
Contact tube diameter  
Wire cross-section, min. / max.  
Rated current  
Rated voltage  
Temperature range of housing  
Protection degree  
Contact surface

Note

Solder connection  
Zinc diecast, nickel-plated  
M16  
0.14...0.75 mm<sup>2</sup>  
6 A  
250 V  
-30...+90 °C  
IP 67  
Ag (silver)

Solder connection  
Zinc diecast, nickel-plated  
M16  
0.14...0.75 mm<sup>2</sup>  
5 A  
125 V  
-40 ... +85 °C  
IP 40  
Ag (silver)

**Dimensioned drawing****Dimensioned drawing**

# Introduction



Valve plugs for custom cables are often incorporated when designing special machines. Such plugs are used to connect solenoid valves.

Weidmüller valve plugs are available in all customary forms. The range includes form A, form B and form C to industry standards and to DIN.

These valve plugs are available without circuitry in 3-pole and 4-pole versions. A flat gasket seal is included which, when screwed on, guarantees IP 65 protection.

D

## Ordering data


Type	(Qty.=1)	Order No.
<b>Type A</b>		
SAIB-VSA-3P/250/9-OB		1873070000
SAIB-VSA-4P/250/9-OB		1873080000
SAIB-VSA-3P/250/11-OB		1873090000
SAIB-VSA-4P/250/11-OB		1873100000
SAIB-VSA-3P/230/9/LD		1873110000
SAIB-VSA-3P/24/9/LD		1873120000
SAIB-VSA-3P/230/9-H/OB		1873130000
SAIB-VSA-4P/230/9-H/OB		1873140000
SAIB-VSA-3P/230/11-H/OB		1873150000
SAIB-VSA-4P/230/11-H/OB		1873160000
<b>Type B</b>		
SAIB-VSB-3P/250/9-OB		1873170000
SAIB-VSB-3P/24/9/LD		1873180000
SAIB-VSB-3P/250/9-OB		1873190000
<b>Type C</b>		
SAIB-VSC-3P/250/7-OB		1873200000
SAIB-VSC-4P/250/7-OB		1873210000
SAIB-VSCD-3P/250/7-OB		1873220000
SAIB-VSCD-4P/250/7-OB		1873230000
All types supplied complete with seal.		

## Legend


Designation code	
VS-	Valve plug
OB-	Without cables
3P, 4P-	No. of poles
7, 9, 11-	Cable entry (PG)
H	High form
T	Transparent housing
3P	2 + PE
4P	3 + PE
LD	24 V LED free-wheel diode

Type of valve plug	Contact gap
A	18.0 mm
B	11.0 mm
BD	10.0 mm
C	9.4 mm
CD	8.0 mm


**Plug in connector Type A**  
to DIN EN 175301-803



**Plug in connector Type B**



**Plug in connector Type C**



# Protective sleeve adapter



In machine construction, it is very common for cables to be run in the open air. To be able to protect cables from damage through a wide range of causes such as rodents, it is sometimes necessary to protect the cable with a protective sleeve.

To fasten the protective sleeve to a plug in connector designed for custom assembly, Weidmüller offers a protective sleeve adapter. This adapter is used instead of the PG7 cable gland. The protective sleeve is quick to fit, protecting the cable straight away.

**D**


## Ordering data

Type	Qty.	Order No.
SAI-SSA-PG7	10	1938300000

## Fitting a protective sleeve adapter



1. Unscrewing the PG7 cable gland



2. Screwing on the protective sleeve adapter




3. Fitting a PG7 protective sleeve



4. Finished

## Connection of protective sleeve adapter to other plug connectors



1. Connect the protective tubing to the tube union



2. Finished

The protective sleeve is also suitable for protecting cables with valve plugs. A corresponding connecting piece is already present on valve plugs with moulded seal.

# 7/8" connectors

<b>7/8" connectors</b>	
Product description	E.2
Pin Outs	E.3
Construction of the customisable connector and assembly instructions	E.4
7/8" connector	E.6
7/8" built-in connector	E.8
7/8" sensor cables	E.11

## Product description

Connectors with threads measured in inches have been used for many years, mainly outside Europe. The 7/8" thread types are the main group found within this group of products. They are essentially used in bus systems like Fieldbus Foundation or DeviceNet. In recent years these connectors also have become popular as supply ports for I/O nodes, due to the low number of pins and their sturdy construction.

**Weidmüller now offers this product range in the following versions:**


- Customisable connectors
- Built-in connectors
- Moulded cables.

7/8" connectors are available in 3-pole (2 + PE), 4-pole (3 + PE), 5-pole (4 + PE) versions. Connectors with different pole counts are not plug compatible. The contact surfaces are gold-plated.



## Customisable connectors


In certain circumstances it may be required to be able to assemble cables yourself. This may be for various reasons. For example, the length of the cable cannot be determined in advance, or during servicing, there may be a requirement to produce connections yourself. So that this can be easily achieved, simple connection solutions are required. With 7/8" connectors the screw connection provides the best solution due to its small dimensions and easy assembly. These customisable connectors also have sufficient space for the stranded wire ends. Weidmüller offers versions with differently sized cable glands to properly fit larger and smaller cable diameters. The contacts are gold-plated, for higher contact reliability.




## Pin out

### Male insert (mating side)


2+PE-pole



4-pole




4+PE-pole




### Female insert (mating side)


2+PE-pole



4-pole




4+PE-pole




# Customisable connector assembly instructions

## Straight connector




E

## Angled connector




# Individual component drawing of the customisable connector

## Straight connector



E

## Angled connector



**Screw connection 7/8", PG9**  
Cable diameter 6...8 mm

**SAIS / SAIB**

Straight

**SAISW / SAIBW**

Angled

**Ordering data**

Male	Type	QTY	Order No.
	SAIS-3/9-7/8"	1	1291870000
	SAIS-4/9-7/8"	1	1808840000
	SAIS-5/9-7/8"	1	1301220000

Socket	Type	QTY	Order No.
	SAIB-3/9-7/8"	1	1291910000
	SAIB-4/9-7/8"	1	1812480000
	SAIB-5/9-7/8"	1	1292000000

**Note**

Male	Type	QTY	Order No.
	SAISW-3/9-7/8"	1	1291890000
	SAISW-4/9-7/8"	1	1808830000
	SAISW-5/9-7/8"	1	1291980000

Socket	Type	QTY	Order No.
	SAIBW-3/9-7/8"	1	1291930000
	SAIBW-4/9-7/8"	1	1812470000
	SAIBW-5/9-7/8"	1	1292020000

**Technical data**


Type of connection	Screw connection
Housing main material	PBT
Contact tube diameter	7/8"
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.5...1.5 mm <sup>2</sup>
Rated current	9A (4- and 5-pole), 12A (3-pole)
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Contact material	CuZn
Plugging cycles	≥ 50
Pollution severity	3

**Note**


Type of connection	Screw connection
Housing main material	PBT
Contact tube diameter	7/8"
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.5...1.5 mm <sup>2</sup>
Rated current	9A (4- and 5-pole), 12A (3-pole)
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Contact material	CuZn
Plugging cycles	≥ 50
Pollution severity	3

**Note**

Type of connection	Screw connection
Housing main material	PBT
Contact tube diameter	7/8"
Cable diameter	6...8 mm (PG9)
Wire cross-section, min. / max.	0.5...1.5 mm <sup>2</sup>
Rated current	9A (4- and 5-pole), 12A (3-pole)
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Contact material	CuZn
Plugging cycles	≥ 50
Pollution severity	3

**Note****Dimensioned drawing**

Torque, see E.12

**Dimensioned drawing**

**Screw connection 7/8", PG11**  
Cable diameter 8...10 mm

**SAIS / SAIB**

Angled

**SAISW / SAIBW**

Angled

**Ordering data**

Male	Type	QTY	Order No.
	SAIS-3/11-7/8"	1	1291880000
	SAIS-4/11-7/8"	1	1291950000
	SAIS-5/11-7/8"	1	1291970000
Socket			
	SAIB-3/11-7/8"	1	1291920000
	SAIB-4/11-7/8"	1	1292050000
	SAIB-5/11-7/8"	1	1292010000
Note			



Type	QTY	Order No.
SAISW-3/11-7/8"	1	1291900000
SAISW-4/11-7/8"	1	1292040000
SAISW-5/11-7/8"	1	1291990000
SAIBW-3/11-7/8"	1	1291940000
SAIBW-4/11-7/8"	1	1292070000
SAIBW-5/11-7/8"	1	1292030000

**Technical data**

Type of connection	Screw connection
Housing main material	PBT
Contact tube diameter	7/8"
Cable diameter	8...10 mm (PG11)
Wire cross-section, min. / max.	0.5...1.5 mm <sup>2</sup>
Rated current	9A (4- and 5-pole), 12A (3-pole)
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Contact material	CuZn
Plugging cycles	≥ 50
Pollution severity	3
Note	Torque, see E.12

Type of connection	Screw connection
Housing main material	PBT
Contact tube diameter	7/8"
Cable diameter	8...10 mm (PG11)
Wire cross-section, min. / max.	0.5...1.5 mm <sup>2</sup>
Rated current	9A (4- and 5-pole), 12A (3-pole)
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Contact material	CuZn
Plugging cycles	≥ 50
Pollution severity	3
Note	Torque, see E.12

Type of connection	Screw connection
Housing main material	PBT
Contact tube diameter	7/8"
Cable diameter	8...10 mm (PG11)
Wire cross-section, min. / max.	0.5...1.5 mm <sup>2</sup>
Rated current	9A (4- and 5-pole), 12A (3-pole)
Rated voltage	250 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Contact material	CuZn
Plugging cycles	≥ 50
Pollution severity	3
Note	Torque, see E.12

**Dimensioned drawing****Dimensioned drawing**

Torque, see E.12

## 7/8" built-in connector

**7/8"**  
Mounts behind wall



## Ordering data

Male	
	3-pole
	4-pole
	5-pole
Socket	
	3-pole
	4-pole
	5-pole
Note	


Type	QTY	Order No.
SAIE-7/8"-S-3-0.2U-H	1	1292350000
SAIE-7/8"-S-4-0.2U-H	1	1292420000
SAIE-7/8"-S-5-0.2U-H	1	1292490000
SAIE-7/8"-B-3-0.2U-H	1	1292390000
SAIE-7/8"-B-4-0.2U-H	1	1292450000
SAIE-7/8"-B-5-0.2U-H	1	1292520000

## Technical data

Housing main material	Zinc diecast, nickel-plated
Contact tube diameter	7/8"
Core cross-section	0.75 mm <sup>2</sup>
Rated current	8A (4- and 5-pole), 10A (3-pole)
Rated voltage	300 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Contact material	CuZn
Plugging cycles	≥ 100
<b>Note</b>	

7/8"
0.75 mm <sup>2</sup>
8A (4- and 5-pole), 10A (3-pole)
300 V
-25...+85 °C
IP 67
Gold-plated
CuZn
≥ 100

## Dimensioned drawing



7/8"

PG 11



### Ordering data

Male	Type	QTY	Order No.
	SAIE-7/8"-S-3-0.2U-PG11	1	1292330000
	SAIE-7/8"-S-4-0.2U-PG11	1	1292400000
	SAIE-7/8"-S-5-0.2-PG11	1	1292470000
Socket			
	SAIE-7/8"-B-3-0.2U-PG11	1	1292370000
	SAIE-7/8"-B-4-0.2U-PG11	1	1292430000
	SAIE-7/8"-B-5-0.2U-PG11	1	1292500000


### Note

### Technical data

Housing main material	Zinc diecast, nickel-plated
Contact tube diameter	7/8"
Core cross-section	0.75 mm <sup>2</sup>
Rated current	8A (4- and 5-pole), 10A (3-pole)
Rated voltage	300 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Contact material	CuZn
Plugging cycles	≥ 100

### Note

### Dimensioned drawing



## 7/8" built-in connector



7/8"

PG 13.5

## Ordering data

Male	
	3-pole
	4-pole
	5-pole
Socket	
	3-pole
	4-pole
	5-pole
Note	


Type	QTY	Order No.
SAIE-7/8"-S-3-0.2U-PG13.5	1	1292340000
SAIE-7/8"-S-4-0.2U-PG13.5	1	1292410000
SAIE-7/8"-S-5-0.2U-PG13.5	1	1292480000
SAIE-7/8"-B-3-0.2U-PG13.5	1	1292380000
SAIE-7/8"-B-4-0.2U-PG13.5	1	1292440000
SAIE-7/8"-B-5-0.2U-PG13.5	1	1292510000

## Technical data


Housing main material	Zinc diecast, nickel-plated
Contact tube diameter	7/8"
Core cross-section	0.75 mm <sup>2</sup>
Rated current	8A (4- and 5-pole), 10A (3-pole)
Rated voltage	300 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Contact material	CuZn
Plugging cycles	≥ 100
Note	

Housing main material	Zinc diecast, nickel-plated
Contact tube diameter	7/8"
Core cross-section	0.75 mm <sup>2</sup>
Rated current	8A (4- and 5-pole), 10A (3-pole)
Rated voltage	300 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 67
Contact surface	Gold-plated
Contact material	CuZn
Plugging cycles	≥ 100
Note	

## Dimensioned drawing



## 7/8" one end without connector



## Ordering data

<b>Male, straight</b>	1.5 m
<b>Male, angled</b>	1.5 m
<b>Female, straight</b>	1.5 m
<b>Female, angled</b>	1.5 m
<b>Note</b>	

<b>3-pole</b>	
<b>Type</b>	<b>Order No.</b>
SAIL-7/8"G-3-1.5U	<b>1292080150</b>
SAIL-7/8"W-3-1.5U	<b>1292090150</b>
SAIL-7/8"BG-3-1.5U	<b>1292100150</b>
SAIL-7/8"BW-3-1.5U	<b>1292110150</b>

<b>4-pole</b>	
<b>Type</b>	<b>Order No.</b>
SAIL-7/8"G-4-1.5U	<b>1292120150</b>
SAIL-7/8"W-4-1.5U	<b>1292130150</b>
SAIL-7/8"BG-4-1.5U	<b>1292140150</b>
SAIL-7/8"BW-4-1.5U	<b>1292150150</b>

<b>5-pole</b>	
<b>Type</b>	<b>Order No.</b>
SAIL-7/8"G-5-1.5U	<b>1292170150</b>
SAIL-7/8"W-5-1.5U	<b>1292180150</b>
SAIL-7/8"BG-5-1.5U	<b>1292190150</b>
SAIL-7/8"BW-5-1.5U	<b>1292200150</b>


## Standard cable lengths

All cables listed in the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m xxxxxx0150
	3.0 m xxxxxx0300
	5.0 m xxxxxx0500
	10.0 m xxxxxx1000

## Technical data

Rated current / Rated voltage	9 A (4- and 5-pole) / 12 A (3-pole) / 300 V
Protection degree	IP 67, IP 68
Core cross-section	1.5 mm <sup>2</sup>
Contact surface / Contact material	Ni/Au / CuZn
Housing main material	PUR
Sheathing colour	black (similar to RAL 9005)
Temperature range of housing	-25...+85 °C
Plugging cycles	≥ 100
Pollution severity	3

## Dimensioned drawing



# Torques and spanner sizes

## Torques and distances across flats of the cable gland

The following values for strain relief apply to plug-in connectors with strain relief

Cable Ø	Min. cable pull strength	Recommended torque of the clamping screw
2 - 3	min. 20 N	0.3 - 0.4 Nm
3 - 4	min. 30 N	0.3 - 0.4 Nm
4 - 5	min. 40 N	0.8 - 1.0 Nm
5 - 6	min. 50 N	0.8 - 1.0 Nm
6 - 7	min. 60 N	0.8 - 1.0 Nm
7 - 8	min. 70 N	0.8 - 1.0 Nm
8 - 12	min. 80 N	1.0 - 1.4 Nm
12 - 14	min. 120 N	1.0 - 1.4 Nm

**Note:** Torque of the: 7/8" plug-in connector: 1.5 Nm (spanner size: 24)  
M 2.5 Threaded bolt: 0.4 Nm

# IP 67 Remote I/O system SAI Active

<b>IP 67 Remote I/O system SAI Active</b>	
Introduction	F.2
Quick select - SAI Active	F.4
SAI Active Universal - Overview	F.6
SAI Active Universal - PROFIBUS-DP	F.8
SAI Active Universal - CANopen	F.12
SAI Active Universal - DeviceNet™	F.16
SAI Active Universal Pro - Overview	F.20
SAI Active Universal Pro	F.22
SAI Active Universal Wireless - Overview	F.34
SAI Active Universal Wireless	F.36

# Sensor Actuator Interface (SAI Active)

## Decentralised Remote I/O system with IP 67 protection

Industrial automation solutions are becoming more and more decentralised. The Weidmüller sensor-actuator distributor SAI Active provides a fieldbus interface for digital communication. It is capable of merging all types of signals from the field and transmitting them without interference to the central controller unit. The SAI Active Remote I/O system is available in several variants to support different applications. A wide range of products for industrial automation are available to the user: the basic "SAI-AU" version provides a quick and simple, entry level solution for decentralisation; the professional "SAI-AU Pro" version has versatile extension options and functional modules; and the "SAI-AU Wireless" system provides a radio based solution.

The SAI Active Remote I/O system features IP 67 protection. It provides users with the opportunity to add input and/or output units to the process in a decentralised manner directly on location. The wiring is uncomplicated with pre-assembled cables and standardised M8 and M12 connectors. This simplifies the installation process and reduces the risk of cabling errors. There is no need for complex parallel wiring of the sensors and actuators. Nor do you need to merge the cables together at a central location or electrical cabinet. The IP 67 modules have a sturdy construction and provide excellent reliability under adverse conditions involving dust, moisture, acids, high temperatures or vibrations.



In comparison to traditional passive solutions which require a separate line from the point of measurement to the controller for each signal, the active modules stand out because they need only one line to digitally transmit all the signals of a standard fieldbus system. The measurement signal is transmitted to the controller unit precisely (i.e., with no drift). Thus there is no need for manual calibration.

The SAI Active Remote I/O system is available for industrial fieldbus protocols (PROFIBUS-DP, DeviceNet™, CANopen, Modbus ASCII) and Ethernet protocols (Modbus TCP and Ethernet/IP). Standardised device drivers are available. They allow you to carry out a vendor-neutral integration into your engineering system without the use of any proprietary software. The drivers can also be used with a wide range of controller units. The diagnostic capabilities of the SAI Active system (available in part using a web browser) make troubleshooting simple. They also significantly reduce the time required for initial commissioning and maintenance. Each module provides a continual specific diagnostic function for each individual channel. When a sensor, actuator or module error is detected, an easily recognised signal is displayed with an arrow icon on the corresponding module. An alert is simultaneously sent on the fieldbus or directly to the controller unit. This allows the application to react quickly so that prompt system analysis can be carried out.



F

The SAI Active system offers many benefits including less expensive installation and maintenance. It also makes optimal use of space with its compact modules.

This system includes all purpose compact modules and modular subbus components – providing users with decentralised automation that they can profit from as a long term solution.

Weidmüller offers users a wide line of active and passive sensor-actuator distributors for designing a single vendor system. The distributors are versatile enough to be used for practically all industrial automation applications. Our product line is being constantly improved, expanded and adapted to meet future needs.

Use the following table for quickly finding the proper product. Plenty of documentation and software is available to support you during the project planning and initial commissioning phases. All software programs and corresponding product documentation can be downloaded free of charge from the Weidmüller web site.



## Selection table

Order No.	Product designation	Connection system		Communication					
		M8	M12	PROFIBUS DP	CANopen	DeviceNet™	Modbus ASCII (RS 232 / USB)	Modbus TCP	Ethernet/IP
<b>SAI Active Universal</b>									
1906550000	SAI-AU M8 PB 16DI	X		X					
1906640000	SAI-AU M8 PB 16DI/8DO	X		X					
1975450000	SAI-AU M8 PB 8DI8DO 2A	X		X					
1890020000	SAI-AU M12 PB 16DI		X	X					
1890010000	SAI-AU M12 PB 16DI/8DO		X	X					
1968220000	SAI-AU M12 PB 8DI8DO 2A		X	X					
1890000000	SAI-AU M12 PB AI/AO/DI		X	X					
1906680000	SAI-AU M8 CAN 16DI	X			X				
1906690000	SAI-AU M8 CAN 16DI/8DO	X			X				
1906650000	SAI-AU M12 CAN 16DI		X		X				
1906660000	SAI-AU M12 CAN 16DI/8DO		X		X				
1906670000	SAI-AU M12 CAN AI/AO/DI		X		X				
1906730000	SAI-AU M8 DN 16DI	X				X			
1906740000	SAI-AU M8 DN 16DI/8DO	X				X			
1906700000	SAI-AU M12 DN 16DI		X			X			
1906710000	SAI-AU M12 DN 16DI/8DO		X			X			
1906720000	SAI-AU M12 DN AI/AO/DI		X			X			
<b>SAI Active Universal Pro</b>									
1024310000	SAI-AU M8 PB GW 16DI	X		X					X
1938550000	SAI-AU M12 PB GW 16DI		X	X					X
1938570000	SAI-AU M12 DN GW 16DI	X			X				X
1962240000	SAI-AU M12 USB GW 8I8O		X			X			X
1938600000	SAI-AU M8 SB 8DI	X							X
1938660000	SAI-AU M8 SB 8DO 2A	X							X
1938630000	SAI-AU M8 SB 8DIO	X							X
1938610000	SAI-AU M12 SB 8DI		X						X
1938668000	SAI-AU M12 SB 8DO 2A		X						X
1938640000	SAI-AU M12 SB 8DIO		X						X
1938690000	SAI-AU M12 SB 4AI		X						X
1938700000	SAI-AU M12 SB 4AO		X						X
1938730000	SAI-AU M12 SB 2Counter		X						X
1938720000	SAI-AU M12 SB 4Thermo		X						X
1938710000	SAI-AU M12 SB 4PT100		X						X
<b>SAI Active Universal Wireless</b>									
1006980000	SAI-AU M12 GW PB/BT 12I		X	X					X
1006940000	SAI-AU M12 BT 16DI	X							X
1006930000	SAI-AU M12 BT 16DI/8DO		X						X
1006920000	SAI-AU M12 BT4AI2AO2DIO		X						X

	Digital	Analogue	Counter	TC	RTD	Digital	Output current	Outputs	Output range	Supply voltage feed circuits	Special characteristics	Page
16										2		F.8
max.. 16, min. 8 (can be configured)						max.. 8, min. 0 (can be configured)	0.5 A			4	- Max. I/O channels = 16	F.8
8						8	2 A			4	- Max. total current, output = 8 A	F.8
16										2		F.8
max. 16, min. 8 (can be configured)						max. 8, min. 0 (can be configured)	0.5 A			1	- Max. I/O channels = 16	F.8
8						8	2 A			2	- Max. total current, output = 8 A	F.8
4	4							2	-10...+10 V, 0...+10 V, 0...20 mA, 4...20 mA	2		F.9
16										2		F.12
max. 16, min. 8 (can be configured)						max. 8, min. 0 (can be configured)	0.5 A			4	- Max. I/O channels = 16	F.12
16										2		F.12
max. 16, min. 8 (can be configured)						max. 8, min. 0 (can be configured)	0.5 A			4	- Max. I/O channels = 16	F.12
4	4							2	-10...+10 V, 0...+10 V, 0...20 mA, 4...20 mA	2		F.13
16										2		F.16
max. 16, min. 8 (can be configured)						max. 8, min. 0 (can be configured)	0.5 A			4	- Max. I/O channels = 16	F.16
16										2		F.16
max. 16, min. 8 (can be configured)						max. 8, min. 0 (can be configured)	0.5 A			4	- Max. I/O channels = 16	F.16
4	4							2	-10...+10 V, 0...+10 V, 0...20 mA, 4...20 mA	2		F.17
16										2		F.22
16										2		F.22
16										2		F.24
8						8	0.5 A			2		F.26
8										2		F.28
						8	2 A			2	- Max. total current, output = 8 A	F.28
max. 8, min. 0 (can be configured)						max. 8, min. 0 (can be configured)	0.5 A			2	- Max. I/O channels = 8 - Max. total current, output = 4 A	F.28
8												F.28
						8	2 A			2	- Max. I/O channels = 8 - Max. total current, output = 4 A	F.28
max. 8, min. 0 (can be configured)						max. 8, min. 0 (can be configured)	0.5 A			2	- Max. I/O channels = 8	F.28
	4											F.29
								4	-10...+10 V, 0...+10 V, 0...20 mA, 4...20 mA			F.29
				2						2		F.30
				4								F.31
					4							F.32
12										2		F.37
16										2		F.37
max. 16, min. 8 (can be configured)						max. 8, min. 0 (can be configured)	0.5 A			4	- Max. I/O channels = 16	F.37
max. 4, min. 2 (can be configured)	4					max. 2, min. 0 (can be configured)	0.5 A	2	-10...+10 V, 0...+10 V, 0...20 mA, 4...20 mA	2	- Max. I/O channels = 10	F.37

# SAI Active Universal

## Compact, basic versions of the Remote I/O system with IP 67 protection

The SAI Active Universal consists of basic, compact designed variants that include a variety of modules for digital and analogue inputs and outputs. The housing has a sturdy construction in compliance with strict industrial requirements. It is resistant against aggressive materials, vibration, shock, temperature, water and dust.

The high quality connection system uses conventional, standardised M8 and M12 connectors with standard compliant coding. They ensure a reliable wiring process with less risk of errors. Two M12 connections for the fieldbus allow for a continuous bus installation without any additional T-distributor. The functional earth connection is automatically created when installing on a metallic earthed base.





#### 4 independent voltage circuits

The modules can be supplied with up to four different voltage potentials. The module voltage can be simultaneously used for the inputs. In addition, up to three feed points are available for outputs; these can be switched off individually depending on the application requirements. Plug in cross connectors can be used to merge voltage potentials on the module.



#### Efficient diagnostics and status alerts

The status of the I/Os is shown directly on the module using arrow icons. The arrows point to the label and the plug in position. Up to seven status LEDs are available for displaying additional information about the power supply, fieldbus status and group diagnostics. The information is simultaneously transmitted to the controller unit via the bus system.



#### Freedom of choice

Total compliance with many industrial fieldbus standards: this permits integration with all conventional controllers so that the modules can be used in practically all applications. SAI Active Universal supports PROFIBUS-DP, CANopen, DeviceNet™ communication protocols.

**M8**  
Analogue  
Digital  
**M12**

#### A wide variety of variants

All SAI Active modules with digital inputs or digital outputs are optionally available with standard M8 or M12 connection systems. For modules in the 16DI/8DO series, the configuration can be customised to fit the application so that anywhere between 16DI to 8DI/8DO can be used. Output cables with up to 2 A per channel are used to connect almost any load. Analogue modules can be configured flexibly for the current of voltage outputs.

**PROFIBUS-DP**

**Remote I/O for digital signal processing**

**Ordering data****Module variants**

- 16 Digital In; 16 Digital In / 8 Digital Out
- 16 Digital In; 16 Digital In / 8 Digital Out
- 8 Digital In / 8 Digital Out
- 8 Digital In / 8 Digital Out

**Note****Technical data****Connections**

Fieldbus (BUS-IN)

Fieldbus (BUS-OUT)

Supply voltage (AUX-IN)

Supply voltage (AUX-OUT)

I/O connections

**Voltage supply**

Operating voltage

Contact load

Max. total current module

**Digital inputs**

Permitted input voltage

Input current, low

Input current, high

Input current, low

Input current, high

Input filter

**Digital outputs**

max. current-carrying capacity per output signal

Switching frequency load (resistive / inductive / inrush)

Short-circuit-proof

Output voltage, low

Output voltage, high

Max. total current of outputs

**Fieldbus**

Bus system

Transmission rate

Addressing

System integration

**General data**

L x W x H

Earth

Protection degree

Operating temperature

Storage temperature

Housing main material / UL 94 flammability rating

Certificate

**SAI-AU****SAI-AU**

Type	Qty.	Order No.
SAI-AU M8 PB 16DI	1	1906550000
SAI-AU M12 PB 16DI	1	1890020000

Type	Qty.	Order No.
SAI-AU M8 PB 16DI/8DO	1	1906640000
SAI-AU M12 PB 16DI/8DO	1	1890010000
SAI-AU M8 PB 8DI8DO 2A	1	1975450000
SAI-AU M12 PB 8DI8DO 2A	1	1968220000

1x M12 plug 5-pole, B-coded

1x M12 female 5-pole, B-coded

2x M12 plug 5-pole, A-coded

16 x M8 socket 3-pole / 8 x M12 socket 5-pole, A-coded

24 V (18 V DC ... 30 V DC)

Per PIN max. 4 A

10 A

-30 V to +30 V (protected against polarity reversal)

&lt; 15 mA in accordance with EN 61131-2 Type 1

2 mA to 15 mA in accordance with EN 61131-2 Type 1

&lt; 15 mA in accordance with EN 61131-2 Type 1

2 mA to 15 mA in accordance with EN 61131-2 Type 1

3 ms

0.5 A, 2 A

max. 100 Hz / max. 1 Hz / max. 8 Hz

Yes, cut-off for short circuit and error message

0 V DC

Supply voltage less 0.7 V DC

7 A, 8 A

**Profibus-DP**

Max. 12 Mbit/s (automatic detection)

Via rotary coding switch (1 - 126)

GSD file (Device-specific for each module)

210 mm / 54 mm / 32 mm

&lt; 400 g

IP 67

0 °C...+60 °C

-25 °C...+85 °C

Pocan, PBT / V-O

CE, cULus

**Note****Note****Note**

**PROFIBUS-DP**

**Remote I/O for digital and analogue signal processing**

**SAI-AU****Ordering data**

Module variants	Type	Qty.	Order No.
4 Analogue In / 2 Analogue Out / 4 Digital In	SAI-AU M12 PB AI/AO/DI	1	1890000000

**Note****Technical data****Connections**

Fieldbus (BUS-IN)	1x M12 plug 5-pole, B-coded
Fieldbus (BUS-OUT)	1x M12 female 5-pole, B-coded
Supply voltage (AUX-IN)	1x M12 plug 5-pole, A-coded
Supply voltage (AUX-OUT)	1x M12 female 5-pole, A-coded
I/O connections	8 x M12 socket 5-pole, A-coded

**Voltage supply**

Operating voltage	24 V (18 V DC ... 30 V DC)
Contact load	Per PIN max. 4 A
Max. total current module	10 A

**Digital inputs**

Permitted input voltage	-30 V to +30 V (protected against polarity reversal)
Input current, low	< 15 mA in accordance with EN 61131-2 Type 1
Input current, high	2 mA to 15 mA in accordance with EN 61131-2 Type 1
Input current, low	< 15 mA in accordance with EN 61131-2 Type 1
Input current, high	2 mA to 15 mA in accordance with EN 61131-2 Type 1
Input filter	3 ms

**Analogue inputs**

Measurement range	-10 V ... +10 V, 0 V ... 10V, 0 ... 20 mA, 4...20 mA
Maximum input voltage in relation to GND	35 V
Input resistance (load)	<125 Ohm
Max. input current (differential)	-50 mA to +50 mA (protected against polarity reversal)
Short-circuit-proof	Yes

**Resolution / Accuracy**

Analogue outputs	12-bit / < 0.2 %
Measurement range	-10 V ... +10 V, 0 V ... 10V, 0 ... 20 mA, 4...20 mA
Output interval	5 ms to 250 ms (can be configured)
Short-circuit-proof	Yes

**Resolution / Accuracy**

Fieldbus	12-bit / < 0.2 %
Bus system	Profibus-DP
Transmission rate	Max. 12 Mbit/s (automatic detection)
Addressing	Via rotary coding switch (1 – 126)

**System integration**

General data	GSD file (Device-specific for each module)
L x W x H	210 mm / 54 mm / 32 mm
Earth	< 400 g
Protection degree	IP 67
Operating temperature	0 °C...+60 °C
Storage temperature	-25 °C...+85 °C
Housing main material / UL 94 flammability rating	Pocan, PBT / V-0
Certificate	CE, cULus

**Note**

# Engineering tables for PROFIBUS



When planning the automation of a facility, you must have a wide variety of components available.

These engineering tables list all the components required for wiring up the SAI Active modules.

## PROFIBUS modules



## PROFIBUS accessories



## Sensor/actuator accessories



## Markers



## Protective caps



## Ordering data

Description	Type	Qty.	Order No.
<b>PROFIBUS modules</b>			
16 Digital In	SAI-AU M12 PB 16DI	1	1890020000
16 Digital In / 8 Digital Out	SAI-AU M12 PB 16DI/8DO	1	1890010000
4 Analogue In / 2 Analogue Out / 4 Digital In	SAI-AU M12 PB AI/AO/DI	1	1890000000
8 Digital In / 8 Digital Out	SAI-AU M12 PB 8DI/8DO 2A	1	1968220000
16 Digital In	SAI-AU M8 PB 16DI	1	1906550000
16 Digital In / 8 Digital Out	SAI-AU M8 PB 16DI/8DO	1	1906640000
8 Digital In / 8 Digital Out	SAI-AU M8 PB 8DI/8DO 2A	1	1975450000
<b>PROFIBUS accessories</b>			
PROFIBUS cables with female plug and male plug			Chapter C
PROFIBUS cables with female plug and other side open			Chapter C
PROFIBUS cables with male plug and other side open			Chapter C
PROFIBUS plug-in connector			Chapter C
PROFIBUS terminating resistor	SAIEND PB M12 5P B-COD	1	1784770000
<b>Sensor/actuator accessories</b>			
Sensor-actuator cables			Chapter B
Sensor-actuator plugs			Chapter D
<b>Markers</b>			
Semi-transparent markers for PrintJet printing	ESG 8/13.5/43.3 SAI AU	5	1912130000
<b>Protective caps</b>			
M8 Dust cap (Sensor connections)	SAI-SK M8	50	1802760000
M12 Dust cap (Sensor connections)	SAI-SK	30	9456050000
M12 Dust cap (Bus-out and power-out)	SAI-SK-M12-UNI	20	2330260000
M12 Dust cap (Bus-in and power-in)	SAI-SK plug M12	50	1781520000



**CANopen**

**Remote I/O for digital signal processing**

**Ordering data**

Module variants	Type	QTY	Order No.
16 Digital In; 16 Digital In / 8 Digital Out	SAI-AU M8 CAN 16DI	1	1906680000
16 Digital In; 16 Digital In / 8 Digital Out	SAI-AU M12 CAN 16DI	1	1906650000

**Note****SAI-AU****SAI-AU****Technical data****Connections**

Fieldbus (BUS-IN)	1x M12 plug 5-pole, A-coded
Fieldbus (BUS-OUT)	1x M12 female 5-pole, A-coded
Supply voltage (AUX-IN)	1x M12 plug 5-pole, A-coded
Supply voltage (AUX-OUT)	1x M12 female 5-pole, A-coded
I/O connections	16 x M8 socket 3-pole / 8 x M12 socket 5-pole, A-coded

**Voltage supply**

Operating voltage	24 V (18 V DC ... 30 V DC)
Contact load	Per PIN max. 4 A
Max. total current module	8 A

**Digital inputs**

Permitted input voltage	-30 V to +30 V (protected against polarity reversal)
Input current, low	< 15 mA in accordance with EN 61131-2 Type 1
Input current, high	2 mA to 15 mA in accordance with EN 61131-2 Type 1
Input current, low	< 15 mA in accordance with EN 61131-2 Type 1
Input current, high	2 mA to 15 mA in accordance with EN 61131-2 Type 1
Input filter	3 ms

**Digital outputs**

max. current-carrying capacity per output signal	0.5 A, 2 A
Switching frequency load (resistive / inductive / inrush)	max. 100 Hz / max. 1 Hz / max. 8 Hz
Short-circuit-proof	Yes, cut-off for short circuit and error message
Output voltage, low	0 V DC
Output voltage, high	Supply voltage less 0.7 V DC
Max. total current of outputs	7 A, 8 A

**Fieldbus**

Bus system	CANopen
Transmission rate	Max. 1 Mbit/s (automatic detection)
Addressing	Via rotary coding switch (1 - 127)
System integration	EDS file (Device-specific for each module)

**General data**

L x W x H	210 mm / 54 mm / 32 mm
Earth	< 400 g
Protection degree	IP 67
Operating temperature	0 °C...+60 °C
Storage temperature	-25 °C...+85 °C
Housing main material / UL 94 flammability rating	Pocan, PBT / V-O
Certificate	CE, cULus

**Note**

**CANopen**

**Remote I/O for digital and analogue signal processing**

**SAI-AU****Ordering data**

Module variants	Type	QTY	Order No.
4 Analogue In / 2 Analogue Out / 4 Digital In	SAI-AU M12 CAN AI/AO/DI	1	1906670000

**Note****Technical data****Connections**

Fieldbus (BUS-IN)

Fieldbus (BUS-OUT)

Supply voltage (AUX-IN)

Supply voltage (AUX-OUT)

I/O connections

**Voltage supply**

Operating voltage

Contact load

Max. total current module

**Digital inputs**

Permitted input voltage

Input current, low

Input current, high

Input current, low

Input current, high

Input filter

**Digital outputs**

max. current-carrying capacity per output signal

Switching frequency load (resistive / inductive / inrush)

Short-circuit-proof

Output voltage, low

Output voltage, high

Max. total current of outputs

**Fieldbus**

Bus system

Transmission rate

Addressing

System integration

**General data**

L x W x H

Earth

Protection degree

Operating temperature

Storage temperature

Housing main material / UL 94 flammability rating

Certificate

Type	QTY	Order No.
SAI-AU M12 CAN AI/AO/DI	1	1906670000

1x M12 plug 5-pole, A-coded
1x M12 female 5-pole, A-coded
1x M12 plug 5-pole, A-coded
1x M12 female 5-pole, A-coded

24 V (18 V DC ... 30 V DC)
Per PIN max. 4 A
8 A

-30 V to +30 V (protected against polarity reversal)
< 15 mA in accordance with EN 61131-2 Type 1
2 mA to 15 mA in accordance with EN 61131-2 Type 1
< 15 mA in accordance with EN 61131-2 Type 1
2 mA to 15 mA in accordance with EN 61131-2 Type 1
3 ms

max. current-carrying capacity per output signal
Switching frequency load (resistive / inductive / inrush)
Short-circuit-proof
Output voltage, low
Output voltage, high
Max. total current of outputs

CANopen
Max. 1 Mbit/s (automatic detection)
Via rotary coding switch (1 – 127)
EDS file (Device-specific for each module)

210 mm / 54 mm / 32 mm
< 400 g
IP 67
0 °C...+60 °C
-25 °C...+85 °C
Pocan, PBT / V-0
CE, cULus

**Note**

F

# Engineering tables for CANopen



When planning the automation of a facility, you must have a wide variety of components available.

These engineering tables list all the components required for wiring up the SAI Active modules.

## CANopen modules



## CANopen accessories



## Sensor/actuator accessories



## Markers



## Protective caps



## Ordering data

Description	Type	Qty.	Order No.
<b>CANopen modules</b>			
16 Digital In	SAI-AU M12 CAN 16DI	1	1906650000
16 Digital In / 8 Digital Out	SAI-AU M12 CAN 16DI/8DO	1	1906660000
4 Analogue In / 2 Analogue Out / 4 Digital In	SAI-AU M12 CAN AI/AO/DI	1	1906670000
16 Digital In	SAI-AU M8 CAN 16DI	1	1906680000
16 Digital In / 8 Digital Out	SAI-AU M8 CAN 16DI/8DO	1	1906690000

## CANopen accessories

CANopen cables with female plug and male plug	Chapter C
CANopen cables with female plug and other side open	Chapter C
CANopen cables with male plug and other side open	Chapter C
<b>CANopen plug-in connector</b>	
CANopen terminating resistor	SAIEND CAN-M12 5P A-COD
	1 1784760000

## Sensor/actuator accessories

Sensor-actuator cables	Chapter B
<b>Sensor-actuator plugs</b>	
Sensor-actuator plugs	Chapter D

## Markers

Semi-transparent markers for PrintJet printing	ESG 8/13.5/43.3 SAI AU	5	1912130000
---	------------------------	---	------------

## Protective caps

M8 Dust cap (Sensor connections)	SAI-SK M8	50	1802760000
M12 Dust cap (Sensor connections)	SAI-SK	30	9456050000
M12 Dust cap (Bus-out and power-out)	SAI-SK-M12-UNI	20	2330260000
M12 Dust cap (Bus-in and power-in)	SAI-SK plug M12	50	1781520000



**DeviceNet™**

**Remote I/O for digital signal processing**

**Ordering data****Module variants**

- 16 Digital In; 16 Digital In / 8 Digital Out
- 16 Digital In; 16 Digital In / 8 Digital Out

**Note****SAI-AU****SAI-AU****Technical data****Connections**

Fieldbus (BUS-IN)

Fieldbus (BUS-OUT)

Supply voltage (AUX-IN)

Supply voltage (AUX-OUT)

I/O connections

**Voltage supply**

Operating voltage

Contact load

Max. total current module

**Digital inputs**

Permitted input voltage

Input current, low

Input current, high

Input current, low

Input current, high

Input filter

**Digital outputs**

max. current-carrying capacity per output signal

Switching frequency load (resistive / inductive / inrush)

Short-circuit-proof

Output voltage, low

Output voltage, high

Max. total current outputs

**Fieldbus**

Bus system

Transmission rate

Addressing

System integration

**General data**

L x W x H

Earth

Protection degree

Operating temperature

Storage temperature

Housing main material / UL 94 flammability rating

Certificate

Type	Qty.	Order No.
SAI-AU M8 DN 16DI	1	1906730000
SAI-AU M12 DN 16DI	1	1906700000

Type	Qty.	Order No.
SAI-AU M8 DN 16DI/8DO	1	1906740000
SAI-AU M12 DN 16DI/8DO	1	1906710000

**Note**

**DeviceNet™**

**Remote I/O for digital and analogue signal processing**

**SAI-AU****Ordering data**

Module variants	Type	Qty.	Order No.
4 Analogue In / 2 Analogue Out / 4 Digital In	SAI-AU M12 DN AI/AO/DI	1	1906720000

**Note****Technical data****Connections**

Fieldbus (BUS-IN)	1x M12 plug 5-pole, A-coded
Fieldbus (BUS-OUT)	1x M12 female 5-pole, A-coded
Supply voltage (AUX-IN)	1x M12 plug 5-pole, A-coded
Supply voltage (AUX-OUT)	1x M12 female 5-pole, A-coded
I/O connections	8 x M12 socket 5-pole, A-coded

**Voltage supply**

Operating voltage	24 V (18 V DC ... 30 V DC)
Contact load	Per PIN max. 4 A
Max. total current module	8 A

**Digital inputs**

Permitted input voltage	-30 V to +30 V (protected against polarity reversal)
Input current, low	< 15 mA in accordance with EN 61131-2 Type 1
Input current, high	2 mA to 15 mA in accordance with EN 61131-2 Type 1
Input current, low	< 15 mA in accordance with EN 61131-2 Type 1
Input current, high	2 mA to 15 mA in accordance with EN 61131-2 Type 1
Input filter	3 ms

**Analogue inputs**

Measurement range	-10 V ... +10 V, 0 V ... 10 V, 0 ... 20 mA, 4...20 mA
Maximum input voltage in relation to GND	35 V
Input resistance (load)	<125 Ohm
Max. input current (differential)	-50 mA to +50 mA (protected against polarity reversal)
Short-circuit-proof	Yes
Resolution / Accuracy	12-bit / < 0.2 %

**Analogue outputs**

Measurement range	-10 V ... +10 V, 0 V ... 10 V, 0 ... 20 mA, 4...20 mA
Output interval	5 ms to 250 ms (can be configured)
Short-circuit-proof	Yes
Resolution / Accuracy	12-bit / < 0.2 %

**Fieldbus**

Bus system	DeviceNet™
Transmission rate	Max. 500 kBit/s (automatic detection)
Addressing	Via rotary coding switch (0 – 63)
System integration	EDS file (Device-specific for each module)

**General data**

L x W x H	210 mm / 54 mm / 32 mm
Earth	< 400 g
Protection degree	IP 67
Operating temperature	0 °C...+60 °C
Storage temperature	-25 °C...+85 °C
Housing main material / UL 94 flammability rating	Pocan, PBT / V-0
Certificate	CE, cULus

**Note**



# Engineering tables for DeviceNet™

When planning the automation of a facility, you must have a wide variety of components available.

These engineering tables list all the components required for wiring up the SAI Active modules.

## DeviceNet™ modules



## DeviceNet™ accessories



## Sensor/actuator accessories



## Markers



## Protective caps



## Ordering data

Description	Type	Qty.	Order No.
<b>DeviceNet™ modules</b>			
16 Digital In	SAI-AU M12 DN 16DI	1	1906700000
16 Digital In / 8 Digital Out	SAI-AU M12 DN 16DI/8DO	1	1906710000
4 Analogue In / 2 Analogue Out / 4 Digital In	SAI-AU M12 DN AI/AO/DI	1	1906720000
16 Digital In	SAI-AU M8 DN 16DI	1	1906730000
16 Digital In / 8 Digital Out	SAI-AU M8 DN 16DI/8DO	1	1906740000

## DeviceNet™ accessories

DeviceNet™ cables with female plug and male plug	Chapter C
DeviceNet™ cables with female plug and other side open	Chapter C
DeviceNet™ cables with male plug and other side open	Chapter C
DeviceNet™ plug-in connector	Chapter C
DeviceNet™ terminating resistor	SAIEND CAN-M12 5P A-COD
	1 1784760000

## Sensor/actuator accessories

Sensor-actuator cables	Chapter B
Sensor-actuator plugs	Chapter D

## Markers

Semi-transparent markers for PrintJet printing	ESG 8/13.5/43.3 SAI AU	5	1912130000
--	------------------------	---	------------

## Protective caps

M8 Dust cap (Sensor connections)	SAI-SK M8	50	1802760000
M12 Dust cap (Sensor connections)	SAI-SK	30	9456050000
M12 Dust cap (Bus-out and power-out)	SAI-SK-M12-UNI	20	2330260000
M12 Dust cap (Bus-in and power-in)	SAI-SK plug M12	50	1781520000




# SAI Active Universal Pro

## Professional versions of the Remote I/O System featuring IP 67 protection

The modules in the SAI Active Universal Pro systems provide additional I/O and functional modules for more versatile topologies. The extension modules come in a compact, space-saving design. They can also be mounted on the side because of the additional drilled holes in the side of the housing. Up to 15 extension modules can be connected over a distance of 50 metres using a shielded, standard M8 sensor cable and the SAI fieldbus module.


In addition to the digital input and output modules, we also offer counter unit modules, thermal modules, RTD modules and analogue modules. The digital input and output modules are also available in M8 and M12 variants. The analogue modules and functional modules are available with M12 connections. Markers are included with every SAI Active module for labelling the I/O channels and the entire device. These markers can be printed on using the PrintJet system from Weidmüller.





### Cost-effective Subbus system

Subbus modules are wired up using conventional, shielded, standard M8 sensor cables. Thus there is no need for expensive custom cables. The extension modules enable versatile expansion and minimise the costs associated with the fieldbus interface. The modules do not, however, detract from the performance of the fieldbus system.




### Integration with an industrial PC

Weidmüller offers an SAI Active Universal Pro module with USB and RS232 interfaces especially for controllers or industrial PCs without any Fieldbus connection. A driver is used to set up the connection; communication is based on the standard Modbus ASCII format. All available extension modules can be used on these components and can be accessed via the controller.



### Simplified installation

The modules have a compact, space-saving design with additional holes drilled on the side of the housing: this allows them to be installed in a quick and versatile manner. All SAI Active modules with digital inputs or digital outputs are optionally available with standard M8 or M12 connection systems. The outputs are short-circuit-proof and protected against polarity reversal.



### Efficient engineering

All Pro-System modules are described in the standardised fieldbus specific device description files. They can be integrated into any controller unit and corresponding engineering system regardless of the particular manufacturer. The configuration (whether for the input, DESINA input, or output) is carried out without any additional software. Any user can configure directly from the engineering system.

## Gateway modules with digital inputs

**SAI-AU GW****SAI-AU GW**

### Ordering data

Module variants	16 Digital In
<b>Note</b>	

Type	Qty.	Order No.
SAI-AU M12 PB GW 16DI	1	1938550000

Type	Qty.	Order No.
SAI-AU M8 PB GW 16DI	1	1024310000

### Technical data

#### Connections

Fieldbus (BUS-IN)  
Fieldbus (BUS-OUT)  
Supply voltage (AUX-IN)  
Connection to Subbus (SUB-OUT)  
I/O connections

1x M12 plug 5-pole, B-coded  
1x M12 female 5-pole, B-coded  
1x M12 plug 5-pole, A-coded  
1 x M8 female 4-pole, A-coded  
8 x M12 socket 5-pole, A-coded

1x M12 plug 5-pole, B-coded  
1x M12 female 5-pole, B-coded  
1x M12 plug 5-pole, A-coded  
1 x M8 female 4-pole, A-coded  
16x M8 female 3-pole

#### Voltage supply

Operating voltage  
Contact load  
Max. total current module

24 V (18 V DC ... 30 V DC)  
Per PIN max. 4 A  
8 A

24 V (18 V DC ... 30 V DC)  
Per PIN max. 4 A  
8 A

#### Digital inputs

Permitted input voltage  
Input current, low  
Input current, high  
Input current, low  
Input current, high  
Input filter

-30 V to +30 V (protected against polarity reversal)  
< 15 mA in accordance with EN 61131-2 Type 1  
2 mA to 15 mA in accordance with EN 61131-2 Type 1  
< 15 mA in accordance with EN 61131-2 Type 1  
2 mA to 15 mA in accordance with EN 61131-2 Type 1  
1 ms, 3 ms, 5 ms, 10 ms, Configurable

-30 V to +30 V (protected against polarity reversal)  
< 15 mA in accordance with EN 61131-2 Type 1  
2 mA to 15 mA in accordance with EN 61131-2 Type 1  
< 15 mA in accordance with EN 61131-2 Type 1  
2 mA to 15 mA in accordance with EN 61131-2 Type 1  
1 ms, 3 ms, 5 ms, 10 ms, Configurable

#### Fieldbus

Bus system  
Transmission rate  
Addressing  
System integration  
**General data**  
L x W x H  
Earth  
Protection degree  
Operating temperature  
Storage temperature  
Housing main material / UL 94 flammability rating  
Certificate

Profibus-DP  
Max. 12 Mbit/s (automatic detection)  
Via rotary coding switch (1 – 126)  
GSD file  
210 mm / 54 mm / 32 mm  
< 350 g  
IP 67  
0 °C...+60 °C  
-25 °C...+85 °C  
Pocan, PBT / V-O  
CE, cULus

Profibus-DP  
Max. 12 Mbit/s (automatic detection)  
Via rotary coding switch (1 – 126)  
GSD file  
210 mm / 54 mm / 32 mm  
< 350 g  
IP 67  
0 °C...+60 °C  
-25 °C...+85 °C  
Pocan, PBT / V-O  
CE, cULus

#### Note



# Engineering tables for PROFIBUS

When planning the automation of a facility, you must have a wide variety of components available.

These engineering tables list all the components required for wiring up the SAI Active modules.

## PROFIBUS modules



## PROFIBUS accessories



## Subbus cables / terminating resistor



## Sensor/actuator accessories



## Markers



## Protective caps



## Ordering data

Description	Type	Qty.	Order No.
<b>PROFIBUS modules</b>			
PROFIBUS Gateway M12	SAI-AU M12 PB GW 16DI	1	1938550000
PROFIBUS Gateway M8	SAI-AU M8 PB GW 16DI	1	1024310000
Subbus module	SAI-AU M12 SB 8DI	1	1938610000
Subbus module	SAI-AU M12 SB 8DI/8DO	1	1938640000
Subbus module	SAI-AU M8 SB 8DI	1	1938600000
Subbus module	SAI-AU M8 SB 8DI/8DO	1	1938630000
Subbus module	SAI-AU M12 SB AI	1	1938690000
Subbus module	SAI-AU M12 SB AO	1	1938700000
Subbus module	SAI-AU M12 SB PT100	1	1938710000
Subbus module	SAI-AU M12 SB Thermo	1	1938720000
Subbus module	SAI-AU M12 SB Zähler	1	1938730000
Subbus module	SAI-AU M8 SB 8DO 2A	1	1938660000
Subbus module	SAI-AU M12 SB 8DO 2A	1	1938680000
<b>PROFIBUS accessories</b>			
PROFIBUS cables with female plug and male plug			Chapter C
PROFIBUS cables with female plug and other side open			Chapter C
PROFIBUS cables with male plug and other side open			Chapter C
PROFIBUS plug-in connector			Chapter C
PROFIBUS terminating resistor	SAIEND PB M12 5P B-COD	1	1784770000
<b>Subbus cables / Terminating resistor</b>			
Subbus cables			Chapter C
Subbus terminating resistor	SAIEND CAN M8 4P	1	1955340000
<b>Sensor/actuator accessories</b>			
Sensor-actuator cables			Chapter B
Sensor-actuator plugs			Chapter D
<b>Markers</b>			
Semi-transparent markers for PrintJet printing	ESG 8/13.5/43.3 SAI AU	5	1912130000
<b>Protective caps</b>			
M8 Dust cap (Sensor connections)	SAI-SK M8	50	1802760000
M12 Dust cap (Sensor connections)	SAI-SK	30	9456050000
M12 Dust cap (Bus-out and power-out)	SAI-SK-M12-UNI	20	2330260000
M12 Dust cap (Bus-in and power-in)	SAI-SK plug M12	50	1781520000

## Gateway modules with digital inputs

**SAI-AU GW**

### Ordering data

Module variants	Type	Oty.	Order No.
16 Digital In	SAI-AU M12 DN GW 16DI	1	<b>1938570000</b>

### Note

### Technical data

Connections	1x M12 plug 5-pole, A-coded 1x M12 female 5-pole, A-coded 1x M12 plug 5-pole, A-coded 1 x M8 female 4-pole, A-coded 8 x M12 socket 5-pole, A-coded
Operating voltage	24 V (18 V DC ... 30 V DC)
Contact load	Per PIN max. 4 A
Max. total current module	8 A
Digital inputs	-30 V to +30 V (protected against polarity reversal) < 15 mA in accordance with EN 61131-2 Type 1 2 mA to 15 mA in accordance with EN 61131-2 Type 1 < 15 mA in accordance with EN 61131-2 Type 1 2 mA to 15 mA in accordance with EN 61131-2 Type 1 1 ms, 3 ms, 5 ms, 10 ms, Configurable
Fieldbus	DeviceNet Max. 500 kBit/s (automatic detection) Via rotary coding switch (0 – 63) EDS file
General data	L x W x H 210 mm / 54 mm / 32 mm Earth < 350 g IP 67 0 °C...+60 °C -25 °C...+85 °C Housing main material / UL 94 flammability rating Pocan, PBT / V-0 Certificate CE, cULus

### Note



# Engineering table for DeviceNet™

When planning the automation of a facility, you must have a wide variety of components available.

These engineering tables list all the components required for wiring up the SAI Active modules.

## DeviceNet™ and EtherNet/IP™ modules



## DeviceNet™ and EtherNet/IP™ accessories



## Subbus cables / terminating resistor



## Sensor/actuator accessories



## Markers



## Protective caps



## Ordering data

Description	Type	Qty.	Order No.
<b>DeviceNet™ and EthernetIP™ modules</b>			
DeviceNet™ Gateway	SAI-AU M12 DN GW 16DI	1	1938570000
Subbus module	SAI-AU M12 SB 8DI	1	1938610000
Subbus module	SAI-AU M12 SB 8DI/8DO	1	1938640000
Subbus module	SAI-AU M8 SB 8DI	1	1938600000
Subbus module	SAI-AU M8 SB 8DI/8DO	1	1938630000
Subbus module	SAI-AU M12 SB AI	1	1938690000
Subbus module	SAI-AU M12 SB AO	1	1938700000
Subbus module	SAI-AU M12 SB PT100	1	1938710000
Subbus module	SAI-AU M12 SB Thermo	1	1938720000
Subbus module	SAI-AU M12 SB Zähler	1	1938730000
Subbus module	SAI-AU M8 SB 8DO 2A	1	1938660000
Subbus module	SAI-AU M12 SB 8DO 2A	1	1938680000

## DeviceNET™ and EthernetIP™ accessories

DeviceNet™ cables with female plug and male plug	Chapter C
DeviceNet™ cables with female plug and other side open	Chapter C
DeviceNet™ cables with male plug and other side open	Chapter C
DeviceNet™ plug-in connector	Chapter C
DeviceNet™ terminating resistor	SAIEND CAN-M12 5P A-COD
	1 1784760000

## Subbus cables / Terminating resistor

Subbus cables	Chapter C
Subbus terminating resistor	SAIEND CAN M8 4P
	1 1955340000

## Sensor/actuator accessories

Sensor-actuator cables	Chapter B
Sensor-actuator plugs	Chapter D

## Markers

Semi-transparent markers for PrintJet printing	ESG 8/13.5/43.3 SAI AU	5	1912130000
---	------------------------	---	------------

## Protective caps

M8 Dust cap (Sensor connections)	SAI-SK M8	50	1802760000
M12 Dust cap (Sensor connections)	SAI-SK	30	9456050000
M12 Dust cap (Bus-out and power-out)	SAI-SK-M12-UNI	20	2330260000
M12 Dust cap (Bus-in and power-in)	SAI-SK plug M12	50	1781520000

## Gateway modules with digital inputs / outputs



### SAI-AU GW



#### Ordering data

Module variants	Type	Oty.	Order No.
16 Digital In; 8 Digital In / 8 Digital Out	SAI-AU M12 USB GW 8180	1	1962240000

#### Note

#### Technical data

Connections	1x M12 plug 5-pole, B-coded (BUS-USB) 1x M12 female 5-pole, B-coded (BUS-RS232) 1x M12 plug 5-pole, A-coded 1 x M8 female 4-pole, A-coded 8 x M12 socket 5-pole, A-coded
Voltage supply	24 V (18 V DC ... 30 V DC) Per PIN max. 4 A 8 A
Digital inputs	-30 V to +30 V (protected against polarity reversal) < 15 mA in accordance with EN 61131-2 Type 1 2 mA to 15 mA in accordance with EN 61131-2 Type 1 < 15 mA in accordance with EN 61131-2 Type 1 2 mA to 15 mA in accordance with EN 61131-2 Type 1 1 ms, 3 ms, 5 ms, 10 ms, Configurable
Digital outputs	0.5 A max. 100 Hz / max. 1 Hz / max. 8 Hz Yes, cut-off for short circuit and error message 0 V DC Supply voltage less 0.7 V DC 4 A
Fieldbus	Modbus ASCII (RS 232 / USB) 115.2 kBit/s Static Register
General data	210 mm / 54 mm / 32 mm < 350 g IP 67 0 °C...+60 °C -20 °C... Pocan, PBT / V-O CE, cULus

#### Note

# Engineering tables for Modbus ASCII via RS232 or USB

**Modbus-IDA**  
the architecture for distributed automation



When planning the automation of a facility, you must have a wide variety of components available.

These engineering tables list all the components required for wiring up the SAI Active modules.

## Modbus ASCII and USB modules



## Modbus ASCII and USB accessories



## Subbus cables / terminating resistor



## Sensor/actuator accessories



## Markers



## Protective caps



## Ordering data

Description	Type	Qty.	Order No.
<b>Modbus ASCII and USB modules</b>			
USB Gateway	SAI-AU M12 USB GW 8180	1	1962240000
Subbus module	SAI-AU M12 SB 8DI	1	1938610000
Subbus module	SAI-AU M12 SB 8DI/8DO	1	1938640000
Subbus module	SAI-AU M8 SB 8DI	1	1938600000
Subbus module	SAI-AU M8 SB 8DI/8DO	1	1938630000
Subbus module	SAI-AU M12 SB AI	1	1938690000
Subbus module	SAI-AU M12 SB AO	1	1938700000
Subbus module	SAI-AU M12 SB PT100	1	1938710000
Subbus module	SAI-AU M12 SB Thermo	1	1938720000
Subbus module	SAI-AU M12 SB Zähler	1	1938730000
Subbus module	SAI-AU M8 SB 8DO 2A	1	1938660000
Subbus module	SAI-AU M12 SB 8DO 2A	1	1938680000

## Modbus ASCII and USB accessories

USB Module plug-in connector	Chapter C
------------------------------	-----------

## Subbus cables / Terminating resistor

Subbus cables	Chapter C
Subbus terminating resistor	SAIEND CAN M8 4P 1 1955340000

## Sensor/actuator accessories

Sensor-actuator cables	Chapter B
Sensor-actuator plugs	Chapter D

## Markers

Semi-transparent markers for PrintJet printing	ESG 8/13.5/43.3 SAI AU	5	1912130000
---	------------------------	---	------------

## Protective caps

M8 Dust cap (Sensor connections)	SAI-SK M8	50	1802760000
M12 Dust cap (Sensor connections)	SAI-SK	30	9456050000
M12 Dust cap (Bus-out and power-out)	SAI-SK-M12-UNI	20	2330260000
M12 Dust cap (Bus-in and power-in)	SAI-SK plug M12	50	1781520000

### Subbus modules with digital inputs/outputs

#### SAI-AU Digital



cUL  
LISTED  
IND.CONTEQ  
1V03

#### SAI-AU Digital



cUL  
LISTED  
IND.CONTEQ  
1V03

### Ordering data

Module variants
8 Digital In; 8 Digital In / 8 Digital Out
8 Digital In; 8 Digital In / 8 Digital Out
8 Digital Out 2A
8 Digital Out 2A

Note

### Technical data

Connections
Supply voltage (AUX-IN)
Connection to Subbus (SUB-IN)
Connection to Subbus (SUB-OUT)
I/O connections
Voltage supply
Operating voltage
Contact load
Max. total current module
Digital inputs
Permitted input voltage
Input current, low
Input current, high
Input current, low
Input current, high
Input filter
Separation of potentials to module electronics
Digital outputs
max. current-carrying capacity per output signal
Separation of potentials to module electronics
Switching frequency, resistive load
Switching frequency, inductive load
Switching frequency, lamp load
Short-circuit-proof
Output voltage, low
Output voltage, high
Max. total current outputs
Fieldbus
Bus system
Addressing
System integration
General data
L x W x H
Earth
Protection degree
Operating temperature
Storage temperature
Housing main material / UL 94 flammability rating
Certificate

Note



**Subbus modules with functional inputs****SAI-AU Counter****Ordering data**

Module variants	2 counter inputs / 2 gate outputs
<b>Note</b>	

Type	Oty.	Order No.
SAI-AU M12 SB 2Counter	1	<b>1938730000</b>

**Technical data**

Connections	Supply voltage (AUX-IN) Connection to Subbus (SUB-IN) Connection to Subbus (SUB-OUT) I/O connections
<b>Voltage supply</b>	Operating voltage Contact load Max. total current module
<b>Functional inputs</b>	Counting breadth Switching frequency Number of inputs
<b>Fieldbus</b>	Bus system Addressing System integration
<b>General data</b>	L x W x H Earth Protection degree Operating temperature Storage temperature Housing main material / UL 94 flammability rating Certificate

1x M12 plug 5-pole, A-coded 1 x M8 plug 4-pole, A-coded 1 x M8 female 4-pole, A-coded 4 x M12 female, 5-pole A-coded
24 V (18 V DC ... 30 V DC)
Per PIN max. 4 A
8 A
32 Bit
100 kHz
2 x enables, 2 x counters, 2 x count directions
Subbus
automatic
automatic
180 mm / 30 mm / 32 mm
< 200 g
IP 67
0 °C...+60 °C
-25 °C...+85 °C
Pocan, PBT / 5VA
CE, cULus

**Note****Note**

**Subbus modules with functional inputs****SAI-AU Thermo****Ordering data**

Module variants	4 thermal inputs
Note	

Type	Oty.	Order No.
SAI-AU M12 SB 4Thermo	1	1938720000

**Technical data****Connections**

Connection to Subbus (SUB-IN)  
Connection to Subbus (SUB-OUT)

**I/O connections****Voltage supply**

Operating voltage

**Functional inputs**

Sensor  
Temperature range  
Resolution  
Conversion time  
Measurement error  
Input filter  
cold junction compensation

**Fieldbus**

Bus system  
Addressing  
System integration

**General data**

L x W x H  
Earth  
Protection degree  
Operating temperature  
Storage temperature  
Housing main material / UL 94 flammability rating  
Certificate

**Connections**

1 x M8 plug 4-pole, A-coded  
1 x M8 female 4-pole, A-coded

4 x M12 female, 5-pole A-coded

24 V (18 V DC ... 30 V DC)

Types J, K, L, B, E, N, R, S, T, U: mV readings

Typical for sensor, Preset Type K, -100 °C to 1,370 °C

0.1 °C per digit

250 ms (can be configured to 70 ms)

&lt; ± 0.5% (of measuring range limit)

Configurable

External PT1000 connection on pins 1 and 3 (GND)

**Subbus**

automatic

automatic

155 mm / 30 mm32 mm

&lt; 200 g

IP 67

0 °C...+60 °C

-25 °C...+85 °C

Pocan, PBT / 5VA

CE, cULus

**Note**

**Subbus modules with functional inputs****SAI-AU PT100****Ordering data**

Module variants	Type	Oty.	Order No.
4 PT100 inputs	SAI-AU M12 SB 4PT100	1	1938710000

**Note****Technical data****Connections**

Connection to Subbus (SUB-IN)  
Connection to Subbus (SUB-OUT)

**I/O connections****Voltage supply**

Operating voltage

**Functional inputs**

Sensor

Resolution

Conversion time

Measurement error

Input filter

Measurement range for PT sensors

Measurement range for Ni sensors

Resistance measurement

Potentiometer

Measurement current

**Fieldbus**

Bus system

Addressing

System integration

**General data**

L x W x H

Earth

Protection degree

Operating temperature

Storage temperature

Housing main material / UL 94 flammability rating

Certificate

**1 x M8 plug 4-pole, A-coded****1 x M8 female 4-pole, A-coded****4 x M12 female, 5-pole A-coded****24 V (18 V DC ... 30 V DC)**

N100, N1000, N120, PT100, PT1000, PT200, PT300, PT500,  
Potentiometer connection, Resistance measurement

0.1 °C per digit

250 ms (can be configured to 65 ms)

&lt; ± 1 °C

Configurable

-200 °C ... + 850 °C

-60 °C ... +250 °C

max. 4000 Ohm

100 to 4000 Ω (three-wire connection)

Typically 0.5 mA

**Subbus**

automatic

automatic

**155 mm / 30 mm / 32 mm****< 200 g****IP 67****0 °C...+60 °C****-25 °C...+85 °C****Pocan, PBT / 5VA**

CE, cULus

**Note**



# SAI Active Universal Wireless

## Wireless versions of the Remote I/O System with IP 67 protection

Weidmüller offers a remote wireless solution – the SAI Active Universal Wireless series – for providing radio-based communication to movable facility units. The remote modules form a safe, wireless I/O communications network and thus completely replace drag lines containing bus cables or interference-prone slip-ring assemblies. Maintenance and servicing is reduced because no communication cables are needed. Potential sources of error, such as broken shielding in the communication cables, are eliminated all together. Thus the user benefits from long-term cost savings. He requires neither new cables nor installation material for the new communication system. For the engineering system, the change to a wireless system is transparent; it behaves in an identical manner as the cable bound SAI Active Universal Pro System. No complex programming using proprietary software is required. Safe and reliable operations are ensured by the comprehensive diagnostics options on the module and through the higher-level controller.

All wireless modules feature integrated radio-wave antennae and IP 67 protection. They may be used directly in surroundings containing hazardous substances or humidity. The wireless modules bring together the required inputs and outputs in a very compact size. This ensures that the robot arms are not weighted down with bulky modules, additional components or external antennae. The wireless fieldbus module is a master module responsible for establishing communication with the higher-level controller unit and with the wireless I/O (slave) modules. Various slave modules with digital and analogue inputs and outputs are available and enable exact adjustments to the requirements of a given application. The wireless connection between the modules is established automatically and remains invisible to other wireless devices. This ensures that there will be no interference on the connection. The output power and, thus, the range, can be set individually on the module.






### Can be used instead of bus cables in drag line or slip chains

In non-stationary applications, a wireless connection can be used instead of the error prone drag-line-based bus cable or slip chain transmission. This helps to minimise facility downtimes and reduce costs for maintenance, installation and materials. The SAI wireless system has a similar handling method compared to cable bound systems so installation is simple and safe.

**Bluetooth  
WLAN  
ZigBee**


### Coexistence with other wireless systems

The wireless modules transmit in the license free ISM frequency band. This allows them to be used throughout the world. Integrated wireless mechanisms ensure that the modules can be operated at the same time as other wireless systems from other vendors. This ensures communication with no interference and also allows the system to coexist alongside other wireless systems (such as WLAN, ZigBee or Bluetooth).



### A maximum of 186 modules can be used simultaneously.

The SAI Active Universal Wireless System allows 31 wireless fieldbus modules to be operated simultaneously with six remote I/O modules each. This makes it possible to design an automation solution that can process up to 3348 digital signals. Standardised device description files are provided so that the modules can be integrated into other systems not manufactured by Weidmüller. No special proprietary software is required.



### A wide variety of variants

In addition to the fieldbus wireless module with 12 already integrated digital input channels, the SAI Active Universal Wireless product family encompasses other wireless I/O modules with up to 16 digital inputs, up to 8 of which can be configured and used by the user as outputs. A mixed module with both digital and analogue inputs and outputs is also available.

### Wireless gateway with digital inputs



### Wireless gateway



#### Ordering data

Module variants	Type	Qty.	Order No.
12 Digital In	SAI-AU M12 GW PB/BT 12I	1	1006980000

#### Note

#### Technical data

Connections	1x M12 plug 5-pole, B-coded 1x M12 female 5-pole, B-coded 1x M12 plug 5-pole, A-coded 1x M12 female 5-pole, A-coded 6x M12 female 5-pole
Voltage supply	24 V DC (18 V DC ... 30 V DC) Per PIN max. 4 A
Digital inputs	-30 V to +30 V (protected against polarity reversal) < 15 mA in accordance with EN 61131-2 Type 1 2 mA to 15 mA in accordance with EN 61131-2 Type 1 < 15 mA in accordance with EN 61131-2 Type 1 2 mA to 15 mA in accordance with EN 61131-2 Type 1 1 ms, 3 ms, 5 ms, 10 ms, Configurable
Fieldbus	Profibus-DP GSD file / WIAU0A75.GSD In accordance with the PROFIBUS specification Via rotary coding switch (1 – 126) Max. 31 wireless gateways
Properties of radio system	2.401 GHz ... 2.480 GHz / 1 to 79 channels (can be configured) 0 dBm to 20 dBm / max 100 mW (can be configured)
General data	210 mm / 54 mm / 52 mm < 400 g IP 67 0 °C...+60 °C -25 °C...+85 °C PBT, Pocan / V-0 CE

#### Note



# Engineering tables for PROFIBUS

When planning the automation of a facility, you must have a wide variety of components available.

These engineering tables list all the components required for wiring up the SAI Wireless modules.

## PROFIBUS modules



## PROFIBUS accessories



## Sensor/actuator accessories



## Markers



## Protective caps



## Ordering data

Description	Type	Qty.	Order No.
<b>PROFIBUS modules</b>			
Gateway module with 12 Digital In	SAI-AU M12 GW PB/BT 12I	1	1006980000
Subbus module with 16 Digital In	SAI-AU M12 BT 16DI	1	1006940000
Subbus module with 16 Digital In / 8 Digital Out	SAI-AU M12 BT 16DI/8DO	1	1006930000
Subbus module with 4 Analogue In / 2 Analogue Out / 2 Digital In / 2 Digital Out	SAI-AU M12 BT4AI2A02DIO	1	1006920000
<b>PROFIBUS accessories</b>			
PROFIBUS cables with female plug and male plug			Chapter C
PROFIBUS cables with female plug and other side open			Chapter C
PROFIBUS cables with male plug and other side open			Chapter C
PROFIBUS plug-in connector			Chapter C
PROFIBUS terminating resistor	SAIEND PB M12 5P B-COD	1	1784770000
<b>Sensor/actuator accessories</b>			
Sensor-actuator cables			Chapter B
Sensor-actuator plugs			Chapter D
<b>Markers</b>			
Semi-transparent markers for PrintJet printing	ESG 8/13.5/43.3 SAI AU	5	1912130000
<b>Protective caps</b>			
M12 Dust cap (Sensor connections)	SAI-SK	30	9456050000
M12 Dust cap (Bus-out and power-out)	SAI-SK-M12-UNI	20	2330260000
M12 Dust cap (Bus-in and power-in)	SAI-SK plug M12	50	1781520000

### Wireless slave modules for digital signal processing



### Ordering data

Module variants	Type	Qty.	Order No.
16 Digital In; 16 Digital In / 8 Digital Out	SAI-AU M12 BT 16DI	1	1006940000
16 Digital In / 8 Digital Out			

### Note

### Technical data

#### Connections

Supply voltage (AUX-IN)  
Supply voltage (AUX-OUT)

I/O connections

#### Voltage supply

Operating voltage  
Contact load

#### Digital inputs

Permitted input voltage  
Input current, low  
Input current, high  
Input current, low  
Input current, high  
Input filter

#### Fieldbus

Bus system  
System integration  
Range of coverage  
Addressing  
Communication coexistence

#### Properties of radio system

Frequency band / Channel usage  
Transmit power  
**General data**  
L x W x H  
Earth  
Protection degree  
Operating temperature  
Storage temperature  
Housing main material / UL 94 flammability rating  
Certificate

### Wireless slave



### Wireless slave

M12



Type	Qty.	Order No.
SAI-AU M12 BT 16DI/8DO	1	1006930000

Type	Qty.	Order No.
SAI-AU M12 BT 16DI/8DO	1	1006930000

2x M12 plug 5-pole, A-coded

8 x M12 socket 5-pole, A-coded

24 V DC (18 V DC ... 30 V DC)

Per PIN max. 4 A

-30 V to +30 V (protected against polarity reversal)

< 15 mA in accordance with EN 61131-2 Type 1

2 mA to 15 mA in accordance with EN 61131-2 Type 1

< 15 mA in accordance with EN 61131-2 Type 1

2 mA to 15 mA in accordance with EN 61131-2 Type 1

1 ms, 3 ms, 5 ms, 10 ms, Configurable

Radio in ISM band

automatic

Max. 100 m (open air), Max. 50 m (industrial surroundings)

Via rotary coding switch

Max. 186 (for 31 wireless gateways each with 6 wireless slaves)

2.401 GHz ... 2.480 GHz / 1 to 79 channels (can be configured)

0 dBm to 20 dBm / max 100 mW (can be configured)

210 mm / 54 mm / 52 mm

< 400 g

IP 67

0 °C...+60 °C

-25 °C...+85 °C

PBT, Pocan / V-O

CE

### Note

## Wireless slave module for digital and analogue signal processing



### Wireless slave

M12



### Ordering data

4 Analogue In / 2 Analogue Out / 2 Digital In / 2 Digital Out

#### Note

Type	Qty.	Order No.
SAI-AU M12 BT4AI2AO2DIO	1	1006920000

### Technical data

#### Connections

Supply voltage (AUX-IN)

Supply voltage (AUX-OUT)

I/O connections

#### Voltage supply

Operating voltage

Contact load

Max. total current module

#### Digital inputs

Permitted input voltage

Input current, low

Input current, high

Input current, low

Input current, high

Input filter

#### Digital outputs

max. current-carrying capacity per output signal

Switching frequency load (resistive / inductive / inrush)

Short-circuit-proof

Output voltage, low / Output voltage, high

Max. total current outputs

#### Analogue inputs

Measurement range

Maximum input voltage in relation to GND

Input resistance (load)

Max. input current (differential)

Short-circuit-proof

Resolution / Accuracy

#### Analogue outputs

Measurement range

Output interval

Short-circuit-proof

Resolution / Accuracy

#### Fieldbus

Bus system

System integration

Range of coverage

Addressing

Communication coexistence

#### Properties of radio system

Frequency band / Channel usage

Transmit power

#### General data

L x W x H

Earth

Protection degree

Operating temperature

Storage temperature

Housing main material / UL 94 flammability rating

Certificate

1x M12 plug 5-pole, A-coded

1x M12 female 5-pole, A-coded

8 x M12 socket 5-pole, A-coded

24 V DC (18 V DC ... 30 V DC)

Per PIN max. 4 A

8 A

-30 V to +30 V (protected against polarity reversal)

&lt; 15 mA in accordance with EN 61131-2 Type 1

2 mA to 15 mA in accordance with EN 61131-2 Type 1

&lt; 15 mA in accordance with EN 61131-2 Type 1

2 mA to 15 mA in accordance with EN 61131-2 Type 1

1 ms, 3 ms, 5 ms, 10 ms, Configurable

0.5 A

max. 100 Hz / max. 1 Hz / max. 8 Hz

Yes, cut-off for short circuit and error message

0 V DC / Supply voltage less 0.7 V DC

1 A

-10 V ... +10 V, 0 V ... 10V, 0 ... 20 mA, 4...20 mA

35 V

&lt;125 Ohm

-50 mA to +50 mA (protected against polarity reversal)

Yes

12-bit / &lt; 0.2 %

-10 V ... +10 V, 0 V ... 10V, 0 ... 20 mA, 4...20 mA

20 ms to 250 ms (can be configured)

Yes

12-bit / &lt; 0.2 %

Radio in ISM band

automatic

Max. 100 m (open air), Max. 50 m (industrial surroundings)

Via rotary coding switch

Max. 186 (for 31 wireless gateways each with 6 wireless slaves)

2.401 GHz ... 2.480 GHz / 1 to 79 channels (can be configured)

0 dBm to 20 dBm / max 100 mW (can be configured)

210 mm / 54 mm / 52 mm

&lt; 400 g

IP 67

0 °C...+60 °C

-25 °C...+85 °C

Pocan, PBT / V-0

CE

#### Note



# SAI empty housing

---

<b>SAI empty housing</b>	
The Art of Making the Right Choice	G.2
The advantages at a glance	G.4
Technical description of individual components	G.5
Ordering data	G.6
Technical Information	G.11
Assembly steps for the SAI Universal Housing Set	G.12
SAI AU Housing Types	G.13
Drawings	G.14

---

## The Art of Making the Right Choice


There are numerous types of electronics housings available for the mounting rail with IP 20 protection. This opens up a whole range of options for users. The situation is completely different, however, when working with IP 67. Here the persistent question is how to keep liquids and dusts from penetrating the housing. Many products rely on encapsulation for this protection. When used daily, this is not problematic. But for small batches and for productions where encapsulation is not carried out daily, this technique can present a real obstacle.

Therefore Weidmüller has developed a housing range with absolutely no encapsulation. This also offers the option of using the circuit boards in reflow soldering since the required M12s are available as tray-packaged THT parts.

In the event of problems with the electronic circuitry after assembly, the housing can be re-opened to search for possible causes on the PCB.


The modules are only 54 mm wide and are normally supplied with 8 x M12 connectors along one side. On the bus and supply sides 4 connectors may be fitted. Both areas are separated with a transparent cover which allows settings to be made after they have been assembled.

It is worth highlighting the M12 Reflow-capable PCB plug-in connectors, which can be used in a sustained operating temperature of 105 °C. These are also available individually for use in an individually designed housing application.



Another variant consists of a small housing with two M12 connectors. Here small switches can be integrated easily to adapt to existing levels and the M12 connectors are already included. The housing is packed as a set with 100 pieces. The price refers to a set with 100 equal parts.

If these housing solutions do not offer a viable solution for the required application, Weidmüller may offer a customised housing. With our years of experience, we can even offer an affordable solution for low volume orders. How is this achieved? Please feel free to ask!



G

# The advantages at a glance

## Non-encapsulated housing

- Easy to assemble
- No encapsulation equipment needed
- Recyclable
- Disassembly for testing is possible

## M8/M12 connector

- Reflow-compatible I/O plug-in connector
- High long-term-use temperature
- I/O plug in tray
- M12 available with different coding

## Material

- Housing material laser-compatible PBT. This material is very resistant and sturdy.
- Threaded rings: nickel-plated brass – for secure attachment
- Machined, gold-plated contact – for high current capacity

## Service


- Housings can also be ordered as a set
- They can be laser-inscribed before delivery

## Components

- M12 and M8 connectors can also be ordered individually for use in your custom-designed housings

## Housings

- Light-guide rods are integrated into cover
- Mounting holes on top and side
- Address chamber can be illuminated
- Housings available in black or grey



# Technical description of individual components

It is possible to assemble three different housing types together. These variants have different widths and lengths. The first housing is 54 mm wide and 210.5 mm long. The second and third housing is always 30 mm wide and 155.5 mm or 180.5 mm long.

The following individual components are always required:

**54 mm**



**30 mm short shape**



**30 mm long shape**



**Designation**

- One frame
- One base
- One I/O cover
- One bus/supply cover
- One Functional Earth plate
- One address cover
- One address cover screw
- Ten circuit board screws

**Designation**

- One frame
- One base
- One cover
- One Functional Earth plate
- Six circuit board screws


**Designation**

- One frame
- One base
- One cover
- One Functional Earth plate
- Six circuit board screws

Added to this is the corresponding number of plug-in connector inserts. The quantity should be coordinated with the respective covers - with the I/O covers each requires different M12 plug-in connectors.

## SAI empty housing


## Ordering data

**54 mm****I/O cover**

With threaded bushing, without connector



Designation	Type	Qty.	Order No.
M12	SAI GHDE EA 8M12	25	1246490000
M12 shielded	SAI GHDE EA 8M12 SIBL	25	1246510000
M8	SAI GHDE EA 16M8 O.SIBL	25	1246520000

**Frame, address flap, screw for address flap, floor, shield panel**

Designation	Type	Qty.	Order No.
M12 shielded	SAI RA 54 KU	25	1246530000
Address cover	SAI AD 54	50	1966170000
Screw for address cover	SAI BFSC M3x10	1	4310920000
Base	SAI BP 54 KU	50	1966190000
Functional earth plate	SAI SIBL GH	250	1966200000

**LP screws**

Designation	Type	Qty.	Order No.
Screw for attachment to circuit board	PTSC 25X12 WN5452	100	4311430000

**bus/supply cover, short**

With threaded bushing, without connector



Designation	Type	Qty.	Order No.
4 M12, 1 male, 3 female	SAI GHDE 4M12 1S3B	25	1246560000

You can find all variants on G.8

**O-rings for female sockets**

Designation	Type	Qty.	Order No.
M12	SAI O-RI 7.5X1.5 VI	5000	4311000000
M8	SAI O-RI 5.0X0.8 NBR	50000	4312340000

**M12 plug I/O**

Packaged in tray / reflow compatible



Designation	Type	Qty.	Order No.
Female A-Keyway 5 pole	B KOTR M12 5P A BU SAI	360	2326170000
Female D-Keyway 4 pole	B KOTR M12 4P D BU SAI	360	2341480000

## Ordering data

M8 plug I/O	Designation	Type	Qty.	Order No.
	Female M8 3 pole	B KOTR M8 3P BU SAI	360	2332380000
				
M12 plug, bus/supply side, short	Designation	Type	Qty.	Order No.
	Female A-Keyway 5 pole shielded	B KOTR B M12 5POL A BU	220	2350600000
	Male A-Keyway 5 pole shielded	B KOTR B M12 5POL A SF	220	2350610000
	Female B-Keyway 5 pole shielded	B KOTR B M12 5POL B BU	220	2350620000
	Male B-Keyway 5 pole shielded	B KOTR B M12 5POL B SF	220	2350630000
	Female D-Keyway 4 pole shielded	B KOTR B M12 4POL D BU	220	2350590000
				
M8 plug, bus/supply side, short	Designation	Type	Qty.	Order No.
	Female 4 poles shielded	B KOTR BUS M8 4POL BU	220	2350640000
				
Threaded bushings	Designation	Type	Qty.	Order No.
	Male M12	GWHUE BUS M12 SF SAI	1	4322760000
	Female M12	GWHUE BUS M12 BU SAI	1	4322750000
				
SET	Designation	Type	Qty.	Order No.
	M12 standard	SAI-AU ET SET M12 A COD	1	1235340000

## SAI empty housing


## Ordering data

G

<b>I/O cover (3M12   2 pin, 1 socket // 1M8   1 socket)</b>	Detailed technical drawing showing two circular ports (11), two rectangular ports (12), and two small circular ports (13). Dimensions: width 26.5, height 22.5, depth 15, and side clearance 24.
<b>I/O cover (3M12   1 pin, 2 socket)</b>	Detailed technical drawing showing one circular port (11), two rectangular ports (12), and two small circular ports (13). Dimensions: width 26.5, height 22.5, depth 15, and side clearance 24.
<b>LP I/O cover (4M12   2 pin, 2 socket)</b>	Detailed technical drawing showing four circular ports (11), two rectangular ports (12), and two small circular ports (13). Dimensions: width 26.5, height 22.5, depth 15, and side clearance 24.
<b>I/O cover (4M12   2 pin, 2 socket, turned)</b>	Detailed technical drawing showing four circular ports (11), two rectangular ports (12), and two small circular ports (13). Dimensions: width 26.5, height 22.5, depth 15, and side clearance 24.
<b>I/O cover (4M12   3 pin, 1 socket)</b>	Detailed technical drawing showing three circular ports (11), two rectangular ports (12), and two small circular ports (13). Dimensions: width 26.5, height 22.5, depth 15, and side clearance 24.
<b>I/O cover (4M12   1 pin, 3 socket)</b>	Detailed technical drawing showing one circular port (11), three rectangular ports (12), and two small circular ports (13). Dimensions: width 26.5, height 22.5, depth 15, and side clearance 24.

<b>Type</b>	SAI GHDE 3M12 1M8 SAI	<b>Qty.</b>	25	<b>Order No.</b>	1246540000
<b>Designation</b>	SAI GHDE 3M12 1S2B	<b>Qty.</b>	25	<b>Order No.</b>	1246550000
<b>Designation</b>	SAI GHDE 4M12 2S2B	<b>Qty.</b>	25	<b>Order No.</b>	1246570000
<b>Designation</b>	SAI GHDE 4M12 2X1S1B	<b>Qty.</b>	25	<b>Order No.</b>	1246580000
<b>Designation</b>	SAI GHDE 4M12 3S1B	<b>Qty.</b>	25	<b>Order No.</b>	1246590000
<b>Designation</b>	SAI GHDE 4M12 1S3B	<b>Qty.</b>	25	<b>Order No.</b>	1246560000

## Ordering data



## 30 mm short version

## Cover

With threaded bushing, without connector



Designation	Type	Qty.	Order No.
M12	SAI GHDE 30 S KU M12	20	1246810000
M12 shielded	SAI GHDE 30 S KU SI	20	1246820000
M8	SAI GHDE 30 S KU M8	20	1246830000

## Frame, floor



Designation	Type	Qty.	Order No.
Frame	SAI RA 30 SB KU	20	1246660000
Base	SAI BP 30 SB KU	20	1246840000

## LP screws



Designation	Type	Qty.	Order No.
Screw for attachment to circuit board	PTSC 25X12 WN5452	100	4311430000

## O-rings for female socket



Designation	Type	Qty.	Order No.
M12	SAI O-RI 7.5X1.5 VI	5000	4311000000
M8	SAI O-RI 5.0X0.8 NBR	50000	4312340000

## M12 plug I/O



Designation	Type	Qty.	Order No.
Female A-Keyway 5 pole	B KOTR M12 5P A BU SAI	360	2326170000
Female D-Keyway 4 pole	B KOTR M12 4P D BU SAI	360	2341480000


## bus/supply plug



Designation	Type	Qty.	Order No.
Female M8 4 pole	B KOTR BUS M8 4POL BU	220	2350640000
Male M8 4 pole	B KOTR BUS M8 4POL SF	220	2350650000

## SAI empty housing

### Ordering data



#### 30 mm long version

##### Cover

With threaded bushing, without connector



Designation	Type	Qty.	Order No.
M12	SAI GHDE 30 SB LA M12	20	1246670000
M12 shielded	SAI GHDE 30 SB LA SIBL	20	1246680000
M8	SAI GHDE 30 SB LA M8	20	1246690000

##### Frame, floor



Designation	Type	Qty.	Order No.
Frame	SAI RA 30 SB LA	20	1246720000
Base	SAI BP 30 SB LA	20	1246710000

##### LP screws



Designation	Type	Qty.	Order No.
Screw for attachment to circuit board	PTSC 25X12 WN5452	100	4311430000

##### O-rings for female socket



Designation	Type	Qty.	Order No.
M12	SAI O-RI 7.5X1.5 VI	5000	4311000000
M8	SAI O-RI 5.0X0.8 NBR	50000	4312340000

##### M12 plug I/O



Designation	Type	Qty.	Order No.
Female A-Keyway 5 pole	B KOTR M12 5P A BU SAI	360	2326170000
Female D-Keyway 4 pole	B KOTR M12 4P D BU SAI	360	2341480000

##### bus/supply plug



Designation	Type	Qty.	Order No.
Female M8 4 pole	B KOTR BUS M8 4POL BU	220	2350640000
Male M8 4 pole	B KOTR BUS M8 4POL SF	220	2350650000
Male M12 A-Keyway 5 pole	B KOTR B M12 5POL A SF	220	2350610000

# Technical Information

## O-rings

These are required for the M12 and M8 sockets when establishing a seal in compliance with IP 67. O-rings are required for the female sockets but not for the male plugs.

## Press

You will need a tool that can press the base in and close the housing without damaging it. Such a tool can be ordered through Weidmüller.

## Cover

The covers are fitted with either M12 or M8 threaded nuts. The corresponding inserts must be ordered separately.

## Connectors in tray

The I/O inserts are packaged and delivered in a tray. This makes them compatible with automatic placement processes.

All connector inserts offered in this product line can be reflow soldered.

The bus/supply inserts connectors are packaged and delivered in a box. They can also be reflow soldered.

## Circuit board screws

The circuit board screws are self-cutting screws. Be sure, during assembly, to tighten the screws in the specified order. Ten screws are needed for each circuit board in the 54 mm housings. Six screws are needed per board in the 30 mm housings.

## Sample housings

The Set article number can be used to order a 54 mm housing along with sufficient components for building a complete module. This is suitable for samples or small batches. A set consists of the following components: One I/O cover, bus/supply cover, address cover, screw for address cover, Functional Earth plate, frame, base, eight M12 A-Keyway female sockets, 10 M12 O-rings, two M12 A-Keyway female sockets, two M12 male A-Keyway as bus/supply plug.

## Colour


Housing parts can be ordered in either grey or black. The article numbers here specify the grey frame, grey base and black cover.

## Print

Customised printing is also possible on request. The inscription is made with a laser.

G

# Assembly steps for the SAI Universal Housing Set



## ① Assembling the frames and covers

### Assembly steps

Position the frame with I/O cover and the bus/supply cover in the holder. Snap the printed circuit board in the frame and screw it together with housing (**be sure to maintain the proper torque and tightening sequence**).

Screw torque: 0.6 Nm

### Tightening sequence

5	3	1	7	9
EA			Bus	
6	4	2	8	10

## ② Snap in the housing base

### Assembly steps

Use a press to snap the housing base into the housing frame.

## ③ Final assembly

### Assembly steps

1. Snap on the transparent cover
2. Screw on with 0.5 Nm torque
3. Attach the O-rings with a press
4. Snap on the Functional Earth plate
5. Add accessories (Multicard, protective caps, package inserts)


# SAI AU Housing Types

## SAI empty housing


Type	Designation	Order No.	Type	Qty.
I/O cover	54 mm			
	M12	1246490000	SAI GHDE EA 8M12	25
	M12 shielded	1246510000	SAI GHDE EA 8M12 SIBL	25
	M8	1246520000	SAI GHDE EA 16M8 O.SIBL	25
Frame set	Frame, address cover, screw for address cover, base			
	Frame	1246530000	SAI RA 54 KU	25
	Address cover	1966170000	SAI AD 54	50
	Corresponding screw	4310920000	SAI BFSC M3x10	1
	Base	1966190000	SAI BP 54 KU	50
	Functional Earth Plate	1966200000	SAI SIBL GH	250
PCB screws		1966180000	SAI BFSC M3x10	1000
Bus/supply cover	3 M12, 1 M8	1246540000	SAI GHDE 3M12 1M8 SAI	25
	3 M12 1 male, 2 female	1246550000	SAI GHDE 3M12 1S2B	25
	4 M12, 1 male 3 female	1246560000	SAI GHDE 4M12 1S3B	25
	4 M12, 2 male, 2 female	1246570000	SAI GHDE 4M12 2S2B	25
	4 M12 2X 1 male, 1 female	1246580000	SAI GHDE 4M12 2X1S1B	25
	4 M12 3 male, 1 female	1246590000	SAI GHDE 4M12 3S1B	25
	3 M12 1 PG9	1246610000	SAI GHDE 3M12 1PG9	25
O rings	M12	4311000000	SAI O-RI 7.5X1.5 VI	5000
	M8	4312340000	SAI O-RI 5.0X0.8 NBR	50000
M12 connector I/O	Female A-Keyway 5 pole	2326170000	B KOTR M12 5P A BU SAI	360
	Female D-Keyway 4 pole	2341480000	B KOTR M12 4P D BU SAI	360
M8 connector I/O		2332380000	B KOTR M8 3P BU SAI	360
M12 connector, bus/supply cover side	Female A-Keyway 5 pole	2350600000	B KOTR B M12 5POL A BU	220
	Male A-Keyway 5 pole	2350610000	B KOTR B M12 5POL A SF	220
	Female B-Keyway 5 pole shielded	2350620000	B KOTR B M12 5POL B BU	220
	Male B-Keyway 5 pole shielded	2350630000	B KOTR B M12 5POL B SF	220
	Female D-Keyway 4 pole shielded	2350590000	B KOTR B M12 4POL D BU	220
M8 connector	Female 4 pole shielded	2350640000	B KOTR BUS M8 4POL BU	220
SET	M12 standard	1235340000	SAI-AU ET SET M12 A COD	
Type	30 mm short			
Cover	M12	1246810000	SAI GHDE 30 S KU M12	20
	M12 shield	1246820000	SAI GHDE 30 S KU SI	20
	M8	1246830000	SAI GHDE 30 S KU M8	20
Frame set	Base	1246840000	SAI BP 30 SB KU	20
	Frame	1246660000	SAI RA 30 SB KU	20
PCB screws		1966180000	SAI BFSC M3x10	1000
O rings	M12	4311000000	SAI O-RI 7.5X1.5 VI	5000
	M8	4312340000	SAI O-RI 5.0X0.8 NBR	50000
M12 connector I/O	Female A-Keyway 5 pole	2326170000	B KOTR M12 5P A BU SAI	360
	Female D-Keyway 4 pole	2341480000	B KOTR M12 4P D BU SAI	360
	Female M8 4 pole	2350640000	B KOTR BUS M8 4POL BU	220
	Male M8 4 pole	2350650000	B KOTR BUS M8 4POL SF	220
Type	30 mm long			
Cover	M12	1246670000	SAI GHDE 30 SB LA M12	20
	M12 shielded	1246680000	SAI GHDE 30 SB LA SIBL	20
	M8	1246690000	SAI GHDE 30 SB LA M8	20
Frame set	Base	1246710000	SAI BP 30 SB LA	20
	Frame	1246720000	SAI RA 30 SB LA	20
PCB screws		1966180000	SAI BFSC M3x10	1000
O rings	M12	4311000000	SAI O-RI 7.5X1.5 VI	5000
	M8	4312340000	SAI O-RI 5.0X0.8 NBR	50000
M12 connector I/O	Female A-Keyway 4 pole	2326170000	B KOTR M12 5P A BU SAI	360
	Female A-Keyway 5 pole	2341480000	B KOTR M12 4P D BU SAI	360
	Female D-Keyway 4 pole	2350640000	B KOTR BUS M8 4POL BU	220
	Female M8 4 pole	2350650000	B KOTR BUS M8 4POL SF	220
	Male M8 4 pole	2350660000	B KOTR B M12 5POL A SF	220
	Male M12 A-Keyway 5 pole	2350610000	B KOTR B M12 5POL A SF	220

G


# I/O connector, plug M12




# I/O plug socket M12




## I/O plug pin M8




## I/O plug socket M8




## E/A plug socket M12




## E/A plug socket M8




## 30 mm housing, long




## 30 mm housing, short




# Free space 30 mm housing long with M12




# Free space 30 mm housing long with M8



# Free space 30 mm housing short with M8



# Free space 54 mm housing





# JACKPAC® (IP 67)

## JACKPAC® (IP 67)

JACKPAC® - Overview	H.2
JACKPAC® relay module	H.3
JACKPAC® timer	H.4
JACKPAC® signal inverter	H.5
JACKPAC® test	H.6
JACKPAC® - General Data and Accessories	H.7
Empty housing SAI JACKPAC® for custom built-in components	H.8

H

# The Concept

## The IP 20 Solution

Until now, all signal conditioning tasks were carried out by modules designed to IP 20. For their own protection, these needed to be installed in central switchgear cabinets. However, decentralised solutions that do not require large switchgear cabinets are increasingly being sought for use in modern-day industrial automation technology. It is true that shielded signals can be fed to the machinery via powerful fieldbus systems; but in each case, however, there remains an interconnecting cable between the subdistribution boards and the sensors/actuators are susceptible to interference from surrounding operations. As has always been the case, signals are still influenced by overvoltages and earth loops; interference pulses are superimposed on sensor signals and malfunctions can be initiated.


The result is that signal conditioning modules sealed to IP 20 require terminal boxes, such as switchgear cabinets, or even cost-intensive special solutions (for example, sensor-actuator distributors with integrated signal-conditioning functions providing as many functions as possible, even when these are surplus to requirements).

## The JACKPAC® Solution

By introducing **JACKPAC®**, the new M12 Signal Box with the high IP 67 ingress protection, Weidmüller can now provide a modular and versatile concept that makes it possible to condition signals in an industrial environment. Requiring no additional enclosures, these modules can be installed directly on the machine, in the production plant, conveyor system or within a process.

The M12 connector, which is standardised all over the world, makes it possible to integrate the **JACKPAC®** at any point in the sensor-actuator cabling. The fixed pin assignment means it is easy to install and is protected against polarity reversal. This versatility really comes into its own when an installation needs to be altered or modernised, simply because no additional enclosures or cabling are required.

By providing this high degree of protection and versatility, **JACKPAC®** renders possible innovative automation concepts based on decentralised applications – without large control cabinets or small distribution boards – for consistent, transparent, efficient and cost-efficient installations.



- Easy 'Plug and Play' installation
- Universal and versatile usage
- No additional enclosure required
- Saves time and costs
- Ideal for decentralised concepts and plant modernisation (retrofitting)


## Switching amplifiers

- Switching amplifiers are simply built into the actuator system controls
- Switching outputs can be amplified from 24 V DC / 0.5 A to 24 V DC / 2 A
- Galvanic isolation is optional, for insulating between the input and output circuits, which prevents conducted interference on the switching output
- Switched voltage feed at output via T-distributor




## JPR 24 V DC 1CO M12

without isolation



## JPR 24 V DC ISO 1CO M12

with electrical isolation



## Technical data

Input	24 V DC ±20 %	
Rated control voltage	8 mA	
Rated current DC	200 mW	
Power rating	16.8 V / 1.2 V	
DC Response/dropout volt	5 mA / 1 mA	
DC pickup/dropout current	Yes	
Output	24 V / 2 A	
Max. switching power	12 V / 10 mA	
Min. switching power	AgSnO	
Contact material	10 x 10 <sup>6</sup> switching cycles	
Mechanical service life	0.1 Hz	
Max. switching frequency at rated load	ca. 5 ms	
Sparkover time / Drop-out time		
Insulation coordination (EN 50 178)		
Rated voltage	300	
Surge voltage category	III	
Pollution severity	2	
General data		
Ambient temperature (operational)	-25 °C...+70 °C	
Storage temperature	-25 °C...+70 °C	
Conductor connection system	M12 plug / socket, A-coded	
Approvals	cULus; GOSTME25	
Dimensions		
Clamping range (nominal / min. / max.)	mm <sup>2</sup>	
Length x width x height	83 / 36 / 14.4	
Note	Details for TU = 20 °C	
Ordering data		
Type	Qty.	Order No.
JPR 24VDC 1CO M12	1	8771420000
Type	Qty.	Order No.
JPR 24VDC ISO 1CO M12	1	8771430000

## Ordering data

Type	Qty.	Order No.
JPR 24VDC 1CO M12	1	8771420000

## Note

## Accessories

### Note

Retaining clip  
JP CLIP M: 8778490000

## Note

Retaining clip  
JP CLIP M: 8778490000

**Timer relay**

Signal extenders can be easily connected to the cable between the sensor and the input modules. They extend the pulse length from a minimum of 1 ms to 50 ms or 100 ms. This enables short sensor signals to be reliably recognised and evaluated by the controller.

**Technical data**

Input	18...24...30 V DC 3.5...7.0...10.0 mA 50 ms	Output	18...24...30 V DC 3.5...7.0...10.0 mA 100 ms
Max. switching voltage, DC	30 V	Max. switching voltage	30 V
Max. switching current	400 mA	Max. switching current	400 mA
<b>Insulation coordination (EN 50 178)</b>		<b>Insulation coordination (EN 50 178)</b>	
Rated voltage	32 V	Rated voltage	32 V
Impulse withstand voltage	330 V	Impulse withstand voltage	330 V
Surge voltage category	I	Surge voltage category	I
Pollution severity	2	Pollution severity	2
<b>General data</b>		<b>General data</b>	
Ambient temperature (operational)	0 °C...+60 °C	Ambient temperature (operational)	0 °C...+60 °C
Storage temperature	-20 °C...+85 °C	Storage temperature	-20 °C...+85 °C
Conductor connection system	M12 plug / socket, A-coded	Conductor connection system	M12 plug / socket, A-coded
Approvals	CE; cULus; GOSTME25	Approvals	CE; cULus; GOSTME25

**Dimensions**

Clamping range (nominal / min. / max.)	mm <sup>2</sup>
Length x width x height	mm

Note	83 / 36 / 14.4	83 / 36 / 14.4
------	----------------	----------------

**Ordering data**

Type	Qty.	Order No.
JPTA 50MS 24VDC PNP M12	1	8771440000
JPTA100MS 24VDC PNP M12	1	8836630000

Note		
------	--	--

**Accessories**



Note	Retaining clip JP CLIP M: 8778490000	Retaining clip JP CLIP M: 8778490000
------	---	---

**JPTA 50 MS 24VDC PNP M12**

Pulse stretching, 50 ms

**JPTA 100 MS 24VDC PNP M12**

Pulse stretching, 100 ms





## Signal inverter

Signal inverters convert PNP sensor signals to NPN signals and NPN signals back to PNP. This means that existing circuits do not require complex alteration and the existing inputs on the I/O cards can be put to best use. This is particularly well suited for the Asian and North American markets.

## JPP NPN PNP 24 V DC



## JPP PNP NPN 24 V DC



## Technical data

Input	2-/3-Conductor Sensor NPN-type 18...24...30 V DC < 200 mA NO contact	Output	2-/3-Conductor Sensor PNP-Type 18...24...30 V DC < 200 mA NO contact
Solid-state type	Solid state relay 18...30 V DC 400 mA ≤ 1 V	Solid-state type	Solid state relay 18...30 V DC 400 mA
Rated switching voltage	32 V	Rated switching voltage	32 V
Rated switching current	330 V	Rated switching current	330 V
Voltage drop at max. load	I	Voltage drop at max. load	I
Insulation coordination (EN 50 178)	2	Insulation coordination (EN 50 178)	2
Rated voltage	0 °C...+60 °C	Rated voltage	0 °C...+60 °C
Impulse withstand voltage	-20 °C...+85 °C	Impulse withstand voltage	-20 °C...+85 °C
Surge voltage category	M12 plug / socket, A-coded	Surge voltage category	M12 plug / socket, A-coded
Pollution severity	cULus; GOSTME25	Pollution severity	cULus; GOSTME25
General data	CE; cULus; GOSTME25	General data	CE; cULus; GOSTME25
Ambient temperature (operational)		Ambient temperature (operational)	
Storage temperature		Storage temperature	
Conductor connection system		Conductor connection system	
Approvals		Approvals	

## Dimensions

Clamping range (nominal / min. / max.)	mm <sup>2</sup>
Length x width x height	mm

Note	83 / 36 / 14.4	83 / 36 / 14.4
------	----------------	----------------

## Ordering data

Type	Qty.	Order No.
JPP NPN PNP 24VDC	1	8852350000
JPP PNP NPN 24VDC	1	8857030000

Note		
------	--	--

## Accessories


Note	Retaining clip JP CLIP M: 8778490000	Retaining clip JP CLIP M: 8778490000
------	---	---

**Test adapter**

The new JACKPAC® test adapter can be easily integrated at any point on an M12 network and enables quick and easy connection of a testing device via the 5 PUSH IN connections. Status indicators show the status of the 2 signal channels as well as the 24 V DC auxiliary voltage.

**JP TEST**

with status indication

**Technical data****Input**

Rated control voltage

Rated current DC

Status indicator

**Output**

Continuous current

Power

**General data**

Ambient temperature (operational)

Storage temperature

Conductor connection system

Approvals

18...24...30 V DC

2.2 mA (LED)

Green LED

2 A

2.2 mA at 24 V

0 °C...+55 °C

-25 °C...+70 °C

M12 plug / socket, A-coded

CE; GOSTME25

**Dimensions**Clamping range (nominal / min. / max.)  
Length x width x height      mm<sup>2</sup>  
mm

83 / 36 / 14.4


**Note****Ordering data**

Type	Qty.	Order No.
JP TEST	1	8794120000


**Note****Accessories****Note**Retaining clip  
JP CLIP M: 8778490000

**General data**

Ingress protection class	IP 67
Housing material	PBT, RAL 7032 (grey)
Flammability class	V0 to UL94
Screw socket	M12, CuZn, nickel plated, A-coded
Rated torque	0.8 ... 1 Nm

**Contact assignment (socket)**

Pole	Assignment
1	+24 V DC
2	Input / output 2
3	0 V DC
4	Input / output 1
5	PE / Earth

**Accessories****Retaining clip**

Type	Qty.	Order No.
Stainless steel JP CLIP M	1	8778490000

**Twin plug**

Type	Qty.	Order No.
5-pole SAI-Y-5S PARA M12/M12	1	1783430000

**Screwy® M12**

Type	Qty.	Order No.
With torque SCREWTY M12 DM	1	1900001000

**Sensor cables**


Type	Qty.	Order No.
4-pole, length 0.3 m SAIL-M12G-M12G-4-0.3U	1	1906300030
4-pole, length 0.6 m SAIL-M12G-M12G-4-0.6U	1	1906300050
4-pole, length 1.5 m SAIL-M12G-M12G-4-1.5U	1	1906300150
5-pole, length 0.3 m SAIL-M12G-M12G-5-0.3U	1	9457340030
5-pole, length 0.6 m SAIL-M12G-M12G-5-0.6U	1	9457340060
5-pole, length 1.5 m SAIL-M12G-M12G-5-1.5U	1	9457340150

Additional accessories can be found in the Sensor Actuator Interface catalogue.

## Empty housing SAI JACKPAC® for custom built-in components

Empty housing SAI JACKPAC®  
for custom built-in components

### SAI JP



### Technical data


#### General data

Temperature range  
Connection system  
Contact base material  
Surface finish


-25 °C ... +70 °C  
M12 plug/socket, A-coded  
AgSnO  
Au

# H

### Dimensioned drawing SAI JP



### Dimensioned drawing, PCBs



#### Dimensions

Length x width x height mm

83 x 36 x 14.4

#### Note

#### Ordering data

##### Housing with M12 connectors

Contents	1 piece
	1 piece
100 pieces	
	100 pieces

#### Note

Type	No. of poles	Qty.	Order No.
SAI JP 4P LG	4	1	1915220000
SAI JP 5P LG	5	1	1918520000
SAI JP 4P LG 100	4	1	8794090000
SAI JP 5P LG 100	5	1	8794080000

Housing without M12 connectors SAI JP FC SET 1933680000  
1 Qty. - 100 pieces

#### Accessories


# Passive distributors

<b>Passive distributors</b>	
Introduction	I.2
M12 distributors	I.4
ECO modules	I.16
M12 Push-Pull	I.18
M12 IDC	I.26
M12 VA stainless steel	I.30
M12 metal distributors	I.32
M12 distributors 1:1 Passive	I.38
M12 Combi distributor	I.39
M12 distributor for NPN and PNP sensors	I.40
M12 wall bushing	I.41
Solutions to customer specification	I.44
M12 distributors accessories	I.45
M8 distributors	I.46
M5 distributors	I.56
M12 Ex i distributors	I.60

## SAI Passive

SAI Passive products are built with premium materials using the highest quality production methods. The fully encapsulated distributors are designed to meet harsh industrial requirements. Naturally they have also been designed so that they are easy to handle. The self assembled connectors in the hooded version, for example, are joined into a single part so that the entire block is available for the connection. This is a unique solution for distributors that has no equal anywhere. Nothing can break off, get mixed up or wired up incorrectly.

The distributors are equipped by default with threaded metal rings. This ensures a very reliable screw-on connection. The nut is completely threaded without any interruptions. This eliminates the possibility of it getting stuck or jammed. The IDC versions are especially noteworthy. Sensor cables of the proper lengths can be connected directly here.



**Compact**

The connection block is a single piece.

**Small**

Extremely small M12 distributor

**Fast**

Insulation displacement connection can be used to directly connect the sensor cables

**Robust**

Threaded metal ring without cut outs for reliable, safe handling

	<b>M12 distributor standard</b>
	<b>M12 distributor with DIP switch coding</b>
	<b>M12 distributor with stainless steel housing</b>
	<b>M12 distributor for Zone 1</b>

## SAI distributor with plug in connection hood: SAI-M



- Integrated plug in connector in connection hood
- M12 robust metal thread for sensor/actuator connection, now also available with plastic thread as an alternative
- Quick replacement of bus cables
- Bus cable can be supplied pre-assembled
- Two connection systems for bus cable:  
screw or tension clamp
- Very flat connection hood:  
no higher than smallest 90° M12 round plug
- Distributor and connection hood can be supplied separately
- Connection hood compatible with 4 and 8 channel SAI distributors (upgrades only entail changing the base module)
- IP 68 Ingress protection class (IDC IP 67),
- Housing made from Pocan® (PBT):
  - high dimensional stability
  - good electrical and mechanical properties
  - flame retardant without dioxin or furan formers
  - resistant to coolants and lubricants
- UL/CSA approvals for M12 SAI distributor
- SAI distributor available in pollution severity class 3
- Cable exit on top
- Weidmüller SAI distributors have the largest storage capacity in the connection hood
- Female connectors integrated into the metal plate for fast and reliable connections
- Wide range of M8 and M12 cables and plug-in connectors
- Various cable lengths available
- Metal hoods and housings also available
- Plug-in connection module for bus cables increases flexibility on site
- Integral, plug in electrical isolation for two separate electric circuits (e.g. for emergency stop)
- Simple and vibration resistant connections on site
- Captive metric screws (grade 8.8 steel) have a +/- head
- M12 and IDC connections
- 1:1 arrangement available

# Overview of M12 Distributors



## Fixed cable version

- Pre-assembled bus cable minimises installation time and reduces wiring errors
- Cable carrier compatible versions are available with polyurethane (PUR) sheathing



## M12 Push-Pull quick-fit connection system

M12 Push-Pull is the new connection system for sensors and actuators. It is downward compatible to the existing M12 system, which means that both old M12 and new M12 Push-Pull lines can be used together on these SAIs. M12 Push-Pull decreases installation time and increases installation safety by means of colour coding and provides an audible click on locking for added reassurance.



## SAI ECO – the cost-effective alternative

Weidmüller SAI distributors with hood have long since been standard fittings in machines and installations.

### Why plastic threaded rings?

There are some applications, however, that call for a further version. In some applications it is necessary to avoid all metal parts, unless these are made from stainless steel. In such cases stainless steel is then used for screws and nuts only, but the M12 threaded rings can be made from plastic. Such modules can now be supplied on request.

The use of plastic rings results in a cheaper alternative. Although the service life and resistance are reduced when compared to metal, this is acceptable for some applications.

# Overview of SAI

## M12 Plastic

	Hood	M23	5 m	10 m	15 m	20 m
4-way, 4-pole	1705920000	9456000000	9456190000	9456200000	9456210000	9456230000
4-way, 5-pole	1701230000	9456000001	9456330000	9456340000	9456350000	9456370000
6-way, 4-pole	1705930000	9456010000	9456470000	9456480000	9456490000	9456510000
6-way, 5-pole	1701240000	9456010001	9456610000	9456620000	9456630000	9456650000
8-way, 4-pole	1705940000	9456020000	9456750000	9456760000	9456770000	9456790000
8-way, 5-pole	1701250000	1795470000	9456890000	9456900000	9456910000	9456930000

## M12 Metal


	Hood without shield connection	Hood with shield connection	5 m	10 m	
4-way, 4-pole		1783540000	9456190002	9456200002	
4-way, 5-pole	1783500000	1783520000			
8-way, 4-pole		1783530000	9456750002	9456760002	
8-way, 5-pole	1783490000	1783510000			

## M12 Line

	M12 group outlet	5 m	10 m	
4-way, 4-pole	1267330000		1070650000	1070660000
4-way, 5-pole		1070630000	1070640000	
6-way, 4-pole	1265940000	1265920000	1265930000	

## M8 Line

	M12 group outlet	Solder version for PCB	5 m	10 m	
4-way, 3-pole	1828740000		1828720000	1828710000	
4-way, 4-pole			1849680000	1849690000	
6-way, 3-pole	1828730000	1057720000	1828700000	1828690000	
6-way, 4-pole			1849700000	1849670000	
8-way, 3-pole	1871680000		1828680000	1828670000	
8-way, 4-pole			1828620000	1828610000	
10-way, 3-pole	1877950000		1828660000	1828650000	
12-way, 3-pole			1828640000	1828630000	

**Hood version****Ordering data****Complete modules**

Without initiator-LED,for analogue signals	4 channel
Without initiator-LED,for analogue signals	6 channel
Without initiator-LED,for analogue signals	8 channel
Tension-clamp connection	4 channel
Tension-clamp connection	8 channel
<b>Base unit</b>	<b>4 plug-in slots</b>
Without initiator-LED,for analogue signals	8 channel
<b>Mounting hood</b>	
Tension-clamp connection	4 channel
Tension clamp connection	6 channel
Screw connection	8 channel
Screw connection	8 channel
Empty	
Complete modules,NPN-switched	8 channel
<b>Note</b>	

**SAI-4/6/8-M**

Type	QTY	Order No.
SAI-4-M 4P M12	1	1705920000
SAI-6-M 4P M12	1	1705930000
SAI-8-M 4P M12	1	1705940000
SAI-4-M 4P M12 UT	2	1705921000
SAI-6-M 4P M12 UT	2	1705931000
SAI-8-M 4P M12 UT	2	1705941000
SAI-4/6/8-MH BLZF3.5	1	1752080000
SAI-4/6/8-MH BLZF3.5 SV	50	1752080050
SAI-4/6/8-MH BL3.5	1	1724750000
SAI-4/6/8-MH BL3.5 SV	50	1724750050
Other versions on request		



**4-pole****SAI-4/6/8-M**


Type	QTY	Order No.
SAI-4-M 5P M12	1	1701230000
SAI-6-M 5P M12	1	1701240000
SAI-8-M 5P M12	1	1701250000
SAI-4-M 5P M12 OL	1	1800000000
SAI-8-M 5P M12 OL2	1	1816610000
SAI-4-M 5P M12 ZF	1	1854000000
SAI-8-M 5P M12 ZF III	1	1767880000
SAI-4-M 5P M12 UT	2	1701231000
SAI-6-M 5P M12 UT	2	1701241000
SAI-8-M 5P M12 UT	2	1701251000
SAI-8-M 5P M12 OL UT	2	1740191000
SAI-4/6/8-MH BLZF3.5	1	1752080000
SAI-4/6/8-MH BLZF3.5 SV	50	1752080050
SAI-4/6/8-MH BL3.5	1	1724750000
SAI-4/6/8-MH BL3.5 SV	50	1724750050
SAI-4/6/8-MH LEER	1	1783460000
SAI-8-M 5P M12 NPN	1	1781060000
Other versions on request		

**5-pole****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	10 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+90 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 V0)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	0.08...1.5 mm²
Suitable for dragline cable (fixed cable connection)	

With dual power supply: 2x8 = 16A total current  
Clamping range up to 2.5 mm² with screw connection

**Wiring diagram****Wiring diagram**

**M12 distributors****Fixed cable version****Ordering data****4 channel**

Cable length 3 m  
Cable length 5 m  
Cable length 10 m  
Cable length 15 m  
Cable length 20 m

**SAI-4/6/8-F**

Type	QTY	Order No.
SAI-4-F 4P PUR 3M	1	9456180000
SAI-4-F 4P PUR 5M	1	9456190000
SAI-4-F 4P PUR 10M	1	9456200000
SAI-4-F 4P PUR 15M	1	9456210000
SAI-4-F 4P PUR 20M	1	9456230000

**SAI-4/6/8-F**

Type	QTY	Order No.
SAI-4-F 5P PUR 3M	1	9456320000
SAI-4-F 5P PUR 5M	1	9456330000
SAI-4-F 5P PUR 10M	1	9456340000
SAI-4-F 5P PUR 15M	1	9456350000
SAI-4-F 5P PUR 20M	1	9456370000

**6 channel**

Cable length 3 m  
Cable length 5 m  
Cable length 10 m  
Cable length 15 m  
Cable length 20 m

Type	QTY	Order No.
SAI-6-F 4P PUR 3M	1	9456460000
SAI-6-F 4P PUR 5M	1	9456470000
SAI-6-F 4P PUR 10M	1	9456480000
SAI-6-F 4P PUR 15M	1	9456490000
SAI-6-F 4P PUR 20M	1	9456510000

Type	QTY	Order No.
SAI-6-F 5P PUR 3M	1	9456600000
SAI-6-F 5P PUR 5M	1	9456610000
SAI-6-F 5P PUR 10M	1	9456620000
SAI-6-F 5P PUR 15M	1	9456630000
SAI-6-F 5P PUR 20M	1	9456650000

**8 channel**

Cable length 3 m  
Cable length 5 m  
Cable length 10 m  
Cable length 15 m  
Cable length 20 m

Type	QTY	Order No.
SAI-8-F 4P PUR 3M	1	9456740000
SAI-8-F 4P PUR 5M	1	9456750000
SAI-8-F 4P PUR 10M	1	9456760000
SAI-8-F 4P PUR 15M	1	9456770000
SAI-8-F 4P PUR 20M	1	9456790000

Type	QTY	Order No.
SAI-8-F 5P PUR 3M	1	9456880000
SAI-8-F 5P PUR 5M	1	9456890000
SAI-8-F 5P PUR 10M	1	9456900000
SAI-8-F 5P PUR 15M	1	9456910000
SAI-8-F 5P PUR 20M	1	9456930000

**8 channel with reinforced fixed cable\***

Cable length 2 m  
Cable length 5 m  
Cable length 10 m  
Cable length 15 m  
Cable length 20 m

Type	QTY	Order No.
SAI-8-F 5P 2M 0.5/1.0U	1	7915030000
SAI-8-F 5P 5M 0.5/1.0U	1	9457590000
SAI-8-F 5P 10M 0.5/1.0U	1	9457600000
SAI-8-F 5P 15M 0.5/1.0U	1	1784510000
SAI-8-F 5P 20M 0.5/1.0U	1	1784500000



Type	QTY	Order No.
SAI-8-F 5P 2M 0.5/1.0U	1	7915030000
SAI-8-F 5P 5M 0.5/1.0U	1	9457590000
SAI-8-F 5P 10M 0.5/1.0U	1	9457600000
SAI-8-F 5P 15M 0.5/1.0U	1	1784510000
SAI-8-F 5P 20M 0.5/1.0U	1	1784500000



**Note**

Other versions on request

**Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	9 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+80 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 V0)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	Yes

\* 3x1mm<sup>2</sup> und 16x0.5mm<sup>2</sup> total current 12A**Wiring diagram****Wiring diagram**

**Fixed cable version****Thin design****SAI-4-F M12 L****SAI-4-F M12 L****Ordering data****4 channel**Cable length 5 m  
Cable length 10 m**Note****SAI-4-F M12 L**

Type	QTY	Order No.
SAI-4-F 4P M12 L 5M	1	1070650000
SAI-4-F 4P M12 L 10M	1	1070660000

Other versions on request



**4-pole**


Type	QTY	Order No.
SAI-4-F 5P M12 L 5M	1	1070630000
SAI-4-F 5P M12 L 10M	1	1070640000

Other versions on request

**5-pole****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	9 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+80 °C
Housing main material	PA 6 GF
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	Yes


**Dimensioned drawing****Dimensioned drawing**

**M12 distributors****Fixed cable version****Thin design****SAI-6-F M12 L****Ordering data****4 channel**Cable length 5 m  
Cable length 10 m**Note****SAI-6-F M12 L**

Type	QTY	Order No.
SAI-6-F 4P M12 L 5M	1	1265920000
SAI-6-F 4P M12 L 10M	1	1265930000

**4-pole****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	9 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+80 °C
Housing main material	PA 6 GF
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	Yes



**Dimensioned drawing**

## Line

## SAI-4-S



## SAI-6-S



## Ordering data

3-pole	4 channel
--------	-----------

## Note

## SAI-4-S

Type	QTY	Order No.
SAI-4-S8 4P M12 L	1	1267330000


## M12

Type	QTY	Order No.
SAI-6-S12 4P M12 L	1	1265940000


## Technical data

Operating voltage	10...30 V
Current of continuous busbars	1 A
max. current-carrying capacity per slot	2 A
Total current	6 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20 ...+80 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

## Dimensioned drawing




## Dimensioned drawing



**M12 distributors**

with M23 outlet

**Ordering data****Complete modules**

4 channel  
6 channel  
8 channel

**Note****SAI-4/6/8-S**

Type	QTY	Order No.
SAI-4-S 4P M12	1	9456000000
SAI-6-S 4P M12	1	9456010000
SAI-8-S 4P M12	1	9456020000

Other versions on request



**4-pole****SAI-4/6/8-S**

Type	QTY	Order No.
SAI-4-S 5P M12	1	9456000001
SAI-6-S 5P M12	1	9456010001
SAI-8-S 5P M12	1	1795470000


Other versions on request

**5-pole****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	10 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+90 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 V0)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

**Wiring diagram****Wiring diagram**

with M16 outlet

**SAI-8-M16****Ordering data****Complete modules**

8 channel

**Note****SAI-8-M16****Type****4-pole****QTY**

1


**Order No.**


1831020000

Other versions on request

**Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	6 A
Pollution severity	3
Protection degree	IP 67
Ambient temperature range	-20...+90 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

**Dimensioned drawing**

**M12 distributors****Hood version  
with DIP-switch coding****SAI-8-M M12 DIP****Ordering data**


<b>Complete modules</b>	8 channel
<b>Note</b>	

**SAI-8-M M12 DIP**

Type	QTY	Order No.
SAI-8-M-4P M12 DIP	1	<b>1059430000</b>
Other versions on request		

**4-pole****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	8 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+90 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	0.08...1.5 mm <sup>2</sup>
Suitable for dragline cable (fixed cable connection)	

**Dimensioned drawing**



# SAI ECO

## SAI ECO – the cost-effective alternative

The Weidmüller SAI distributors with hoods have long since been standard fittings in machines and installations.

### Why plastic threaded rings?

There are some applications, however, that call for a further version. In some applications it is necessary to avoid all metal parts. In such cases stainless steel is then used for screws and nuts only, but the M12 threaded rings can be made from plastic. Such modules can now be supplied on request.

The use of plastic rings results in a cheaper alternative. Although the service life and resistance are reduced when compared to metal, this is acceptable for some applications.

## Cost-effective alternative

The ECO modules were initially developed to optimise costs. Many details of these modules were adapted in such a way that they can still be used wherever standard modules were used in the past, but the individual solutions have now become simpler:

- **Markers:** Markers clipped onto the module can no longer be printed with a identification system. It is easier to simply order the markers with the required printing from us. The markers in the proven MultiCard format are printed with our PrintJetPro Printer.
- **One way disconnector:** Up until now it was usual to achieve electrical isolation devised by Weidmüller by way of jumpers. To reduce costs, these jumpers have been replaced by solder bridges. These are simply cut to provide electrical isolation.
- **No protective caps:** Normally, Weidmüller M12 distributors are always supplied with two protective caps. These were not always required and so they have been omitted.
- **Standard cable gland:** The vibration resistant black screw cable gland has been replaced by a standard IP 68 cable gland.

These cost-cutting measures result in yet more applications for Weidmüller SAI distributors.


## Greater reliability than with comparable systems

Plastic threaded rings are nothing new. However, the problem in the past was that the threaded rings formed part of the housing and were therefore made from the same plastic.

Weidmüller has once again pioneered a new and better solution. Weidmüller plastic rings are manufactured separately, which means that a more suitable, more durable material can be chosen. The Weidmüller production method is also patented.



**Special threaded ring increases durability**

**Hood version****Ordering data****Complete modules**

NPN	4 channel
NPN	6 channel
NPN	8 channel
Base unit	4 channel
Base unit	6 channel
Base unit	8 channel

**Mounting hood**

Tension clamp connection  
Screw connection

**Note****SAI-4/6/8-M**

Type	QTY	Order No.
SAI-4-M 5P M12 ECO	1	1892100000
SAI-6-M 5P M12 ECO	1	1892090000
SAI-8-M 5P M12 ECO	1	1892080000
SAI-4-M 5P M12 NPN ECO	1	1892100005
SAI-8-M 5P M12 NPN ECO	1	1892080005
SAI-4-M 5P M12 ECO UT	2	1892101000
SAI-6-M 5P M12 ECO UT	2	1892091000
SAI-8-M 5P M12 ECO UT	2	1892081000
SAI-4/6/8-MH BLZF3.5 SV	50	1752080050
SAI-4/6/8-MH BL3.5 SV	50	1724750050

These distributors are supplied without protective caps and markers.


**5-pole**

Type	QTY	Order No.

**Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	10 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+90 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	Pocan
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	0.08...1.5 mm <sup>2</sup>
Suitable for dragline cable (fixed cable connection)	

With dual power supply: 2x8 = 16A total current  
Clamping range up to 2.5 mm<sup>2</sup> with screw connection

**Wiring diagram**

## M12 Push-Pull: SAI distributors and cables, with rapid-connection technology

### SAI distributors with M12 Push-Pull plug




Whereas the standard M12 system requires the sleeves to be laboriously screwed on and that operation is hindered by the vibration guard, M12 Push-Pull works with one click, just like those well-known garden hose systems. The audible locking function guarantees a safe and reliable connection as well as a good seal.

M12 Push-Pull is currently supplied by Weidmüller and five other international companies.

M12 Push-Pull connections provide sufficient space for using T-pieces. The SAI module is slimmer and now only 54 mm wide.

### M12 Push-Pull M23 versions



The new SAI M12 Push-Pull distributors can be used with M12 plug-in connectors but also with the new M12 Push-Pull plug-in connectors.

The SAI distributors are available in fixed cable, hood, bayonet connection and M23 versions.


M12 Push-Pull speeds up installation and increases installation reliability thanks to the colour coding and the audible click when locking it into place.

### M12 Push-Pull hood version



### M12 Push-Pull with bayonet connection



**Fixed cable version****Ordering data****4 channel**

Cable length 2 m  
Cable length 5 m  
Cable length 10 m

**8 channel**

Cable length 2 m  
Cable length 5 m  
Cable length 10 m

**Note****SAI-4/8-F**

Type	QTY	Order No.
SAI-4-F 4P FC 2M	1	1848080000
SAI-4-F 4P FC 5M	1	1848060000
SAI-4-F 4P FC 10M	1	1848050000
SAI-8-F 4P FC 2M	1	1847990000
SAI-8-F 4P FC 5M	1	1848000000
SAI-8-F 4P FC 10M	1	1847980000
Other versions on request		



**4-pole****SAI-4/8-F**

Type	QTY	Order No.
SAI-4-F 5P FC 2M	1	1847940000
SAI-4-F 5P FC 5M	1	1847950000
SAI-4-F 5P FC 10M	1	1847930000
SAI-8-F 5P FC 2M	1	1848020000
SAI-8-F 5P FC 5M	1	1848030000
SAI-8-F 5P FC 10M	1	1848010000
Other versions on request		

**5-pole****Technical data**


Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	4 A
Total current	10 A
Pollution severity	3
Protection degree	IP 67
Ambient temperature range	-25...+80 °C
Housing main material	PA 6 GF
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	Yes

Master trunk cable 3x1mm<sup>2</sup> x n x 0.34mm<sup>2</sup>; Halogen

**Wiring diagram****Wiring diagram**

**M12 Push-Pull**

with M23 outlet

**Ordering data****Complete modules**4 channel  
8 channel**Note****SAI-4/8-S**

Type	QTY	Order No.
SAI-4-S 4P FC	1	1847960000
SAI-8-S 4P FC	1	1847920000

Other versions on request



**4-pole****SAI-4/8-S**

Type	QTY	Order No.
SAI-4-S 5P FC	1	1847970000
SAI-8-S 5P FC	1	1848040000

Other versions on request

**Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	4 A
Total current	9 A
Pollution severity	3
Protection degree	IP 67
Ambient temperature range	-25...+80 °C
Housing main material	PA 6 GF
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

**Wiring diagram****Wiring diagram**

with M23 outlet on front



#### SAI-4/8-SH

#### 4-pole

Type	QTY	Order No.
SAI-4-SH 4P FC	1	1859110000
SAI-8-SH 4P FC	1	1859120000

#### SAI-4/8-SH

#### 5-pole


Type	QTY	Order No.
SAI-4-SH 5P FC	1	1859130000
SAI-8-SH 5P FC	1	1859140000

#### Ordering data

##### Complete modules

4 channel  
8 channel


##### Note




#### Technical data


Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	4 A
Total current	9 A
Pollution severity	3
Protection degree	IP 67
Ambient temperature range	-25...+80 °C
Housing main material	PA 6 GF
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

#### Wiring diagram



#### Wiring diagram



**M12 Push-Pull****Hood version****SAI-8-M****Ordering data**


Complete modules	8 channel

**Note****SAI-8-M**

Type	QTY	Order No.
SAI-8-M 5P FC	1	1848070000
Other versions on request		

**5-pole****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	4 A
Total current	
Pollution severity	3
Protection degree	IP 67
Ambient temperature range	-25...+80 °C
Housing main material	PA 6 GF
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

Master trunk cable 3x1mm<sup>2</sup> x n x 0.34mm<sup>2</sup>; halogen-free**Dimensioned drawing**

Terminal	Slot M12	Contact	Colour
1	1	4	white
2	2	4	green
3	3	4	yellow
4	4	4	grey
5	5	4	pink
6	6	4	red
7	7	4	black
8	8	4	violet
9	1	2	grey/pink
10	2	2	red/blue
11	3	2	white/green
12	4	2	brown/green
13	5	2	white/yellow
14	6	2	yellow/brown
15	7	2	white/grey
16	8	2	grey/brown
17	1-8	1	brown (+)
18	1-8	3	blue (-)
PE	1-8	5	green/yellow (PE)

**CNOMO****SAI-4/8-S****SAI-4/8-F****Ordering data****4 channel**

Cable length 5 m  
Cable length 10 m

**8 channel**

Cable length 5 m  
Cable length 10 m

**M23**

4 channel  
8 channel

**Note****SAI-4/8-S**

Type	QTY	Order No.
SAI-4-S 5P CNOMO	1	1861540000
SAI-8-S 5P CNOMO	1	1861580000



**5-pole**


Type	QTY	Order No.
SAI-4-F 5P CNOMO 5M	1	1861570000
SAI-4-F 5P CNOMO 10M	1	1861560000

**Technical data**

Operating voltage	10...50 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	4 A
Total current	8 A
Pollution severity	3
Protection degree	IP 67
Ambient temperature range	-25...+80 °C
Housing main material	PA 6 GF
Contact carrier material	PBT (UL 94 V0)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	Yes

Max. total current with 4-channel distributor is 8A. And with 8-channel distributor is 12A

**Dimensioned drawing****Dimensioned drawing**

**M12 Push-Pull****Bayonet joint****SAI-8-SHB****Ordering data****Complete modules**

8 channel

**Note****SAI-8-SHB****Type****5-pole****QTY**

1


**Order No.**


1872440000

Other versions on request

**Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	4 A
Total current	9 A
Pollution severity	3
Protection degree	IP 67
Ambient temperature range	-25...+80 °C
Housing main material	PA 6 GF
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

**Dimensioned drawing**

**Bayonet joint with socket connector on reverse****SAI-8-SHB****Ordering data**

Complete modules	8 channel


8 channel

**SAI-8-SHB**


Type	QTY	Order No.
SAI-8-SHB 5P F13 FC	1	1872460000
Other versions on request		

**5-pole****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	4 A
Total current	9 A
Pollution severity	3
Protection degree	IP 67
Ambient temperature range	-25...+80 °C
Housing main material	PA 6 GF
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

**Dimensioned drawing**

## IDC – the quick connection



### Hood version

- Compact IDC connection cuts production, commissioning and maintenance work
- Robust, knurled metal nut, safe handling requiring little force
- The dimensions of the IDC distributor correspond to and are compatible with the standard SAI distributor.
- Plug-in connection module for bus cables enhances on-site flexibility
- Three sizes for 4, 6 and 8 channels
- 3-pole version with one I/O signal per channel, 4-pole version with two I/O signals per channel
- Individual on site assembly of sensor/actuator lines
- Fast, reliable connection with IDC connection element
- IP 67 Ingress protection classification.

### SAI fixed cable version

- Pre-assembled bus cables minimise installation work and avoid wiring errors
- 3 sizes for 4, 6 and 8 channels
- Highly flexible, cable carrier compatible bus cables with polyurethane (PUR/PVC) sheathing
  - 3 x 0.75 mm<sup>2</sup>
  - n x 0.34 mm<sup>2</sup>,
- 3-pole version with one I/O signal per channel, 4-pole version with two I/O signals per channel

### IDC connection element

#### Ordering data

Type	Qty.	Order No.
SAI-SA-3-IDC	1	9457720000
SAI-SA-4-IDC	1	1766810000



#### The significant advantages of Weidmüller tools:

- Easy handling
- Very small, ideal for confined assembly conditions
- Patented solution
- Metal Connectors

Insulation displacement connections on Weidmüller SAI distributors are currently the smallest but also the most robust connection elements on the market. Thanks to their extremely small dimensions, corresponding distributors are available with the same dimensions in M12 or IDC versions.

For large series, e.g. where more than 100 modules are used every year, we recommend using a special tool to simplify the handling of the connected lines even further. However, this tool is not always necessary because all connection elements can usually be readily tightened by hand.

#### IDC-Tool



#### Ordering data

Type	Qty.	Order No.
SAI-IDC-Tool	1	1795020000

#### Screwy®

The IDC elements can also be tightened with the Weidmüller Screwty®.



#### Ordering data


Type	Qty.	Order No.
Screwty®-M12-DM	1	1900001000

#### Protective cap M12 for IDCw



#### Ordering data

Type	Qty.	Order No.
SAI-SK-M12 IDC	10	1794850000

**Hood version****Ordering data****Complete modules**

4 channel
6 channel
8 channel

**Base unit**

4 channel
6 channel
8 channel

**Mounting hood**

Tension-clamp connection
Tension clamp connection
Screw connection
Screw connection

**Note****SAI-4/6/8-M IDC**

Type	QTY	Order No.
SAI-4-M 3P IDC	1	1760040000
SAI-6-M 3P IDC	1	1760050000
SAI-8-M 3P IDC	1	1760060000
SAI-4-M 3P IDC UT	2	1760041000
SAI-6-M 3P IDC UT	2	1760051000
SAI-8-M 3P IDC UT	2	1760061000
SAI-4/6/8-MH BLZF3.5	1	1752080000
SAI-4/6/8-MH BLZF3.5 SV	50	1752080050
SAI-4/6/8-MH BL3.5	1	1724750000
SAI-4/6/8-MH BL3.5 SV	50	1724750050
Other versions on request		



**3-pole****SAI-4/6/8-M IDC**


Type	QTY	Order No.
SAI-4-M 4P IDC	1	1766780000
SAI-6-M 4P IDC	1	1766790000
SAI-8-M 4P IDC	1	1766800000
SAI-4-M 4P IDC UT	2	1766781000
SAI-6-M 4P IDC UT	2	1766791000
SAI-8-M 4P IDC UT	2	1766801000
SAI-4/6/8-MH BLZF3.5	1	1752080000
SAI-4/6/8-MH BLZF3.5 SV	50	1752080050
SAI-4/6/8-MH BL3.5	1	1724750000
SAI-4/6/8-MH BL3.5 SV	50	1724750050
Other versions on request		

**4-pole****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	10 A
Pollution severity	2
Protection degree	IP 67
Ambient temperature range	-20...+90 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	0.08...1.5 mm <sup>2</sup>
Suitable for dragline cable (fixed cable connection)	

With dual power supply: 2x8 = 16 A total current  
Clamping range up to 2.5 mm<sup>2</sup> with screw connection

**Wiring diagram****Wiring diagram**

**Fixed cable version****Ordering data****4 channel**Cable length 5 m  
Cable length 10 m**6 channel**Cable length 5 m  
Cable length 10 m**8 channel**Cable length 5 m  
Cable length 10 m**Note****SAI-4/6/8-F IDC**



Type	QTY	Order No.
SAI-4-F 3P IDC PUR 5M	1	1766720000
SAI-4-F 3P IDC PUR 10M	1	1766730000
SAI-6-F 3P IDC PUR 5M	4	1766740000
SAI-6-F 3P IDC PUR 10M	1	1766750000
SAI-8-F 3P IDC PUR 5M	1	1766760000
SAI-8-F 3P IDC PUR 10M	1	1766770000
Other versions on request		

**3-pole****SAI-4/6/8-F IDC**

Type	QTY	Order No.
SAI-4-F 4P IDC PUR 5M	1	1766660000
SAI-4-F 4P IDC PUR 10M	1	1766670000
SAI-6-F 4P IDC PUR 5M	1	1766680000
SAI-6-F 4P IDC PUR 10M	1	1766690000
SAI-8-F 4P IDC PUR 5M	1	1766700000
SAI-8-F 4P IDC PUR 10M	1	1766710000
Other versions on request		


**4-pole****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	9 A
Pollution severity	2
Protection degree	IP 67
Ambient temperature range	-20...+80 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	Yes

**Wiring diagram****Wiring diagram**

**M12 VA stainless steel**

**Fixed cable version,  
specifically designed for use  
in food processing equipment**

**SAI-8-F 5P M12 5M VA****Ordering data**

8 channel

Cable length 5 m

Note


**SAI-8-F 5P M12 5M VA**

Type	QTY	Order No.
SAI-8-F 5P M12 5M VA	1	<b>1865310000</b>

**5-pole****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	4 A
Total current	12 A
Pollution severity	3
Protection degree	IP 69K
Ambient temperature range	-25...+70 °C
Housing main material	Stainless steel
Contact carrier material	
Base material of contacts	CuZn, pre-nickelated, gold-plated
screw socket	stainless steel
Housing colour	Silver
Fire behaviour	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	Yes

Accessories include 4 protective covers for unused slots

**Dimensioned drawing**

**Tension-clamp connection M12, stainless steel****SAIS / SAIB VA**

straight

**Ordering data**

Male	Type	QTY	Order No.
	SAIS 5/9-VA	1	<b>1920700000</b>
	SAIS 5/9-VA-B-COD	1	<b>1920720000</b>

Socket	Type	QTY	Order No.
	SAIB 5/9-VA	1	<b>1920710000</b>
	SAIB 5/9-VA-B-COD	1	<b>1920730000</b>


**Note****Technical data**

Type of connection	Tension clamp connection
Housing main material	1.4404/316L
Contact tube diameter	M12
Cable diameter	6..8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 69K
Contact surface	Gold-plated

**Note**

Type	QTY	Order No.
SAIS 5/9-VA	1	<b>1920700000</b>
SAIS 5/9-VA-B-COD	1	<b>1920720000</b>

Type of connection	Tension clamp connection
Housing main material	1.4404/316L
Contact tube diameter	M12
Cable diameter	6..8 mm (PG9)
Wire cross-section, min. / max.	0.25...0.5 mm <sup>2</sup>
Rated current	4 A
Rated voltage	125 V
Temperature range of housing	-25...+85 °C
Protection degree	IP 69K
Contact surface	Gold-plated

**Dimensioned drawing**

PB = PROFIBUS (B-COD)Torque, see E.12

# Sensor-actuator distributors for special applications

## All-metal SAI-4/8-FMM M12



## Shielded cable, e.g. for analogue initiators

Some applications need full shielding from sensor to control. This is possible with the all metal SAI distributors. The distributors are supplied with an EMC cable gland. Initiator LEDs are omitted.

## Especially thick trunk cable

It is sometimes advisable to use the machine manufacturer's standard trunk cable. This cable will usually have a relatively large outside diameter and will therefore require plenty of space (SAI-4/6/8 MHD).

## All-metal fixed cable distributors

Weidmüller metal distributors have proved their worth in many situations. They are available as 4 and 8 channel M12 versions with cable lengths of 5 or 10 m. Metal distributors are also necessary when ESD requirements must be complied with.

The conductive metal surface provides low surface resistance.

## Advantages:


- No ESD/EMC problems
- High resistance to chemicals or mechanical loads
- Standard mounting dimensions

## SAI-M with metal hood

### SAI-4/6/8 MMS SAI-4/6/8 MM

MMS: Modular, Metal, Shield

MM: Modular, Metal




## SAI-4/6/8 MMS with EMC cable gland in metal housing

For especially tough conditions where plastic is totally unsuitable. In certain cases it makes sense to avoid the use of plastics altogether. In such cases a distributor made completely from metal is required that can be connected to others using metal cable glands, without additional connections for the shielding.

## SAI-4/6/8 MH

MH: Modular, High




## Cable gland: M20

For cables with outside insulation diameter from 10 mm to 14 mm. Listed below are just some of the cable sizes that are suitable for the SAI distributor with M20 cable gland:

- 14 x 0.50 mm<sup>2</sup> to 16 x 0.50 mm<sup>2</sup>
- 8 x 0.75 mm<sup>2</sup> to 15 x 0.75 mm<sup>2</sup>
- 8 x 1.00 mm<sup>2</sup> to 10 x 1.00 mm<sup>2</sup>
- 5 x 1.50 mm<sup>2</sup> to 7 x 1.50 mm<sup>2</sup>

## SAI-4/6/8 MHD

MHD: Modular, High, sealed (for especially thick cables)



## Cable gland: M25

For cables with outside insulation diameter from 13 mm to 18 mm. Listed below are just some of the cable sizes that are suitable for the SAI distributor with M25 cable gland:

- 21 x 0.50 mm<sup>2</sup>
- 18 x 0.75 mm<sup>2</sup> to 21 x 0.75 mm<sup>2</sup>
- 14 x 1.00 mm<sup>2</sup> to 20 x 1.00 mm<sup>2</sup>
- 8 x 1.50 mm<sup>2</sup> to 16 x 1.50 mm<sup>2</sup>


### Overview of metal distributors

Type	SAI-UT	Sockets	M12	Poles-Hood	Form	Cable gland	Cable gland	Length	Order No.
SAI-4-MH-4P M12	PBT	4	4	Zn-G	high	M20	plastic	1705922000	
SAI-6-MH-4P M12	PBT	6	4	Zn-G	high	M20	plastic	1705932000	
SAI-8-MH-4P M12	PBT	8	4	Zn-G	high	M20	plastic	1705942000	
SAI-4-MH-5P M12	PBT	4	5	Zn-G	high	M20	plastic	1701232000	
SAI-6-MH-5P M12	PBT	6	5	Zn-G	high	M20	plastic	1701242000	
SAI-8-MH-5P M12	PBT	8	5	Zn-G	high	M20	plastic	1701252000	
SAI-4-MHD-5P M12	PBT	4	5	Zn-G	high	M25	plastic	1701233000	
SAI-6-MHD-5P M12	PBT	6	5	Zn-G	high	M25	plastic	1701243000	
SAI-8-MHD-5P M12	PBT	8	5	Zn-G	high	M25	plastic	1701253000	
SAI-4-MHD-4P M12	PBT	4	4	Zn-G	high	M25	plastic	1705923000	
SAI-6-MHD-4P M12	PBT	6	4	Zn-G	high	M25	plastic	1705933000	
SAI-8-MHD-4P M12	PBT	8	4	Zn-G	high	M25	plastic	1705943000	
SAI-4-MMS-4P M12	Zn-G	4	4	Zn-G	low	M20	EMC	1783540000	
SAI-8-MMS-4P M12	Zn-G	8	4	Zn-G	low	M20	EMC	1783530000	
SAI-4-MMS-5P M12	Zn-G	4	5	Zn-G	low	M20	EMC	1783520000	
SAI-8-MMS-5P M12	Zn-G	8	5	Zn-G	low	M20	EMC	1783510000	
SAI-4-MM-5P M12	Zn-G	4	5	Zn-G	low	M20	brass	1783500000	
SAI-8-MM-5P M12	Zn-G	8	5	Zn-G	low	M20	brass	1783490000	
SAI-4/6/8 MH-MH BL 3.5				Zn-G	high	M20	plastic	1724752000	
SAI-4/6/8 MH-MHD BL 3.5				Zn-G	high	M25	plastic	1724753000	
SAI-8-MH-5P M12 ZF III	PBT	8	5	Zn-G	high	M20	plastic	1782760000	
SAI-8-MMS-5P M12 ZF III	Zn-G	8	5	Zn-G	high	M20	plastic	1782740000	
SAI-4/6/8 MH-MH BL-ZF 3.5				Zn-G	high	M20	plastic	1782750000	
SAI-4-FMM-4P M12 5M	Zn-G	4	4				5 m	9456190002	
SAI-4-FMM-4P M12 10M	Zn-G	4	4				10 m	9456200002	
SAI-8-FMM-4P M12 5M	Zn-G	8	4				5 m	9456750002	
SAI-8-FMM-4P M12 10M	Zn-G	8	4				10 m	9456760002	

**Note:** The cable outside diameter can vary from manufacturer to manufacturer. It is therefore possible that the cable glands hold other cables firmly despite a different strand lay-up.  
In each case, it is best to first measure the cable diameter and then choose an appropriate distributor.

## Fixed cable version

## SAI-4-FMM



## Ordering data

## 4 channel

Cable length 5 m  
Cable length 10 m

## 8 channel

Cable length 5 m  
Cable length 10 m

## Note

## SAI-4-FMM

## 4-pole


Type	QTY	Order No.
SAI-4-FMM-4P M12 5M	4	9456190002
SAI-4-FMM-4P M12 10M	3	9456200002
SAI-8-FMM-4P M12 5M	1	9456750002
SAI-8-FMM-4P M12 10M	3	9456760002


Additional variants on request  
Bus cable is not shielded

## Technical data

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	9 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+90 °C
Housing main material	CuZn, nickel-plated
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	Silver
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	Yes

## Dimensioned drawing



**Hood version****Ordering data****Complete modules, 4-pole**4 channel  
8 channel**Complete modules, 5-pole**4 channel  
8 channel

Tension-clamp connection, high cover

8 channel

**Base unit**

8 channel

**Mounting hood**

Screw connection

**Note****SAI-4/6/8-MMS**

Type	QTY	Order No.
SAI-4-MMS 4P M12	1	1783540000
SAI-8-MMS 4P M12	1	1783530000
SAI-4-MMS 5P M12	1	1783520000
SAI-8-MMS 5P M12	1	1783510000
SAI-4/6/8 MH-MM BL 3.5	1	1724754000
With EMC cable gland		



**M12****SAI-4/6/8-MM**

Type	QTY	Order No.
SAI-4-MM 5P M12	1	1783500000
SAI-8-MM 5P M12	1	1783490000
SAI-8-MMH 5P M12 ZF	1	1782740000
SAI-8-MM 5P M12 UT	2	1783491000
SAI-4/6/8 MH-MM BL 3.5	1	1724754000
MM without initiator LED and with standard metal cable gland		

**M12****Technical data**


Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	10 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+90 °C
Housing main material	CuZn, nickel-plated
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	Silver
Flammability class UL 94	V-0
Clamping range of hood-version	0.08...1.5 mm <sup>2</sup>
Suitable for dragline cable (fixed cable connection)	

Complete shielding transmission via the housing

**Wiring diagram****Wiring diagram**

**Hood version with M20 outlet**

For cables with 10-14 mm outer diameter

**Ordering data****Complete modules**

4 channel	
6 channel	
8 channel	
Tension-clamp connection	8 channel

**Mounting hood**

Tension-clamp connection	
Screw connection	

**Note****SAI-4/6/8-MH**

Type	QTY	Order No.
SAI-4-MH-4P M12	1	1705922000
SAI-6-MH-4P M12	1	1705932000
SAI-8-MH-4P M12	1	1705942000
SAI-4/6/8 MH MH BLZF3,5	1	1782750000
SAI-4/6/8 MH-MH BL 3,5	1	1724752000
Other versions on request		



**4-pole****SAI-4/6/8-MH**

Type	QTY	Order No.
SAI-4-MH-5P M12	1	1701232000
SAI-6-MH-5P M12	1	1701242000
SAI-8-MH-5P M12	1	1701252000
SAI-8-MH-5P M12 ZF III	1	1782760000
SAI-4/6/8 MH MH BLZF3,5	1	1782750000
SAI-4/6/8 MH-MH BL 3,5	1	1724752000
Other versions on request		

**5-pole****Technical data**


Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	10 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+90 °C
Housing main material	CuZn, nickel-plated
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	Silver
Flammability class UL 94	V-0
Clamping range of hood-version	0.08...1.5 mm <sup>2</sup>
Suitable for dragline cable (fixed cable connection)	

With dual power supply: 2x8 = 16 A total current  
Clamping range up to 2.5 mm<sup>2</sup> with screw connection

**Wiring diagram****Wiring diagram**

**Hood version with M25 outlet**

For cables with 13-18 mm outer diameter

**Ordering data****Complete modules**

Type	QTY	Order No.
SAI-4-MHD-4P M12	1	1705923000
SAI-6-MHD-4P M12	1	1705933000
SAI-8-MHD-4P M12	1	1705943000

**Mounting hood**

Screw connection

**Note****SAI-4/6/8-MHD****4-pole**

Type	QTY	Order No.
SAI-4/6/8 MH-MHD BL 3.5	1	1724753000
Other versions on request		



**SAI-4/6/8-MHD****5-pole**

Type	QTY	Order No.
SAI-4-MHD-5P M12	1	1701233000
SAI-6-MHD-5P M12	1	1701243000
SAI-8-MHD-5P M12	1	1701253000
SAI-4/6/8 MH-MHD BL 3.5	1	1724753000
Other versions on request		

**Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	10 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+90 °C
Housing main material	CuZn, nickel-plated
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	Silver
Flammability class UL 94	V-0
Clamping range of hood-version	0.08...1.5 mm <sup>2</sup>
Suitable for dragline cable (fixed cable connection)	

With dual power supply: 2x8 = 16 A total current  
Clamping range up to 2.5 mm<sup>2</sup> with screw connection

**Wiring diagram****Wiring diagram**

## For switching with five no-voltage contacts in an M12 without LED


with hood



base element



metal

**Emergency stop wiring**

Sometimes a machine builder will need more than two floating contacts in one M12 plug-in connector. This is the case, for example, in the wiring for some "emergency stop" circuits. It was for this application that Weidmüller developed the 1:1 SAI distributor.

This SAI distributor has four M12 plug-in connectors with five floating contacts in one socket connector. The distributor is supplied complete with hood.

When connecting PT100 3- and 4-conductor initiators, we recommend the new shielded metal version. If you need other circuit configurations, simply contact us.

**Note:** This distributor should not be used as the base module for active bus distributors.

**Wiring diagram**


Socket	Contact	BL 3.5 contact
1	1	1
1	2	2
1	3	3
1	4	4
1	5	5
2	1	6
2	2	7
2	3	8
2	4	9
2	5	10
3	1	11
3	2	12
3	3	13
3	4	14
3	5	15
4	1	16
4	2	17
4	3	18
4	4	19
4	5	20
-	-	21

**Technical data**

Current per channel	2 A
Total current	8 A
LEDs	No LEDs are integrated at any point.

**Ordering data**

Type	Qty.	Order No.
SAI4-M 5P M12 1:1 (plastic hood)	1	1806010000
Base element (plastic)	1	1806011000
SAI4-MMS 5P M12 1:1 (metal hood)	1	1897680000

**SAI distributor with 8 poles per M12****Applications**

This distributor can be used both as a base module for satellite solutions (SAI-Combi) and for connecting sensors/units with more than two contacts.

**SAI-Combi**

A sub-distribution board can be connected to every M12 with the help of the SAI-4-M 8P in conjunction with the SAI Active bus hood. This SAI should then be a 4-channel distributor with one channel per socket. The SAI-4-M 4P M12 is particularly suitable.

Part No. **1705920000**.

**Sensors, units with more than two signals in one line**

As one socket in this module contains four signal paths and, in addition, two +, two - and one PE, components with more than two signal lines can be connected to this module. Eight-pole connecting cables are available on request.

**Wiring**

M12 socket	M12 contact	BL 3.5 connection	PLC input	Supply
1	1	1	E0.0	
1	2	3	E0.1	
1	3	5	E0.2	
1	4	7	E0.3	
2	1	2	E0.4	
2	2	4	E0.5	
2	3	6	E0.6	
2	4	8	E0.7	
3	1	9	E1.0	
3	2	11	E1.1	
3	3	13	E1.2	
3	4	15	E1.3	
4	1	10	E1.4	
4	2	12	E1.5	
4	3	14	E1.6	
4	4	16	E1.7	
1/3	5	17		24 V
2/4	5	19		24 V
1/3	6/7	18		0 V
2/4	6/7	20		0 V
1/2/3/4	8	PE		PE

The jumpers in the distributor enable the potentials of 17 and 19 or 18 and 20 to be bridged. Contacts 6 and 7 are bridged in the 8-pole M12 in order to increase the current-carrying capacity, total current per M12: 2 A, signal current per pin: 1 A


**Ordering data**

Type	Qty.	Order No.
Complete module: SAI-4-M 8P M12	1	<b>1807640000</b>
Base separate: SAI-4-M M12 UT	1	<b>1807641000</b>
Matching hood passive: SAI-4/6/8-MH-BL3.5	1	<b>1724750000</b>

**Technical information:** The distributor does not include any signalling LEDs. Supply LEDs and electrical isolation are provided


## Fixed cable version

### Fixed cable version




### M12 sockets

Pin 1 = +24 V DC  
 Pin 2 = NPN Input  
 Pin 3 = 0 V DC  
 Pin 4 = PNP Input  
 Pin 5 = PE



### Wiring diagram (schematic)



This distributor includes the option of attaching either a PNP sensor or an NPN sensor with 2 or 3 conductor connection to an M12 socket.

Eight inputs are available in total. In the case of a switched sensor, a + signal on the corresponding wire is connected through and the appropriate LED is illuminated.

The upper LED "N" is illuminated for NPN sensors and the lower LED "P" for PNP sensors. Do not connect a T-piece to the M12 socket.

The existing M12 plug-in connectors are wired in such a manner that the PNP sensor can be connected to pin 4 and the NPN sensor to pin 2.

The distributor has eight channels and 5 m of cable. Other versions are also available.

### Pin assignment

M12 socket	Pin	Function	Pin	Function	Output	Wire colour	Wire size
1	4	PNP	2	NPN	1	white	0.34 mm <sup>2</sup>
2	4	PNP	2	NPN	2	green	0.34 mm <sup>2</sup>
3	4	PNP	2	NPN	3	yellow	0.34 mm <sup>2</sup>
4	4	PNP	2	NPN	4	grey	0.34 mm <sup>2</sup>
5	4	PNP	2	NPN	5	pink	0.34 mm <sup>2</sup>
6	4	PNP	2	NPN	6	red	0.34 mm <sup>2</sup>
7	4	PNP	2	NPN	7	black	0.34 mm <sup>2</sup>
8	4	PNP	2	NPN	8	violet	0.34 mm <sup>2</sup>
all	1	24 V DC				brown	0.75 mm <sup>2</sup>
all	3	0 V DC				blue	0.75 mm <sup>2</sup>
all	5	PE				green/yellow	0.75 mm <sup>2</sup>

### Technical data


Operating voltage	24 V DC ±20 %
Operation temperature	0..80 °C
Storage temperature	-25..80 °C
Ingress protection class	IP 68
PUR cable	5 m
Max. no-load current for 2-wire NPN sensors	2 mA DC

### Ordering data

Type	Qty.	Order No.
SAI-8-F 5P NPN-PNP 5M	1	1814990000

## Panel feed-through

## SAI-8-B 5P M12 SL



## Ordering data

## SAI-8-B 5P M12 SL

## 5-pole



Type	QTY	Order No.
SAI-8-B 5P M12 SL	1	1847560000
BL 3.5 connector included in delivery		

## Note

## Technical data

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	3 A
Total current	10 A
Pollution severity	3
Protection degree	IP 65
Ambient temperature range	-20...+90 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	0.08...1.5 mm <sup>2</sup>
Suitable for dragline cable (fixed cable connection)	

## Dimensioned drawing



# Overview

## Distributors for system cabling


On site distribution is becoming more important. For example, in some places the IP 20 I/O module has to be mounted in housings directly on the machine. This is where a simplified form of wiring is essential.

## Weidmüller now offers two simple solutions


- A distributor equipped at the rear with a standardised ribbon cable connector, which is compatible with the Weidmüller PLC system interface.
- Weidmüller also offers a unique solution for feeding bus cables through panels that can be plugged in from both sides.

## Advantages

- Sensors and actuators can be plugged in from outside
- Through-panel version can be mounted in cut outs in steel panels
- Standardised ribbon cable connector inside
- Plus: M12 through-panel feed that can be plugged in from both sides



## Drilling template



## Advantages of system cabling

### Fast

- Time saving installation
- Reduces commissioning and trouble-shooting times
- On site wiring cuts wiring costs

### Safe

- Reduces installation errors
- Using system cables instead of individual wires improves clarity in control cabinets
- Direct marking corresponding to the PLC

### Variability


- Additional I/O modules available
- Cable length options
- Easy replacement of I/O interfaces provides flexibility

## Contact assignment


### Male connector X1

M12 socket		Male connector X1
1 ... 8	Pin 1	U +
1 ... 8	Pin 3	U -
1 ... 8	Pin 5	PE

### Male connector X1



### M12 socket




## Contact assignment

### Male connector X2

M12 socket		Male connector X2
1	Pin 4	1
2	Pin 4	2
3	Pin 4	3
4	Pin 4	4
5	Pin 4	5
6	Pin 4	6
7	Pin 4	7
8	Pin 4	8
1 - 8	Pin 1	9
1 - 8	Pin 3	10

### Male connector X2



### Note:

You will find further products for Interface units and PLC solutions in the Electronic catalogue 4.5.

## Technical data

Operating voltage

10 - 30 V (DC)

Outputs

max. 1 A per channel / max. 8 A in total

Inputs

max. 1 A in total

### Mounting conditions

Mounting surface

sheet steel, flat, min. 1.5 mm thick, or panels with at least equivalent stability, max. 6 mm thick

max. 40 °C

IP 67/IP 68 only in conjunction with control cabinets with equivalent class of protection

Fixings

4 screws + washers + nuts / torque: 0.8 Nm

Note:

Connect the male connector 3.5 (X1) when using actuators

## Ordering data

Type	Qty.	Order No.
SAI-8-B 4P M12 F10	1	1812170000
BL 3.50/07/180 SN DKGN BX	50	1606530000

## Pre-assembled hood version

In some cases, it can be advantageous to receive the hoods in pre-assembled form.

Here MF means: basic modules are supplied along with assembled hoods.

Here MHF are the assembled hoods only.

The wire cross-sections are  $3 \times 1 \text{ mm}^2$  and  $n \times 0.34 \text{ mm}^2$ . The quality of conduction is identical to that of fixed cable distributors.

Technical data can be found on pages W.2 and W.9



### SAI distributor with pre-assembled hood

#### Colour-coded cable

##### Ordering data

Type	Length	4-pole Order No.
8-channel		
SAI-8-MF 4P PUR 5M	5 m	1799960000
SAI-8-MF 4P PUR 10M	10 m	1789190000

##### Ordering data

Type	Length	5-pole Order No.
4-channel		
SAI-4-MF 5P PUR 5M	5 m	1804600000
SAI-4-MF 5P PUR 10M	10 m	1804580000
8-channel		
SAI-8-MF 5P PUR 5M	5 m	1804590000
SAI-8-MF 5P PUR 10M	10 m	9457430000
8-channel, without initiator LED		
SAI-8-MF 5P PUR 5M OL	5 m	9457350000

### Pre-assembled hood

#### Colour-coded cable

##### Ordering data

Type	Length	4-pole Order No.
SAI-4/6/8-MHF 4P PUR 4M	4 m	1791450400
SAI-4/6/8-MHF 4P PUR 6M	6 m	1791450600
SAI-4/6/8-MHF 4P PUR 9M	9 m	1791450900
SAI-4/6/8-MHF 4P PUR14M	14 m	1791451400
SAI-4/6/8-MHF 4P PUR20M	20 m	1791452000
SAI-4/6/8-MHF 4P PUR28M	28 m	1791452800
SAI-4/6/8-MHF 4P PUR34M	34 m	1791453400

### Matching base module

Type	Qty.	Order No.
SAI-4-M-4PM12UT	1	1705921000
SAI-6-M-4PM12UT	1	1705931000
SAI-8-M-4PM12UT	1	1705941000

### Pre-assembled hood

##### Ordering data

Type	Length	5-pole Order No.
SAI-4/6/8-MHF 5P PUR 4M	4 m	1791460400
SAI-4/6/8-MHF 5P PUR 6M	6 m	1791460600
SAI-4/6/8-MHF 5P PUR 9M	9 m	1791460900
SAI-4/6/8-MHF 5P PUR14M	14 m	1791461400
SAI-4/6/8-MHF 5P PUR16M	16 m	1791461600
SAI-4/6/8-MHF 5P PUR20M	20 m	1791462000
SAI-4/6/8-MHF 5P PUR28M	28 m	1791462800
SAI-4/6/8-MHF 5P PUR34M	34 m	1791463400
SAI-4/6/8-MHF 5P PUR40M	40 m	1791464000
SAI-4/6/8-MHF 5P PUR50M	50 m	1791465000
SAI-4/6/8-MHF 5P PUR55M	55 m	1791465500

### Matching base module

Type	Qty.	Order No.
SAI-4-M-5PM12UT	1	1701231000
SAI-6-M-5PM12UT	1	1701241000
SAI-8-M-5PM12UT	1	1701251000

Protective cap for hooded distributor, empty,  
Terminal rail foot for distributor

SAI-4/6/8-MH LEER



SAI-TS35 MF

**Ordering data**


<b>Mounting hood</b>	Empty
<b>Note</b>	

SAI-4/6/8-MH LEER

Type	QTY	Order No.
SAI-4/6/8-MH LEER	1	1783460000

**4-pole**

Type	QTY	Order No.
SAI-TS35 MF	1	1917400000

**Dimensioned drawing**

## SAI-M8

Weidmüller offers two different series for the M8 range. Both of these series offer key advantages: while one is optimised for size, the other has a patented shape and protected design that make it easy to handle. The SAI M8 product line is available with up to 12 plug in slots (as a fixed-cable version) and with up to 10 plug-in slots (as a pluggable version). The housings can be screwed on from the side or from the top which makes them more versatile. They are durable and well-sealed with a sturdy, fully encapsulated construction.

These single row distributors are easy to handle; their compact shape makes them one of the smallest product solutions available on the market. The hooded distributor is a favourite from the line or ergonomic distributors (also nicknamed the hedgehog distributor). The cable outlet is customisable and can exit from the top or from the back. These distributors are also fully encapsulated.





### Easily accessible

The side-mounted M8 connector ensures very convenient handling



### Directly on the PCB

Custom versions are also available.  
This is the PCB connection module.



### Space-saving

The line version has a very small size.

# Overview

## Fixed cable version



## Hood version



## M23 version



### Compact dimensions, readily accessible M8 connections, eye-catching design

The unconventional design of this generation of SAI M8 distributors catches the eye immediately. Their shape is helpful because in this patented design the sockets are no longer arranged in simple rows. Instead, some are on 45° bevelled surfaces. That considerably improves the accessibility of the screw connections for the sensor and actuator cables. Ease of use, compact dimensions and the eye catching design are the obvious advantages of this M8 generation.

The following variations are available:

- SAI M8 distributor with removable connection hood; the bus cable can be connected either vertically or horizontally
- SAI M8 distributor with permanently attached, pre-assembled bus cable, 5 or 10 m long; this version is particularly slim and is therefore ideal for mounting in confined spaces
- SAI M8 distributor with metal plated M23 thread

# SAI-M8-Line

## M8 distributor with M12 outlet



## M8 distributor line / fixed-cable version



## M8 distributor with solder pins



## Extra-narrow M8 distributor for confined spaces

Single-row M8 distributors are the smallest sensor-actuator modules currently available with this thread size and it is precisely their size that is a decisive factor for applications and this form has become very popular. It is important to maintain the widest possible range of options. The SAI-M8-Line products can provide many interesting solutions:



- 4 and 6 channel modules with 8-pole M12 bus connection
- 8 and 10 channel modules with 12-pole bus connection
- 4, 10 and 12 channel distributors with fixed cable connection, the 4 and 8 channel modules also with 4 poles

It is important to note that the distributors can be labelled with the same markers as the Weidmüller 5 mm modular terminals. Therefore, no new tags have to be introduced. The modules can also be mounted sideways and are completely encapsulated.

Consequently, Weidmüller SAI distributors represent stability, robustness, flexibility and compactness - all in a single unit.

## PCB version of a complete SAI distributor

During the design of PCBs, it is often necessary to plug in different external data lines. There are a variety of connectors available for this purpose. For machine construction, the M8 and M12 connectors have become established as the standard solutions for sensor and actuator wiring. When attempting to mount these PCB-type connectors to the PCB, there is a significant risk that they will not be firmly attached to the board. Now, the SL version of the SAI distributor series solves this problem. The distributor can be completely mounted onto a PCB. It features soldering pins for the electrical connection to the PCB. The distributor itself should be slightly raised up during assembly by means of washers. This provides some clearance under the board. Naturally, the power supply channels are bridged in the distributor. This saves space on the PCB since there is no need for holes on any assembly surface. Thus the reverse side can be used for other purposes.

**M8 distributors****Hooded/fixed cable version****SAI-4/8-M****SAI-4/8-F****Ordering data**

<b>3-pole</b>	
Cable length 5 m (with fixed cable version)	4 channel
	8 channel
Cable length 10 m (with fixed cable version)	4 channel
	8 channel
<b>4-pole</b>	
Cable length 5 m (with fixed cable version)	4 channel
	8 channel
Cable length 10 m (with fixed cable version)	4 channel
	8 channel
<b>Note</b>	



**SAI-4/8-M****M8**

Type	QTY	Order No.
SAI-4-M 3P M8	1	1784680000
SAI-8-M 3P M8	1	1784670000
SAI-4-M 4P M8	1	1784700000
SAI-8-M 4P M8	1	1784690000
Other versions on request		

Type	QTY	Order No.
SAI-4-F 3P M8 PUR 5M	1	1784640000
SAI-8-F 3P M8 PUR 5M	1	1784620000
SAI-4-F 3P M8 PUR 10M	1	1784630000
SAI-8-F 3P M8 PUR 10M	1	1784610000
SAI-4-F 4P M8 PUR 5M	1	1784600000
SAI-8-F 4P M8 PUR 5M	1	1784580000
SAI-4-F 4P M8 PUR 10M	1	1784590000
SAI-8-F 4P M8 PUR 10M	1	1784570000
Other versions on request		

**Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	2 A
Total current	8 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+80 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 V0)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	0.08...1 mm²
Suitable for dragline cable (fixed cable connection)	Yes



**Dimensioned drawing****Dimensioned drawing**

## With M23/ M16 outlet

SAI-4/8-M23



SAI-8-M16



## Ordering data

3-pole	8 channel
4-pole	4 channel 8 channel
<b>Note</b>	

SAI-4/8-M23

Type	QTY	Order No.
SAI-4-M23 4P M8	1	1784660000
SAI-8-M23 4P M8	1	1784650000
Other versions on request		

M23


Type	QTY	Order No.
SAI-8-M16 3P M8	1	1795900000
Other versions on request		

M16


## Technical data

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	2 A
Total current	8 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+90 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 V0)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

Dimensioned drawing




Dimensioned drawing





## Line

**SAI-4/6-S**



**SAI-5/8-S**



### **Ordering data**

3-pole	4 channel
	6 channel
	8 channel
	10 channel

3-pole without LED

4 channel  
6 channel

Note

**SAI-4/6-S**

M12

Type	QTY	Order No.
SAI-4-S 3P M8 L	1	1828740000
SAI-6-S 3P M8 L	1	1828730000
SAI-4-S 3P M8 L 0L	1	1051760000
SAI-6-S 3P M8 L 0L	1	1932380000


M12

Type	QTY	Order No.
SAI-8-S12 3P M8 L	1	1871680000
SAI-10-S12 3P M8 L	1	1877950000


## Technical data

Operating voltage	10...30 V
Current of continuous busbars	1 A
max. current-carrying capacity per slot	2 A
Total current	6 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	25...+80 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelated, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	Yes

## Dimensioned drawing




## Dimensioned drawing



Line  
PCB version

### SAI-6-S M8 L SL



#### Ordering data

3-pole	6 channel
--------	-----------

#### Note


### SAI-6-S M8 L SL


Type	QTY	Order No.
SAI-6-S 3P M8 L SL	1	1057720000
Other versions on request		

#### Technical data

Operating voltage	10...30 V
Current of continuous busbars	1 A
max. current-carrying capacity per slot	2 A
Total current	6 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-25...+80 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	Yes

#### Dimensioned drawing



**M8 distributors****Line / Fixed cable version****Ordering data****Cable length 5 m (with fixed cable version)**

4 channel  
6 channel  
8 channel  
10 channel  
12 channel

**SAI-4/6/8/10/12-L**

Type	QTY	Order No.
SAI-4-F 3P M8 L 5M	1	<b>1828720000</b>
SAI-6-F 3P M8 L 5M	1	<b>1828700000</b>
SAI-8-F 3P M8 L 5M	1	<b>1828680000</b>
SAI-10-F 3P M8 L 5M	1	<b>1828660000</b>
SAI-12-F 3P M8 L 5M	1	<b>1828640000</b>

**Cable length 10 m (with fixed cable version)**



4 channel  
6 channel  
8 channel  
10 channel  
12 channel

**SAI-4/6/8/10/12-L**

Type	QTY	Order No.
SAI-4-F 4P M8 L 5M	1	<b>1849680000</b>
SAI-6-F 4P M8 L 5M	1	<b>1849700000</b>
SAI-8-F 4P M8 L 5M	1	<b>1828620000</b>
SAI-4-F 4P M8 L 10M	1	<b>1849690000</b>
SAI-6-F 4P M8 L 10M	1	<b>1849670000</b>
SAI-8-F 4P M8 L 10M	1	<b>1828610000</b>

**Note****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	1 A
max. current-carrying capacity per slot	2 A
Total current	6 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-25...+80 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	Yes

**Wiring diagram****Wiring diagram**



# Overview

## M5-Line with M12 outlet



## Fixed cable version



## M5-Line with M16 outlet



### The Weidmüller SAI-M5 distributors are currently the smallest SAI distributors in the world

Whether it is mobile phones or computers, as functionality increases, so the size of components decreases. Today, machine designers face the same problem. Space is at a premium, even in large machines, particularly where the sensor components are located. In the past the M8 distributor solved these problems. However, these units are now considered to be too large. The first move was to make the sensors smaller. Then it was the turn of the cables and distributors.


These extremely small units are surprisingly easy to handle. M5 plug in connectors have three or four poles and are thus equivalent to M8 plug-in connectors.

However, unlike the M8 plug in connectors, the different M5 pole numbers are compatible with each other. The advantage is obvious: 4 pole units which are required, for example, for antivalent sensors can now be plugged into one and the same distributor with standard NOC applications. In the M8 system special adapters are required. In addition to size, the module weight is also critical in some applications. For example, the speed of a handling machine is influenced by the weight of the moving parts. The M5 system offers outstanding benefits with its unrivalled small size and light weight.

There is no version for custom bus cable assembly for this SAI distributor, which is delivered with a plug in connection and a fixed cable connection. A compact 12 pole M12 plug in connector has been developed as a plug in connection specifically for this distributor.

This ratio of surface area to number of connections is reminiscent of the computer industry. The M16 bus connections can be integrated in the module as an option, so that the SAI M5 can be used as a combined SAI system. A Y-configuration is possible in conjunction with the M16 splitter.

The fixed cable version is particularly suitable for standard applications where the distributor is permanently installed and the electrical installation does not have to be disconnected after installation.

**MM5 distributors****Quality comes in little packages...**

This is the motto applied by Weidmüller when developing its M5 plug in connectors. The outstanding feature of these connectors is their tiny size. Attention has also been given to stability and good conductivity.

For a comparison of sizes, take a look at the photos on the left.

These products are ideal for handling machines where light weight and small size are vital.

**Comparing the sizes**

**M12      M8      M5**





**M12      M8      M5**

**Marking**

Each channel is marked with the channel number. Each initiator LED can be exactly allocated with the letters A and B. In addition, the distributor and every channel can be marked.

**M5 distributors**

Line

**SAI-4/8-F****SAI-4/8-S****Ordering data**

<b>3-pole</b>	
Cable length 5 m (with fixed cable version)	4 channel
	8 channel

<b>4-pole</b>	
Cable length 5 m (with fixed cable version)	4 channel
	8 channel

<b>4-pole</b>	
Cable length 5 m (with fixed cable version)	4 channel
	8 channel
Cable length 10 m (with fixed cable version)	4 channel
	8 channel

<b>Note</b>	
	Other versions on request

**SAI-4/8-F****M5**

Type	QTY	Order No.
SAI-4-F 3P M5 L5M	1	1851740000
SAI-8-F 3P M5 L5M	1	1851760000
SAI-4-F 3P M5 L10M	1	1845820000
SAI-8-F 3P M5 L10M	1	1845830000
SAI-4-F 4P M5 L5M	1	1851770000
SAI-8-F 4P M5 L5M	1	1851750000
SAI-4-F 4P M5 L10M	1	1845800000
SAI-8-F 4P M5 L10M	1	1845810000



Other versions on request

Type	QTY	Order No.
SAI-8-S 3P M5	1	1845850000
SAI-4-S 4P M5	1	1845840000

Other versions on request


**Technical data**

Operating voltage	10...30 V
Current of continuous busbars	1 A
max. current-carrying capacity per slot	3 A
Total current	3 A
Pollution severity	3
Protection degree	IP 67
Ambient temperature range	-25...+80 °C
Housing main material	PA 6 GF
Contact carrier material	Nickel-plated CuZn
Base material of contacts	Au (Gold)
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	Yes

**Dimensioned drawing****Dimensioned drawing**

## Line

## SAI-4/8-S16



## Ordering data


<b>3-pole</b>	4 channel
	8 channel
<b>4-pole</b>	4 channel
	8 channel
<b>Note</b>	

SAI-4/8-S16	M5
Type	QTY
SAI-4-S16 3P M5	1
SAI-8-S16 3P M5	1
SAI-4-S16 4P M5	1
SAI-8-S16/19P 4P M5	1
1845870000, 1845880000 and 1845890000 with M16 / 12-pole 1845860000 with M16 / 19-pole	

## Technical data

Operating voltage	10...30 V
Current of continuous busbars	1 A
max. current-carrying capacity per slot	3 A
Total current	3 A
Pollution severity	3
Protection degree	IP 67
Ambient temperature range	-25...+80 °C
Housing main material	PA 6 GF
Contact carrier material	Nickel-plated CuZn
Base material of contacts	Au (Gold)
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

## Dimensioned drawing



# SAI Ex i distributor for Ex i zone 1

## Hooded version with 4 plug-in slots



## Hooded version with 8 plug-in slots



## SAI distributor for Ex i zone 1

Available for the first time: passive SAI distributors with M12 connection technology in IP 68 ingress protection classification for Ex i hazardous area applications.


The SAI Ex i distributor is certified for zone 1 of potentially explosive areas, even for G and D zones.

SAI Ex i distributors are available with four or eight connections for simple connection of NAMUR sensors. This makes distribution boxes with certification a thing of the past. These modules are suitable for process engineering, but also for "standard" machine applications. The versions are available with or without yellow LEDs.

The distributors are provided with a removable connection hood. This detail also helps to reduce costs because only the defective bus cable needs to be replaced and not the entire distributor.

**Hood version**

Zone 1

**Ordering data****Complete modules**

	4 channel
	6 channel
	8 channel
Without initiator LED	4 channel
Without initiator LED	8 channel

**Note****SAI-4/8-M Ex i**



Type	QTY	Order No.
SAI-4-M 4P Exi Z1 IL	1	1868360000
SAI-8-M 4P Exi Z1 IL	1	1868370000
SAI-4-M 4P Exi Z1 OL	1	1868350000
SAI-8-M 4P Exi Z1 OL	1	1894380000

**4-pole****SAI-4/8-M Ex ia**

Type	QTY	Order No.
SAI-4-M 5P M12 Ex ia	1	1896050000
SAI-6-M 5P M12 Ex ia	1	1896070000
SAI-8-M 5P M12 Ex ia	1	1896090000

**5-pole****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	100 mA
max. current-carrying capacity per slot	100 mA
Total current	2.3 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+40 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	0.1...1.5 mm <sup>2</sup>
Suitable for dragline cable (fixed cable connection)	

**Wiring diagram****Wiring diagram**



# M23 Connectors and cables

<b>M23 Connectors and cables</b>	
Product Description: SAI M23 Connectors	J.2
Contact assignment	J.7
Technical data	J.8
Overview	J.10
M23 connector for signal transmission	J.12
M23 connector for power transmission	J.26
Moulded M23 cables	J.30
SAI distributor M12 with M23	J.31
SAI distributor M8 with M23	J.33
Installation instructions – Signal connectors	J.34
Installation instructions – Power connectors	J.39
M23 connector	J.43

## SAI M23

### A comprehensive product line of connectors, distributors and cables

M23 connectors are mainly used for connecting electrical drives and servo-motors into industrial automation applications.

The M23 connectors are very easy to handle and operate. In addition to the injection-moulded variants and the SAI distributors with M23 connectors, Weidmüller is now offering customisable versions and built in plugs.





### The M23 built in connector

The M23 built in connector provides a custom fit solution for building directly into the device.



### M23 connectors for crimping

M23 connectors are easy to handle and operate. This is supported by the type of crimping that is used.



### Robust metal housing

The M23 connectors feature an extra robust design.



### Solutions for power and signals

The extensive product line includes the key housing shapes, such as angled connectors, coupling connectors and device connectors.



**M23 connector for signal transmission**  
Housings



**M23 connector for signal transmission**  
Built in connector



**M23 connector for power transmission**  
Housings



**M23 connector for power transmission**  
Built-in connector



**Moulded M23 cables**



**SAI distributors**

# Product Description: SAI M23 Connectors

## Technology and requirements

The M23 connectors are mainly used for integrating electrical drives and servo motors into industrial automation facilities. The M23 designation is based on the thread diameter of the connector, as shown in Figures 1 and 2. With their wide variety of inserts and housings, these connectors are equally suited for applications involving signal or power transmission. Applications set in harsh industrial environments place strict requirements on the connector. Much is demanded of the housing, the inner insert and the connector contact. Thermal loads, physical loads, and loads from the transmitted electrical power are commonplace. M23 connectors are capable of carrying a load of up to 250/630 V at 9/30 A.

The connectors must be resistant to the penetration of all particles and substances. They must also comply with the required class of IP protection. The material used for manufacture must be resistant to acid and alkaline solutions that may be used during cleaning or production processes. Also it must not be possible for residues to accumulate in the plug which could later contaminate the production flow. It must not be possible for the plug components to loosen due to vibration. In addition, the cable and connector must have EMC shielding for some applications. This keeps external interference from influencing the signals and it also prevents the transmitted signals in the cable from interfering with other cables or components. The standards and directives (such as the German or European standards) that are followed are basically only recommendations concerning the composition of the connector. A so-called "cold standard" exists for the M23 connectors.

## Variants and designs

The variants can be generally classified according to their outer design, into either customisable types, or plastic moulded connectors with pre-connected cables. Both variants are available in male or female versions, and in straight or angled design. Different designs and inserts can be combined to fit the particular application so that an almost limitless variety of combinations is possible. The connector inserts are available in a variety of different pole counts and as either male or female versions. The pole counts also vary in that some contacts in the mating profile may have a larger cross-section than the others. Other types include the device connector variants which are used for contacting and connecting housings. These also come in a variety of designs. The metal alloy in use may differ depending on the particular type of application. For example, stainless steel is used for those variants that will be used in the food processing industry. Each connector is optionally available with EMC protection and a plastic surface.

## Customisable connectors

Customisable connectors are almost all manufactured from metal alloys. Variants with plastic housings or fitting nuts are rare and used mostly for customer-specific solutions. Customisable connectors are made up of a housing, a plastic contact carrier, and the contacts themselves. The various housing types can be equipped with the corresponding contact carriers. The carriers differ in their number of poles and the arrangement of the poles. Different types of contacts may also be used within the contact carriers. The shape of the contacts is either male or female. There are also differences in the width, material, and connection system (such as soldered, crimped or screwed).




Figure 1: M23 cable connector




Figure 2: M23 coupling connector

This modular construction allows for a wide variety of combinations to fit any application type. Figure 3 shows the design and assembly of an M23 signal connector. Since the connector is usually put together in the field, the key requirement is that the connector is easy and reliable for the electrician to handle on-site. A good example of convenient

handling is the integrated EMC shielding. An improved shield connection results because the shielding can be connected in less steps and with fewer tools. The complete assembly process must be clear and concise, and should only take a few steps.




Figure 3: Design and assembly of an M23 connector

### Plastic injection moulded connector with connected cable

Plastic injection moulded cables are cables that have already been fitted with connectors. First the cables are connected with the contacts and then these are mounted into the contact carrier. Next, plastic injection moulding is used to cover the cable and contact carrier with a plastic moulding. This ensures a highly stable and well sealed connector housing. The connector must be destroyed for it to be disconnected from its cable. The connector's outer form and material is put together by a plastic processing tool. The advantage of a moulded cable is that the connection between the cable and the connector has already been tested at the production factory. The electrician need



Plastic injection-moulded M23 connector

only adjust the length. Depending on the application, he may choose to use another connector on the open end or connect the individual cable wires directly (for example, to a terminal block). The advantages of this variant type includes the inexpensive assembly of large batches, the high degree of automation and minimal amount of material used. High reliability and an excellent seal are two additional advantages.

### Connector usage and application

M23 connectors are mainly used for integrating within machine and facility construction applications. These applications require connections with a long life span and high reliability. The failure of a single connector could lead to the failure of the entire production line. It's important to avoid facility outages caused by a connector malfunction, so the machine and facility construction industry relies on connectors with the advantages listed above. Both signals and power must be transferred in such applications. The connector and the cable must be able to withstand harsh industrial conditions. Cables may be under stress from constant motion, in particular for applications involving robotics or dragline chains. Special cables with a specific maximum bending radius are used for such applications (for example, the bending radius may be 10d, i.e., ten times the cable diameter). When constructing a facility, a variety of

connection scenarios are possible based on the particular conditions or adaptations of existing facilities. The length or configuration of the cable must be adapted to fit these conditions. If space is constricted, for instance, it may be necessary to replace a straight connector with an angled one.

Cables can be equipped with both a moulded (extruded) connector and a customisable connector. This ensures proper functionality while providing the flexibility to adapt to changing conditions on location. Safe connections can thus be established with any possible connector combination or at any protective class required. This gives the facility planner the safety he needs. And the electrician on-site can set up the facility properly because he has sufficient





SAI distributor with M23 connector

flexibility to adapt to uncertain conditions. For sensor systems, connectors with high pole counts are often used on SAI distributors. Individual sensors are connected to the distributors where the signals are then centralised. They are then transferred to the controller using a cable with an M23 connector. The most common use for transmitting power involves the connection of servo-motors in machines. M23 connectors are used for this purpose because of their sturdy and compact design and their high power-carrying capacities. Because of the size of the M23 connector, it can also be used in a hybrid version for transmitting both signals and power. The signal-carrying contacts are then shielded within the connector to ensure that the transmitted voltages do not interfere with the signals.



# Contact assignment SAI M23

M23 12- and 19-pole, for SAI distributors and cables

## 12-pole



## 19-pole



Pole	Colour code	Plug-in station	Contact M12
1	white	1	4
2	green	2	4
3	yellow	3	4
4	grey	4	4
5	pink	5	4
6	red	6	4
7	black	7	4
8	violet	8	4
9	blue (-)	1-8	3
10	blue (-)	1-8	3
11	brown (+)	1-8	1
12	green-yellow (PE)	1-8	5

Pole	Colour code	Plug-in station	Contact M12
1	violet	8	4
2	red	6	4
3	grey	4	4
4	red/blue	2	2
5	green	2	4
7	grey/pink	1	2
8	white/green	3	2
9	white/yellow	5	2
10	white/grey	7	2
11	black	7	4
13	yellow/brown	6	2
14	brown/green	4	2
15	white	1	4
16	yellow	3	4
17	pink	5	4
18	grey/brown	8	2
6	blue (-)	1-8	3
12	green-yellow (PE)	1-8	5
19	brown (+)	1-8	1

## Description code

## Housing

G	Inner thread
K	Outer thread
W	angled
S	Signal connectors
L	Power connectors
7/12	Cable passage

## Inserts

BE	Female insert
SE	Male insert
4/4	Number of contacts, here for 4 sensor and 4 power contacts

## Contacts

KBC	Female contact
-----	----------------

## Wire cross-section

0.08/0.56	0.08 mm <sup>2</sup> - 0.56 mm <sup>2</sup>
0.25/1.0	0.25 mm <sup>2</sup> - 1.0 mm <sup>2</sup>
0.75/2.5	0.75 mm <sup>2</sup> - 2.5 mm <sup>2</sup>

## Moulded M23 cables

SAIS	Cable with male plug
SAIB	Cable with female plug
12p	12-pole
19p	19-pole
AN	angled
ST	straight
...M	Length in metres

## Contact partitioning

## Signal connectors

Type	1 mm contact	1.5 mm contact	2 mm contact
6-pole			6
7-pole			7
9-pole	8		1
12-pole	12		
16-pole	16		
17-pole	17		
19-pole	16	3	

## Power connectors

Type	1 mm contact	1.5 mm contact	2 mm contact
6-pole			6
4+4-pole	4		4

Contacts for signal plugs cannot be used in inserts for power plugs and vice versa.

# Signal connectors


## Technical data

### Mechanical data

Housing	Copper-Zinc alloy Die Casting
Housing surface	Nickel plated brass other surface upon request
Inserts (for contacts)	Thermoplastic Polyamid PA 6 (Nylon 6/6), PBT / Fire protection class V-0
Contacts	Copper-Zinc alloy
Contact surface at point of contact	Nickel and gold plated (0.25 µm Au)
Minimum mating cycles	> 1000
Seals / O-Rings	Buna-N standard optional Viton® (Viton is a registered trademark of DuPont)
Temperature range	-40 °C - 125 °C
Type of contacts	Crimp, solder, dip-solder (PCB)
Protection, Imperviousness	IP 67 / IP 69 K per EN 60 529 (connected)
Cable diameter range	3 - 17 mm
<b>Electrical Data</b>	
Number of positions	6      7      9      12      16      17      19
Number of contacts	6      7      8   1      12      16      17      16   3
Contact-Ø	mm      2      2      1   2      1      1      1      1   1.5
Nominal current	A      20      20      8   20      8      8      8      8   10
Nominal voltage at pollution degree 2	V~      630      630      500      500      400      400      320
Nominal voltage at pollution degree 3	V~      300      300      200      200      160      160      100
Test voltage	V~      2500      2500      2500      2500      1500      1500      1500
Insulation resistance	MΩ      > 10 <sup>10</sup> > 10 <sup>10</sup> > 10 <sup>10</sup> > 10 <sup>10</sup> > 10 <sup>6</sup> > 10 <sup>6</sup> > 10 <sup>6</sup>
Max. contact resistance	mΩ      3      3      3      3      3      3      3

## Derating curve

Straight Connectors male + female M 23, 12-pole,  
wires 12 x AWG17



# Power connectors


## Technical data

### Mechanical data

Housing	Copper-Zinc alloy Die Casting		
Housing surface	Nickel plated brass other surface upon request		
Inserts (for contacts)	Thermoplastic Polyamid PA 6 (Nylon 6/6), PBT / Fire protection class V-0		
Contacts	Copper-Zinc alloy		
Contact surface at point of contact	Nickel and gold plated (0.25 µm Au)		
Minimum mating cycles	> 1000		
Seals / O-Rings	Buna-N standard optional Viton® (Viton is a registered trademark of DuPont)		
Temperature range	-40 °C - 125 °C		
Type of contacts	Crimp		
Protection, Imperviousness	IP 67 / IP 69 K per EN 60 529 (connected)		
Cable diameter range	7 - 17 mm		
<b>Electrical Data</b>			
Number of positions	5 + PE	4/4	
Number of contacts	6	4	4
Contact Ø	mm	2	1
Nominal current	A	28	8
Nominal voltage at pollution degree 2	V~	800	300
Nominal voltage at pollution degree 3	V~	600	300
Test voltage	V~	4000	2500
Insulation resistance	MΩ	> 10 <sup>13</sup>	> 10 <sup>13</sup>
Max. contact resistance	mΩ	3	3

## Derating curve

Straight connectors male + female M 23, 5 + PE,  
wires 5 x AWG12



# M23 connector for signal transmission

All customisable connectors can also be assembled together with shielded cables.

Housing	Contact inserts*	Contacts
Cable connector	6-pole	Crimp pin 1 mm rotated 0.08 - 0.56 mm <sup>2</sup>
Coupling connector	7-pole	Crimp pin 1 mm rotated 0.14 - 1.00 mm <sup>2</sup>
Angled connector	9-pole	Crimp pin 1 mm rotated 1.00 - 1.50 mm <sup>2</sup>
Angled connector (coupling)	12-pole	Crimp socket 1 mm rotated 0.08 - 0.56 mm <sup>2</sup>
Device connector (front panel)	16-pole	Crimp socket 1 mm rotated 0.14 - 1.00 mm <sup>2</sup>
Device connector with knurled nut	17-pole	Crimp socket 1 mm rotated 1.00 - 1.50 mm <sup>2</sup>
Device connector (single-hole mount)	19-pole	Crimp pin 2 mm rotated 0.14 - 0.56 mm <sup>2</sup>
Device connector (angled)		Crimp socket 2 mm rotated 0.56 - 1.00 mm <sup>2</sup>
Device connector (back panel)		Crimp pin 2 mm rotated 0.75 - 2.50 mm <sup>2</sup>
		Crimp socket 2 mm rotated 0.75 - 2.50 mm <sup>2</sup>

\* Solder and crimp inserts

## M23 connector for power transmission

Housing	Contact inserts*	Contacts
Cable connector	6 x Male 2 mm	Crimp pin 1 mm turned 0.25 – 1.00 mm <sup>2</sup>
Coupling connector	6 x Socket 2 mm	Crimp socket 1 mm turned 0.25 – 1.00 mm <sup>2</sup>
Angled connector	4 x Male 1 mm 4 x Male 2 mm	Crimp pin 2 mm turned 0.75 – 2.50 mm <sup>2</sup>
Angled connector (coupling)	4 x Socket 1 mm 4 x Socket 2 mm	Crimp pin 2 mm turned 2.50 – 4.00 mm <sup>2</sup>
Device connector (front panel)		Crimp socket 2 mm turned 0.75 – 2.50 mm <sup>2</sup>
Device connector with knurled nut		Crimp socket 2 mm turned 2.50 – 4.00 mm <sup>2</sup>
Device connector (back panel)		
Device connector (back panel)		
Device connector (angled)		

\* Crimp inserts

## Moulded M23 cables

Housing
Cable connector
Coupling connector
Angled connector
Angled connector (coupling)




## M23 connector for signal transmission

### Housing

For cables with outer diameter of: 7-12 mm


#### Cable connector



#### Ordering data

Type	Qty.	Order No.
SAI-M23-GS-7/12	1	1995840000
SAI-M23-GS-11/17	1	1299390000

#### Coupling connector




#### Ordering data

Type	Qty.	Order No.
SAI-M23-KS-7/12	1	1169900000

## J


#### Angled connector



#### Ordering data

Type	Qty.	Order No.
SAIL-M23-GS-S-7/12	1	1169920000

#### Angled connector (coupling)




#### Ordering data


Type	Qty.	Order No.
SAIL-M23-KSW-7/12	1	1169930000

**Built-in connector**


With 3.2-mm mounting holes

**Device connector (front panel)****Ordering data**


Type	Qty.	Order No.
SAIE-M23-S-VW	1	1169940000

**Device connector with knurled nut****Ordering data**


Type	Qty.	Order No.
SAIE-M23-S-RM	1	1169950000

**Device connector (single-hole mount)****Ordering data**




Type	Qty.	Order No.
SAIE-M23-S-EM	1	1169970000

**Device connector (angled)****Ordering data**

Type	Qty.	Order No.
SAIE-M23-S-W	1	1169980000




**Device connector (back panel)****Ordering data**

Type	Qty.	Order No.
SAIE-M23-S-HW	1	1169990000

**M23 connector for signal transmission****Inserts****6-pole**

Male insert on plug side

Female insert on plug side

**9-pole**

Male insert on plug side




Female insert on plug side

**Ordering data**

Type	Qty.	Order No.
Insert 6-pole male	1	1170000000
Insert 6-pole socket	1	1170020000




**Ordering data**

Type	Qty.	Order No.
Insert 9-pole male	1	1170050000
Insert 9-pole socket	1	1170060000

**7-pole**

Male insert on plug side

Female insert on plug side

**12-pole**

Male insert on plug side



Female insert on plug side

**Ordering data**


Type	Qty.	Order No.
Insert 7-pole male	1	1170030000
Insert 7-pole socket	1	1170040000

**Ordering data**



Type	Qty.	Order No.
Insert 12-pole male	1	1170070000
Insert 12-pole socket	1	1995850000
Reverse flow socket	1	1296730000

**16-pole**


Male insert on plug side



Female insert on plug side

**19-pole**

Male insert on plug side





Female insert on plug side

**Ordering data**


Type	Qty.	Order No.
Insert 16-pole male	1	1170080000
Insert 16-pole socket	1	1170090000

**Ordering data**

Type	Qty.	Order No.
Insert 19-pole male	1	1170120000
Insert 19-pole socket	1	1170130000

**17-pole**









Male insert on plug side



Female insert on plug side

**Ordering data**

Type	Qty.	Order No.
Insert 17-pole male	1	1170100000
Insert 17-pole socket	1	1170110000

**M23 connector for signal transmission****Contacts****Male, 1 mm****0.08-0.56****0.14-1.00****1.00-1.50****Female, 1 mm****0.08-0.56****0.34-1.00****1.00-1.50****Male, 1.5 mm****0.14-1.00****Female, 1.5 mm****0.14-0.56****0.56-1.00****Ordering data**

Type	Qty.	Order No.
1.0 mm Male (0.08-0.56) SAI-M23-KSC-0.08/0.56	50	1170140000

1.0 mm Male (0.14-1.00) SAI-M23-KSC-0.14/1.00	50	1170150000
---	----	------------

1.0 mm Male (1.00-1.50) SAI-M23-KSC-1.00-1.5	50	1170170000
--	----	------------

**Ordering data**

Type	Qty.	Order No.
1.0 mm Socket (0.08-0.56) SAI-M23-KBC-0.08/0.56	50	1995860000

1.0 mm Socket (0.34-1.00) SAI-M23-KBC-0.34/1.00	50	1170180000
---	----	------------

1.0 mm Male (1.00-1.50) SAI-M23-KBC-1.00-1.5	50	1170210000
--	----	------------

**Ordering data**


Type	Qty.	Order No.
1.5 mm Male (0.14-1.00) SAI-M23-KSC-1.5-0.14-1	50	1170220000

Type	Qty.	Order No.
1.5 mm Socket (0.14-0.56) SAI-M23-KBC-1.5-14-56	50	1170230000

1.5 mm Socket (0.56-1.00) SAI-M23-KBC-1.5-56-1.0	50	1170240000
--	----	------------

**Male, 2 mm**

0.75-2.00

**Female, 2 mm**

0.75-2.00

**Technical data**

Number of positions

6 | 7 | 9 | 12 | 16 | 17 | 19

Number of contacts

6 | 7 | 8 | 1 | 12 | 16 | 17 | 16 | 3

Contact Ø

mm 2 | 2 | 1 | 2 | 1 | 1 | 1 | 1 | 1.5

**Note:** You can find tools in chapter K. All female connector contacts have SLS technology except for 1170230000 and 1170240000. Other information is available on page J. 44.

**Ordering data**

Type	Qty.	Order No.
2.0 mm Male (0.75-2.00) SAI-M23-KSC2-0.75-2.50	50	1170250000

**Ordering data**

Type	Qty.	Order No.
2.0 mm Socket (0.75-2.00) SAI-M23-KBC2-0.75-2.50	50	1170260000




## M23 inserts with solder contacts

**The M23 solder versions are used for PCB mount soldering or to attach to wires.**

SAI M23 solder inserts with PCB solder pin and solder cups fit the existing M23 housings. This product line is an extension of the existing M23 modular signal connectors. Please also see our M23 Product Information "SAI M23 Connectors".



PCB mount solder contacts are available in different lengths to properly fit with the various housing styles offered by Weidmüller.

All contacts are gold plated for improved connectivity and increased mating cycles.




## Inserts with solder contacts

## 6-pole



Male insert on plug side



Female insert on plug side

## Technical data



No. of poles	6
Contact number / diameter	6 x 2 mm

## Ordering data


Pinout clockwise	Type	Qty.	Order No.
Solder pins, solder cup	SAI-M23-SE-6-F	1	1224000000
Solder sockets, solder cup	SAI-M23-BE-6-F	1	1224010000
PCB solder pins, 3.5 mm	SAI-M23-SE-6-3.5mm	1	1224020000
PCB solder sockets, 3.5 mm	SAI-M23-BE-6-3.5mm	1	1224030000
PCB solder pins, 10 mm	SAI-M23-SE-6-10mm	1	1224050000
PCB solder pins, 17 mm	SAI-M23-SE-6-17mm	1	1224060000
PCB solder sockets, 17 mm	SAI-M23-BE-6-17mm	1	1224040000

PCB hole Ø: 1.5 mm

## 7-pole



Male insert on plug side



Female insert on plug side

## Technical data

No. of poles	7
Contact number / diameter	7 x 2 mm



## Ordering data

Pinout clockwise	Type	Qty.	Order No.
Solder pins, solder cup	SAI-M23-SE-7-F	1	1224070000
Solder sockets, solder cup	SAI-M23-BE-7-F	1	1224080000
PCB solder pins, 3.5 mm	SAI-M23-SE-7-3.5mm	1	1224090000
PCB solder sockets, 3.5 mm	SAI-M23-BE-7-3.5mm	1	1224100000
PCB solder pins, 10 mm	SAI-M23-SE-7-10mm	1	1224120000
PCB solder pins, 17 mm	SAI-M23-SE-7-17mm	1	1224130000
PCB solder sockets, 17 mm	SAI-M23-BE-7-17mm	1	1224110000


PCB hole Ø: 0.8 mm (1.2 mm at 17 mm socket)

## Inserts with solder contacts

## 9-pole



Male insert on plug side





Female insert on plug side




## Technical data

No. of poles	9
Contact number / diameter	8 x 1 mm + 1 x 2 mm

## 12-pole



Male insert on plug side



Female insert on plug side



## Technical data



No. of poles	12
Contact number / diameter	12 x 1 mm

## Ordering data


Pinout clockwise	Type	Qty.	Order No.
Solder pins, solder cup	SAI-M23-SE-9-F	1	1224490000
Solder sockets, solder cup	SAI-M23-BE-9-F	1	1224500000
PCB solder pins, 3.5 mm	SAI-M23-SE-9-3.5mm	1	1224510000
PCB solder pins, 10 mm	SAI-M23-SE-9-10mm	1	1224540000
PCB solder sockets, 10 mm	SAI-M23-BE-9-10mm	1	1224520000
PCB solder pins, 17 mm	SAI-M23-SE-9-17mm	1	1224550000
PCB solder sockets, 17 mm	SAI-M23-BE-9-17mm	1	1224530000
Pinout counter clockwise			
Solder pins, solder cup	SAI-M23-SE-9-F-G	1	1224730000
Solder sockets, solder cup	SAI-M23-BE-9-F-G	1	1224740000
PCB solder pins, 10 mm	SAI-M23-SE-9-10mm-G	1	1224770000
PCB solder sockets, 10 mm	SAI-M23-BE-9-10mm-G	1	1224750000
PCB solder pins, 17 mm	SAI-M23-SE-9-17mm-G	1	1224780000
PCB solder sockets, 17 mm	SAI-M23-BE-9-17mm-G	1	1224760000

PCB hole Ø: 1 mm contact = 0.8 mm (1.2 mm at 17 mm socket)

2 mm contact = 1.5 mm

**M23 connector for signal transmission****Inserts with solder contacts****16-pole**



Male insert on plug side




Female insert on plug side

**Technical data**

No. of poles	16
Contact number / diameter	6 x 1 mm

**17-pole**

Male insert on plug side



Female insert on plug side

**Technical data**

No. of poles	17
Contact number / diameter	17 x 1 mm

**Ordering data**

Pinout clockwise	Type	Qty.	Order No.
Solder pins, solder cup	SAI-M23-SE-16-F	1	1224240000
Solder sockets, solder cup	SAI-M23-BE-16-F	1	1224250000
PCB solder pins, 3.5 mm	SAI-M23-SE-16-3.5mm	1	1224260000
PCB solder sockets, 3.5 mm	SAI-M23-BE-16-3.5mm	1	1224270000
PCB solder pins, 10 mm	SAI-M23-SE-16-10mm	1	1224290000
PCB solder pins, 17 mm	SAI-M23-SE-16-17mm	1	1224310000
PCB solder sockets, 17 mm	SAI-M23-BE-16-17mm	1	1224280000



**Pinout counter clockwise**

Solder pins, solder cup	SAI-M23-SE-17-F	1	1224320000
Solder sockets, solder cup	SAI-M23-BE-17-F	1	1224330000
PCB solder pins, 3.5 mm	SAI-M23-SE-17-3.5mm	1	1224340000
PCB solder pins, 10 mm	SAI-M23-SE-17-10mm	1	1224370000
PCB solder sockets, 10 mm	SAI-M23-BE-17-10mm	1	1224350000
PCB solder pins, 17 mm	SAI-M23-SE-17-17mm	1	1224380000
PCB solder sockets, 17 mm	SAI-M23-BE-17-17mm	1	1224360000


PCB hole Ø: 0.8 mm (1.2 mm at 17 mm socket)

## Inserts with solder contacts

## 19-pole



Male insert on plug side



Female insert on plug side



## Technical data

No. of poles	19
Contact number / diameter	16 x 1 mm + 3 x 1.5 mm

## Ordering data

Pinout clockwise	Type	Qty.	Order No.
Solder pins, solder cup	SAI-M23-SE-19-F	1	1224390000
Solder sockets, solder cup	SAI-M23-BE-19-F	1	1224400000
PCB solder pins, 3.5 mm	SAI-M23-SE-19-3.5mm	1	1224410000
PCB solder pins, 3.5 mm, with PE contact pin 12	SAI-M23-SE-19-3.5mmPE12	1	1224460000
PCB solder sockets, 3.5 mm, with PE contact pin 12	SAI-M23-BE-19-3.5mm-PE	1	1224440000
PCB solder pins, 10 mm	SAI-M23-SE-19-10mm	1	1224470000
PCB solder sockets, 10 mm	SAI-M23-BE-19-10mm	1	1224420000
PCB solder pins, 10 mm, with PE contact pin 12	SAI-M23-SE-19-10mm-PE	1	1224430000
PCB solder pins, 17 mm	SAI-M23-SE-19-17mm	1	1224480000
PCB solder sockets, 17 mm	SAI-M23-BE-19-17mm	1	1224450000

PCB hole Ø: 1 mm contact = 0.8 mm (1.2 mm at 17 mm socket)  
1.5 mm contact = 1.5 mm

## M23 connector for signal transmission

### Overview of inserts and housings


This table shows the different combination possibilities of the inserts and solder pins, with housings.

### Solder pin affiliation

Type	Order No.	Solder pin length		
		3.5 mm	10 mm	17 mm
SAIE-M23-S-VW	1169940000		X	X
SAIE-M23-S-RM	1169950000			X
SAIE-M23-S-EM	1169970000			X
SAIE-M23-S-HW	1169990000	X	X	X

### Device connector (front panel)


#### Male insert



#### Male insert

	L1	L2	L3
10 mm	4.5	10.3	11.65
17 mm	4.5	17.3	18.65

#### Female insert



#### Female insert


	L1	L2	L3
10 mm	4.5	5.3	11.1
17 mm	4.5	12.3	18.1

### Ordering data

Type	Qty.	Order No.
SAIE-M23-S-VW	1	1169940000

### Device connector with knurled nut


#### Male insert



#### Male insert

	L1	L2	L3
10 mm	-	-	-
17 mm	4.5	8.6	9.6

#### Female insert



#### Female insert


	L1	L2	L3
10 mm	-	-	-
17 mm	4.5	7.8	8.8

### Ordering data

Type	Qty.	Order No.
SAIE-M23-S-RM	1	1169950000


**Device connector (single-hole mount)**

Male insert



Male insert	L1	L2	L3
10 mm	-	-	-
17 mm	4.5	10.65	16.65

Female insert




Female insert	L1	L2	L3
10 mm	-	-	-
17 mm	4.5	10.1	16.1

**Ordering data**

Type	Qty.	Order No.
SAIE-M23-S-EM	1	1169970000


**Device connector (back panel)**

Male insert



Male insert	L1	L2	L3
10 mm	4.5	10.3	12.65
17 mm	4.5	17.3	19.65

Female insert




Female insert	L1	L2	L3
10 mm	4.5	5.3	12.1
17 mm	4.5	12.3	19.1

**Ordering data**

Type	Qty.	Order No.
SAIE-M23-S-HW	1	1169990000

**Device connector with knurled nut**

Male insert

**Ordering data**


Type	Qty.	Order No.
SAIE-M23-S-RM	1	1169990000

This solder pin length connector has a solder pin insert with 3.5 mm solder pin length.  
3.5 mm solder inserts can only be combined with this plug-in connector and only in the male version.

## Housing

For cables with outer diameter of: 7-12 mm


### Cable connector



#### Ordering data

Type	Qty.	Order No.
SAI-M23-GS-L-7/12	1	1995800000

### Coupling connector




#### Ordering data

Type	Qty.	Order No.
SAI-M23-KS-L-7/12	1	1170270000

## J


### Angled connector



#### Ordering data

Type	Qty.	Order No.
SAIL-M23-GSW-L-7/12	1	1170280000

### Angled connector (coupling)




#### Ordering data


Type	Qty.	Order No.
SAIL-M23-KSW-L-7/12	1	1170290000

**Built-in connector**


With 3.2-mm mounting holes

**Device connector (front panel)****Ordering data**


Type	Qty.	Order No.
SAIE-M23-L-VW	1	1170300000

**Device connector with knurled nut****Ordering data**


Type	Qty.	Order No.
SAIE-M23-L-RM	1	1170310000

**Device connector (single-hole mount)****Ordering data**

Type	Qty.	Order No.
SAIE-M23-L-EM	1	1170320000

**Device connector (angled)****Ordering data**



Type	Qty.	Order No.
SAIE-M23-L-W	1	1170330000

**Device connector (back panel)****Ordering data**

Type	Qty.	Order No.
SAIE-M23-L-HW	1	1170340000

## Inserts



5 + PE




6 times male, 2 mm



4/4



4 times 1-mm female and 4 times 2-mm male




## Ordering data

	Type	Qty.	Order No.
6 times male 2 mm	SAI-M23-SE-L-6	1	1170350000
6 times female, 2 mm	SAI-M23-BE-L-6	1	1170370000


	Type	Qty.	Order No.
4 times 1-mm male and 4 times 2-mm male	SAI-M23-SE-L-4/4	1	1170380000
4 times 1-mm female and 4 times 2-mm female	SAI-M23-BE-L-4/4	1	1995810000

**Contacts****Male, 1 mm**


0.25 - 1.00

**Female, 1 mm**


0.25 - 1.00

**Male, 2 mm**


0.75 - 2.5




2.5 - 4.00

**Female, 2 mm**

0.75 - 2.5



2.5 - 4.00

**Technical data**

No. of poles

5 + PE

4/4

Number of contacts

6

4

Contact Ø

mm

2

1

**Note:** You can find tools in chapter K. All female connector contacts have SLS technology except for 1170230000 and 1170240000. Other information is available on page J. 44.**Ordering data**

Type	Qty.	Order No.
1 mm Male (0.25-1.00)	50	1170390000

**Ordering data**

Type	Qty.	Order No.
1 mm Socket (0.25-1.00)	50	1995830000

**Ordering data**

Type	Qty.	Order No.
2 mm Male (0.75-2.5)	50	1170400000

**Ordering data**

Type	Qty.	Order No.
2 mm Male (2.5-4.00)	50	1170410000


**Ordering data**

Type	Qty.	Order No.
2 mm Socket (0.75-2.5)	50	1995820000

**Ordering data**

Type	Qty.	Order No.
2 mm Socket (2.5-4.00)	50	1170420000

## M23 cables



## Ordering data

<b>Male, straight</b>	1 m
<b>Male, angled</b>	1 m
<b>Female, straight</b>	1 m
<b>Female, angled</b>	1 m
<b>Note</b>	

## Male

## 12-pole



Type	Order No.
SAIS-M23-12P-ST-1,0M	1906280100
SAIS-M23-12P-AN-1,0M	1906290100
SAIB-M23-12P-ST-1,0M	1886440100
SAIB-M23-12P-AN-1,0M	1877440100

## Male

## 19-pole

Type	Order No.
SAIS-M23-19P-ST-1,0M	1818160100
SAIS-M23-19P-AN-1,0M	1818090100
SAIB-M23-19P-ST-1,0M	1818180100
SAIB-M23-19P-AN-1,0M	1818140100

Other versions on request



## Standard cable lengths


All cables listed under the ordering data have a length of 1.5 metres. The last four ordering digits must be changed when ordering other standard cable lengths.	1.5 m	xxxxxx0150
	3.0 m	xxxxxx0300
	5.0 m	xxxxxx0500
	10.0 m	xxxxxx1000


## Technical data

Rated current	8 A
Protection degree	IP 67
Core cross-section	mm <sup>2</sup>
Contact surface	Gold-plated
Temperature range of housing	-25...+85 °C
Rated voltage (acc. to VDE standard 0110 ISO group C)	150 V

Chapter W includes additional technical specifications for the cable

## Dimensioned drawing



**With M23 outlet****Ordering data****Complete modules**4 channel  
8 channel**Note****SAI-4/8-S**



Type	QTY	Order No.
SAI-4-S 4P FC	1	1847960000
SAI-8-S 4P FC	1	1847920000
Other versions on request		

**4-pole****SAI-4/8-S**


Type	QTY	Order No.
SAI-4-S 5P FC	1	1847970000
SAI-8-S 5P FC	1	1848040000
Other versions on request		

**5-pole****Technical data**

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	4 A
Total current	9 A
Pollution severity	3
Protection degree	IP 67
Ambient temperature range	-25...+80 °C
Housing main material	PA 6 GF
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

**Wiring diagram****Wiring diagram**

## With M23 outlet on face end



## Ordering data

## Complete modules

4 channel  
8 channel

## Note

## SAI-4/8-SH

Type	QTY	Order No.
SAI-4-SH 4P FC	1	1859110000
SAI-8-SH 4P FC	1	1859120000

## 4-pole

## SAI-4/8-SH


Type	QTY	Order No.
SAI-4-SH 5P FC	1	1859130000
SAI-8-SH 5P FC	1	1859140000

## 5-pole


## Technical data

Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	4 A
Total current	9 A
Pollution severity	3
Protection degree	IP 67
Ambient temperature range	-25...+80 °C
Housing main material	PA 6 GF
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

## Wiring diagram




## Wiring diagram



## With M23 outlet

## SAI-4/8-M23



## Ordering data

## 4-pole

4 channel  
8 channel

## Note

## SAI-4/8-M23

## M23


Type	QTY	Order No.
SAI-4-M23 4P M8	1	1784660000
SAI-8-M23 4P M8	1	1784650000

Other versions on request

## Technical data


Operating voltage	10...30 V
Current of continuous busbars	2 A
max. current-carrying capacity per slot	2 A
Total current	8 A
Pollution severity	3
Protection degree	IP 68
Ambient temperature range	-20...+90 °C
Housing main material	Pocan
Contact carrier material	PBT (UL 94 VO)
Base material of contacts	CuZn, pre-nickelized, gold-plated
screw socket	CuZn, nickel-plated
Housing colour	grey, RAL 7032
Flammability class UL 94	V-0
Clamping range of hood-version	
Suitable for dragline cable (fixed cable connection)	

## Dimensioned drawing




# Cable connector

1.



2.




3.




5.




6.




7.




8.





4.




## Angled connector



## Device connector with knurled nut



## Device connector, male



## Device connector, female


1.



2.



3.



4.




5.



6.




## Cable connector




## Device connector


1.




2.




3.






4.



## Device connector



x  
Contact 1 mm = 4 mm  
Contact 2 mm = 7 mm




## Device connector, single-hole mount

1.




X  
Contact 1 mm = 4 mm  
Contact 2 mm = 7 mm

2.



3.




4.



# M23 connector

## Easy to assemble

- An integrated approach for all plug sizes
- A patented assembly module consisting of terminal insert and insulating body
- Assembly and shield connection combined into one step
- Simple, quick and safe assembly in the housing



## Flexibility



Total modularity means flexibility Male or female inserts can even be used with any of the housing types for the M23 power connectors.



The concise layout of this connector range and the reduced number of individual parts has clear benefits for the user – quicker assembly and easier installation.



The spacer sleeves are colour-coded for the male and female inserts.



Assembly and shield connection are combined into one step.




The variable shield connection ensures secure EMC protection for both light and heavy shielding braid.

### Secure contact with SLS® technology

The new, premium-grade contact – the spring-loaded socket (SLS®) system

- Integrated spring takes the pin contact and clasps it radially
- Outstanding electrical characteristics with the most secure contact
- Quick assembly: solder contacts already tin-plated




### Euro-Lock system® for a secure mount

Euro-Lock system® – the patented interlock system

- The integrated support clip locks the contacts into the insulating body
- Contacts are easy to install and remove
- No special tool is required

### High-quality cable gland

- Replaceable male or female inserts in each type of housing
- Integrated strain relief mechanism with patented HSK cable gland
- Internationally certified, with proven and established quality





# Tools and markers

<b>Tools and markers</b>		
Introduction		K.2
Screwy <sup>®</sup>		K.4
Cutting tools		K.7
Sheathing and insulation stripping tools		K.8
Stripping and cutting tools		K.9
M23 crimping tools		K.12
Identification systems		K.14

## SAI tools

The Screwty® is a state-of-the-art tool that features a unique, patented retention method. The adjustable torque ensures that the connectors have actually been sealed tightly. The Screwty® attachment for M23 is also very important because the sealing method for the M8 and M12 connectors are comparable to the M23.

The fact that the Screwty® attachment slips back is a major advantage of this system. This means that it does not have to be re-applied, as would be the case when using an open

ended wrench. There is also no risk that the screw can loosen when you turn the tool the wrong way since the Screwty® is only capable of exerting force in one direction.


It is also possible to put other tool attachments on the 1/4"-drive. This allows the use of torque spanner wrenches or torque screwdrivers. This is also available without torque for those who cannot fit a torque tool into their budgets.



The Screwty® can also be used to screw on M23 connectors.



The tool does not have to be re-applied. During the follow-up it simply slips back.



You can change the function from closed to open by simply turning it around.



The Screwty® can also be purchased as a set with other suitable attachments.



### Screwty® torque

- Screw-on circular plug, safety sealed
- Easier work



### Cutting tools

- Cutting shape for various cable sizes
- Cutting without deformation of the conductor



### Sheathing and insulation stripping tools

- No need to adjust cutting depth
- No damage to inner conductors



### Stripping and cutting tool


- Special, self adjusting stripping blades do not damage the conductor



**Screwty®**  
Bolting tools



**Cutting tools**



**Sheathing and insulation stripping tools**



**Stripping and cutting tools**



**SAI M23 crimping tool**



**Identification systems**

# Screwty® for M8/M12/M23



## The Torque Screwty®


- Easier work
- Screw on circular plug, safety sealed

## The perfect tool for all situations

Screwty® is the ideal, universal tool for tightening and releasing cable glands on all common sensor and actuator cables. The Screwty® can also reach those round plugs normally considered inaccessible! No great force is required, simply turn the tool to tighten or release the plug in connector as required.

The Screwty® also fits the majority (more than 90 %) of the cables and plug-in connectors of other suppliers and is therefore a unique tool that is useful worldwide. The Screwty® consists of a handle with a conventional 1/4" fitting. This means it can be used for all sizes: for M12 and M8 round plugs, and the M12F and M8F types, as well as for plugs and sockets on custom cables. The Screwty® is suitable for the following round plugs:

Size	M8	M8F	M12	M12F
	10 ±0.3 mm	11.9 ±0.3 mm	14.5 ±0.3 mm	19.8 ±0.3 mm
Thread	M8x1	M8x1	M12x1	M12x1



An adjustable torque fitting is also available for the Screwty®, for guaranteeing extra reliability during installation.

The torque can be infinitely adjusted between 0.5 and 1.7 Nm. This accurate setting enables all round plugs to be tightened precisely with a pre-set torque.

Weidmüller specifies the following torques for its round plugs:

Size	M8	M8F	M12	M12F
Torque	0.5-0.6 Nm	0.5-0.6 Nm	0.8-1.2 Nm	0.8-1.2 Nm
Thread	M8x1	M8x1	M12x1	M12x1

Simply turn the ratchet to tighten or loosen the cable gland.

The Screwty® can also be fitted with other blades to create a torque screwdriver. You can find these blades in our catalogue "Tools".



1. Position Screwty®,
2. tighten connector,
3. finished!

Use of an M12 Screwty®



Use of an M23 Screwty®

**Screwty® standard****Ordering data**

Type	Use	Qty.	Order No.
Screwty® M12	moulded M12 lines	1	1900000000
Screwty® M8	moulded M8 lines	1	1900010000
Screwty® M12 F	M12 plugs for custom assembly	1	1900020000
Screwty® M8 F	M8 plugs for custom assembly	1	1900030000

**Screwty® Set****Ordering data**

Type	Qty.	Order No.
Screwty® Set	1	1910000000
<b>Fittings</b>		
Type	Contents	
Screwty® Set	1x Screwty® standard handle + 1 M12, M8, M12 F, M8 F attachments	

**Screwty® attachments****Ordering data**

Type	Qty.	Order No.
Screwty® M12 KO o. SD	1	1900100000
Screwty® M8 KO o. SD	1	1900110000
Screwty® M12F KO o. SD	1	1900120000
Screwty® M8F KO o. SD	1	1900130000
Screwty® M23 LS	1	1981560000

**Legend:**

F	for custom assemblies
DM	torque
KO o. SD	ratchet only (attachment)
Screwty®	screwdriver
Screwty® DM	torque screwdriver, interchangeable blade
WK	interchangeable blade
LS	power plug

**Screwty® with torque fitting**

Setting aid for Screwty® with torque fitting (included)

**Ordering data**

Type	Use	Qty.	Order No.
Screwty®-M12-DM	moulded M12 lines with torque requirement	1	1900001000
Screwty®-M8-DM	moulded M8 lines with torque requirement	1	1900011000
Screwty®-M12 F-DM	M12 plugs, custom assembly with torque requirement	1	1900021000
Screwty®-M8 F-DM	M8 plugs, custom assembly with torque requirement	1	1900031000

**Fittings**

Type	Contents
Screwty®-M12-DM	1 interchangeable blade, 1 torque handle, 1 setting aid for Screwty® torque, 1 Screwty® M12 attachment
Screwty®-M8-DM	1 interchangeable blade, 1 torque handle, 1 setting aid for Screwty® torque, 1 Screwty® M18 attachment
Screwty®-M12 F-DM	1 interchangeable blade, 1 torque handle, 1 setting aid for Screwty® torque, 1 Screwty® M12 F attachment
Screwty®-M8 F-DM	1 interchangeable blade, 1 torque handle, 1 setting aid for Screwty® torque, 1 Screwty® M18 F attachment

**Screwty® Set-DM****Ordering data**

Type	Qty.	Order No.
Screwty® Set-DM	1	1920000000
<b>Fittings</b>		
Type	Contents	
Screwty® Set-DM	1 interchangeable blade, 1 torque handle, 1 setting aid for Screwty® torque, 1 each of Screwty® M12, M8, M12 F, M8 F attachments	

**Screwty® interchangeable handle/interchangeable bit****Ordering data**

Type	Use	Qty.	Order No.
1/4" handle		1	4294820000
WK-1/4" (Screwty®)		1	1862200000

**SAI tool boxes****SAI-Screwty® Box**

- Stripping of PVC and PUR sensor/actuator cables
- Tightening of M8 and M12 round connectors with adjustable torque setting

**Accessories**

Article description	Qty.
Stripping tool Stripper 6-16 for plastic-sheathed cables up to 10 mm outside diameter	1
Torque screwdriver DMS manual for 0.5-1.7 Nm	1
Torque screwdriver DMS manual for 2.0-8.0 Nm	1
Screwty® attachment for plug-in connectors* M8	1
Screwty® attachment for plug-in connectors* M8F	1
Screwty® attachment for plug-in connectors* M12	1
Screwty® attachment for plug-in connectors* M12F	1
Carry case	1

\*) Screwing attachment for M8/10 mm; M8F/11.9 mm; M12/14.5 mm; M12/19.8 mm;  
F...male and female connectors for custom assembly .

**Ordering data**

Type	Order No.
SAI-SCREWTY BOX	1939180000

**SAI-Screwty® Tool Box**

- Screwing of M8 and M12 round connectors with adjustable torque setting
- Tightening of slot-head and cross-head screws (PZ and PH)

**Accessories**

Article description	Qty.
Torque screwdriver DMS manual for 0.5-1.7 Nm	1
Torque screwdriver DMS manual for 2.0-8.0 Nm	1
Inbus 2.5 / 3.0 / 4.0	1
Slot 0.5 x 3.0	1
Slot 0.8 x 4.0	1
Slot 0.6 x 3.5	1
Cross PH0	1
Cross PH1	1
Cross PH1	1
Torx® T8	1
Torx® T10	1
Torx® T20	1
Torx® T25	1
Screwty® attachment for plug-in connectors* M8	1
Screwty® attachment for plug-in connectors* M8F	1
Screwty® attachment for plug-in connectors* M12	1
Screwty® attachment for plug-in connectors* M12F	1
Carry case	1

\*) Screwing attachment for M8/10 mm; M8F/11.9 mm; M12/14.5 mm; M12/19.8 mm;  
F...male and female connectors for custom assembly .

**Ordering data**

Type	Order No.
SAI-SCREWTY TOOL BOX	1939170000

**Cutting tools**

- Cutting formation for different cable sizes increases the quality of the cuts for smaller cross-sections
- Not suitable for steel wires, steel-armoured cables, aluminium alloys and hard-drawn copper conductors!
- Cutting without deformation of the conductor

**KT 8****KT 12****Technical data****Max. cutting performance, copper cable**

Copper cable - solid, max.	mm <sup>2</sup> /-
Copper cable - stranded, max.	mm <sup>2</sup> /-
Copper cable - flexible, max.	mm <sup>2</sup> /-
Copper cable, max. diameter	mm

**Max. cutting performance, aluminium cable**

Stranded aluminium cable, max (mm <sup>2</sup> )	mm <sup>2</sup> /-
Stranded aluminium cable, max. diameter	mm
Single-core aluminium cable, max.(mm <sup>2</sup> )	mm <sup>2</sup>

**Data / telephone / control cable**

Data / telephone / control cable, max. Ø	mm
--	----

**Tool data**

Length / Width / Height	mm
Weight	g

**Note****Ordering data****Version****KT 8**

16 / 6	
16 / 6	
16 / 6	
8	
16 / 6	
8	
16	
8	
165 / 65 / 25	
180	
Tool closed	

**KT 12**

16 / 6	
25 / 3	
35 / 2	
12	
25 / 6	
8	
25	
12	
215 / 66 / 28	
300	
Tool closed	

**Note**

Type	Qty.	Order No.
KT 8	1	9002650000

Type	Qty.	Order No.
KT 12	1	9002660000

## Sheathing and insulation stripping tools

### Special sheathing and insulation stripping tools

- Quick and accurate stripping
- No need to adjust cutting depth
- No damage to inner conductors

### Stripper 6-16



#### Stripper 6-16

The Stripper 6-16 insulation stripping tool is for removing the outer sheath of sensor cables. No damage to inner wires can occur because the blades have a specially ground surface. Adjusting the tool to different cross-sections is unnecessary. The visual scale of 15 to 20 mm enables quick and precise stripping of outer insulation.

### AM 12

For UTP and STP data cables



- Cutting of UTP and STP data cables and other flexible copper cables with a diameter of up to 4 mm<sup>2</sup> (~AWG11)
- Stripping of the outer insulation of UTP and STP data cables and other round cables with Ø approx. 0.5 ... 12.5 mm
- No damage to the shielding or conductor due to adjustable stripping blade
- Length end stop for repeated cutting and stripping lengths

### Technical data

#### Max. stripping performance

Cable model	
Conductor diameter	mm
Depth of cut	

#### Cutting performance

UTP and STP data cables, max. diameter	mm
Copper cable - flexible, max.	mm <sup>2</sup>

#### Tool data

Length	mm
Weight	g

#### Note

### Ordering data

#### Version

Type	Qty.	Order No.
STRIPPER 6-16 RED-LINE	1	9203110000

#### Note

### Accessories

#### Note

#### Stripper 6-16

suitable for PVC and PUR cables


#### AM 12

UTP and STP data cables

0.5...12.5

adjustable

8

4

97

36

#### Type

Type	Qty.	Order No.
AM 12	1	9030060000

#### Type

Type	Qty.	Order No.
Sheathing stripper		

## Stripping and cutting tools


- For flexible and solid conductors with PVC insulation
- Cable with double insulation in two processing steps without special adjustment
- Automatic opening of clamping jaws after stripping
- No play in self-adjusting cutting unit
- Long-lasting
- No splicing of single conductors
- Optimised ergonomic design
- Stripping length adjustable via end stop
- Adjustable for different insulation thicknesses
- Selectable partial stripping
- Removable handle shells
- Fold-out cutting protection
- Personalised labelling with ESG device markers

## stripax®

0.08...10 mm<sup>2</sup>



- Stripping: PVC-insulated flexible conductors from 0.08...10 mm<sup>2</sup> (~ AWG 28...7)
- Cutting: PVC-insulated flexible conductors from 0.08...10 mm<sup>2</sup> (~ AWG 28...7)
- Processing of multi-conductors, with thin flat ribbon cables and even multiple conductors in one operation
- No damaging of the conductor due to special, self-adjustable stripping blades



## Technical data

### Max. stripping performance

Cable type	
Wire cross-section, min. / max.	mm <sup>2</sup>
Stripping length , max.	mm

### Cutting performance

Conductor cross-section (cutting capacity)	mm <sup>2</sup>
--	-----------------

### Tool data

Length	mm
Weight	g

### Note

## Ordering data

### Version

### STRIPAX® ZERT

Flexible and solid conductors with PVC insulation

0.08...10

25

6

190

175

### Type Qty. Order No.

STRIPAX 1 9005000000

STRIPAX ZERT 1 9017330000

### Note

## Accessories

### Note

### Type Qty. Order No.

Replacement stripping blade 1 1119030000

**multi-stripax®**

**A multifunctional stripping tool for use on a multitude of conductor insulation forms and configurations – even those not covered by the standard**

**multi-stripax® the troubleshooter**




- Interchangeable stripping units
- Proper stripping of any conductor round, flat or special profiles, thanks to the specially shaped stripping blades
- Incorporates cutting function for up to 2.5 mm<sup>2</sup> solid and 6 mm<sup>2</sup> fine
- Fatigue free operation thanks to ergonomic design
- No damage to conductor or remaining insulation
- Best stripping results for industrial applications
- Stripping results reproduced accurately time and time again
- A long lasting, reliable tool thanks to its robust design
- Plus, the customary Weidmüller repair service

**Special stripping units – the answer to diverse stripping tasks**


The multi-stripax® tool, distinguished by its robust design, was developed, following customer feedback, to handle all the stripping tasks they have met with in practice.

Thanks to its interchangeable stripping units, a special solution can be found for every challenge you are likely to meet in the marketplace.

The specially shaped stripping blades guarantee perfect stripping results. The guide plates ensure the correct positioning of the wire and therefore prevent damage to the remaining wire. The clamping jaws hold the conductor with just the right force during the stripping operation and are matched to the specific situation at hand. The flexibility of the multi-stripax® to affect the result of the stripping operations depending on the different variables it encounters makes it a universal troubleshooter.

**Cutting****Positioning****Stripping****multi-stripax®****Technical data**


Cable Type	PVC, Teflon, PTE, PUR, silicone, halogen-free
Conductor cross-section, min.	2 mm
Conductor cross-section, max.	no limit (in several steps)
max. cutting capacity, fine-strand	6 mm <sup>2</sup>
max. cutting capacity, solid	2.5 mm <sup>2</sup>
max. cutting capacity, ribbon	10.2 x 4 mm
Length/Width/Height	250 / 85 / 40 mm
Weight	250 g
<b>Note</b>	

**multi-stripax® incl. stripping unit**

- High quality stripping for industrial applications
- Specially shaped stripping blades enable stripping of special types of insulation and conductor configurations
- Adjustable stop for setting stripping lengths from 2.3 to 30 mm
- Highly flexible thanks to interchangeable stripping units
- Stripping results reproduced accurately time and time again
- No damage to the conductor or insulation
- A long lasting, reliable tool thanks to its robust design
- Integral cutting function for max. 2.5 mm<sup>2</sup> solid or 6 mm<sup>2</sup> flexible cables

**Ordering data**

Illustration	Type	Qty.	Order No.	Features
1	multi-stripax® 6-16	1	9202210000	PVC-insulated cables; Cable cross-section 6 up to 16 mm <sup>2</sup> ; max. stripping lengths depends on cable design / cable type 1. station solid, stranded and flexible 6 mm <sup>2</sup> 2. station solid, stranded and flexible 10 mm <sup>2</sup> 3. station solid, stranded and flexible 16 mm <sup>2</sup> double stranded (flexible) Cutting function up to 6 mm <sup>2</sup>
1	multi-stripax® ASI	1	9202250000	ASI Bus cables 2 x 1.5 mm <sup>2</sup> flexible for PTE, PUR and EPDM insulated cables Stripping of outer insulation and inner cable Cutting function up to 6 mm <sup>2</sup>
1	multi-stripax® GKW LW	1	9205760000	Railway cable Radox GKW LW; Cable cross-section 1.0; 1.5 and 2.5 mm <sup>2</sup> max. stripping lengths depends on cable design / cable type Cutting function up to 6 mm <sup>2</sup>
2	ERAN multi-stripax®	1	9203100000	Length stop
3	ERME multi-stripax®	1	9203070000	Cutting knife

**Note****Stripping units for multi-stripax®****Stripping unit consists of:**

- Highly flexible thanks to interchangeable stripping units
- High quality stripping for industrial applications
- Specially shaped stripping blades enable stripping of special types of insulation and conductor configurations

e = solid  
m = stranded  
f = finely stranded

**Ordering data**

Type	Qty.	Order No.	Features
AIE multi-stripax® 6-16	1	9202260000	PVC-insulated cables; Cable cross-section 6 up to 16 mm <sup>2</sup> ; max. stripping lengths depends on cable design / cable type 1. station solid, stranded and flexible 6 mm <sup>2</sup> 2. station solid, stranded and flexible 10 mm <sup>2</sup> 3. station solid, stranded and flexible 16 mm <sup>2</sup> double stranded (flexible)
AIE multi-stripax® ASI	1	9202300000	ASI Bus cables 2 x 1.5 mm <sup>2</sup> flexible for PTE, PUR and EPDM insulated cables Stripping of outer insulation and inner cable
AIE multi-stripax® GKW LW	1	9205770000	Railway cable Radox GKW LW; Cable cross-section 1.0; 1.5 and 2.5 mm <sup>2</sup> max. stripping lengths depends on cable design / cable type

This tool is suitable for M23 signal connectors and power connectors.

### SAI M23 crimping tool 1



#### Technical data

Crimp contact	Wire cross-section (mm <sup>2</sup> )	Crimping mandrel adjustment	Locator position	Order No.
Crimp male, signal 1 mm	0.14	0.75	11	<b>1170150000</b>
	0.25	0.82		
	0.34	0.90		
	0.50	1.00		
	0.75	1.08		
	1.00	1.20		
Crimp female, signal 1 mm (0.08-0.56 mm <sup>2</sup> )	0.14	0.75	12	<b>1995860000</b>
	0.25	0.80		
	0.35	0.87		
	0.50	0.97		
Crimp female, signal 1 mm (0.34-1.00 mm <sup>2</sup> )	0.50	0.95	12	<b>1170180000</b>
	0.75	4.00		
	1.00	1.05		
Crimp male, signal 1.5 mm	0.14	0.75	3	<b>1170220000</b>
	0.25	0.82		
	0.35	0.90		
	0.50	0.96		
	0.75	1.03		
	1.00	1.00		
Crimp female, signal 1.5 mm	0.14	0.75	4	<b>1170230000</b>
	0.25	0.80		
	0.35	0.87		
	0.50	0.97		
Crimp female, signal 1.5 mm (0.34-1.00 mm <sup>2</sup> )	0.50	0.95	4	<b>1170240000</b>
	0.75	1.00		
	1.00	1.05		
Crimp male, signal 2 mm	0.75	1.30	5	<b>1170250000</b>
	1.00	1.40		
	1.50	1.55		
	2.50	1.75		
Crimp female, signal 2 mm	0.75	1.30	6	<b>1170260000</b>
	1.00	1.40		
	1.50	1.55		
	2.50	1.75		
Crimp male, power 1 mm	0.14	0.75	1	<b>1170390000</b>
	0.25	0.80		
	0.35	0.85		
	0.50	1.03		
	0.75	1.08		
	1.00	1.13		
Crimp female, power 1 mm	0.14	0.75	2	<b>1995830000</b>
	0.25	0.80		
	0.35	0.85		
	0.50	0.89		
	0.75	0.95		
	1.00	1.02		
Crimp male, power 2 mm	0.75	1.20	7	<b>1170400000</b>
	1.00	1.40		
	1.50	1.55		
	2.50	1.70		
Crimp male, power 2 mm	2.50	1.47	7	<b>1170410000</b>
	4.00	1.60		
	0.75	1.20		
Crimp female, power 2 mm	1.00	1.40	8	<b>1995820000</b>
	1.50	1.55		
	2.50	1.70		
Crimp female, power 2 mm	2.50	1.47	8	<b>1170420000</b>
	4.00	1.60		

#### Ordering data

Type	Order No.
SAI M23 CRIMPING TOOL 1	<b>1203840000</b>


#### Adjusting the crimping dimensions

The adjustment mechanism is used to set the crimping depth of the crimping mandrel as described below.

The adjusting dial is used to prepare the infeed; the dial can be turned clockwise (for decreasing the dimension) or counter-clockwise (for increasing the dimension).

#### Adjustment precision

- 1 division mark on the dial v 1/100 mm adjustment
- 1 complete revolution of the dial v 0.2 mm adjustment read from scale
- 5 revolutions of the dial v 1 mm adjustment read from scale



#### Verifying the crimping dimension

The four-mandrel crimping tool is pre-set at the factory.

The actual crimping size should still be checked periodically. It should be checked using the plug gauge (Ø 2.0 mm) that is included with the crimping tool as described below. Use the dial on the stationary tool shank to set the size to 2.0 mm on the scale. Set to the zero-point tick mark on the dial and close the tool. (Refer to the diagram showing the crimping size adjustment.) At this setting, it should be possible to move the 2.00-mm-Ø plug gauge without any play or extra room. If this is not possible, then the size deviation (+/-) can be determined using the dial's fine-adjustment mechanism. If this size check reveals that the tool is not within the tolerance range specified by the manufacturer of the contacts, then you should contact the manufacturer of the tool for further inspection.

#### Servicing and maintenance

Before you start to use the hand crimping tool, it must be clean and in proper working condition. Crimp residue or fragments must be removed from the crimping jaws and locator. The joints should be regularly lubricated using machine oil to protect them from dirt. Make sure that all bolts are secured with locking rings.

This tool is only suitable for M23 signal connectors.

#### Operation mode

The following table specifies the locator positions and the crimping dimensions for various crimping contacts. The contact is inserted through the tool into the locator; this ensures the proper crimping position. The inserted contact is secured by closing gently (approximately to first snap-close level). Now the cable can be easily inserted and it is not possible for the contact to fall out. The tool must be pressed together until it reaches the end stop position in order to function properly. It is then able to open automatically which brings the crimping process to a close in the intended manner.

#### SAI M23 crimping tool 2




#### Adjusting the crimping dimensions

The adjustment mechanism is used to set the crimping depth of the crimping mandrel as described below. The adjusting dial is used to prepare the infeed; the dial can be turned clockwise (for decreasing the dimension) or counter-clockwise (for increasing the dimension).

#### Adjustment precision

- 1 division mark on the dial v 1/100 mm adjustment
- 1 complete revolution of the dial v 0.2 mm adjustment read from scale
- 5 revolutions of the dial v 1 mm adjustment read from scale



#### Verifying the crimping dimension

The four-mandrel crimping tool is pre-set at the factory. The actual crimping size should still be checked periodically. It should be checked using the plug gauge ( $\varnothing 1.0$  mm) that is included with the crimping tool as described below. Use the dial on the stationary tool shank to set the size to 1.0 mm on the scale. Set to the zero-point tick mark on the dial and close the tool. (Refer to the diagram showing the crimping size adjustment.) At this setting, it should be possible to move the 1.00-mm- $\varnothing$  plug gauge without any play or extra room. If this is not possible, then the size deviation (+/-) can be determined using the dial's fine-adjustment mechanism. If this size check reveals that the tool is not within the tolerance range specified by the manufacturer of the contacts, then you should contact the manufacturer of the tool for further inspection.

#### Servicing and maintenance

Before you start to use the hand crimping tool, it must be clean and in proper working condition. Crimp residue or fragments must be removed from the crimping jaws and locator. The joints should be regularly lubricated using machine oil to protect them from dirt. Make sure that all bolts are secured with locking rings.

#### Technical data

Crimp contact	Wire cross-section (mm <sup>2</sup> )	Crimping mandrel adjustment	Locator position	Order No.
Crimp male 1 mm	0.14	0.86	1	<b>1170150000</b>
	0.25	0.90		
	0.34	0.95		
	0.56	0.98		
	0.75	1.03		
	1.00	1.08		
Crimp female 1 mm (0.08-0.56 mm <sup>2</sup> )	0.08	0.75	2	<b>1995860000</b>
	0.14	0.78		
	0.25	0.82		
	0.34	0.86		
	0.56	0.90		
Crimp female 1 mm (0.34-1.00 mm <sup>2</sup> )	0.34	0.77	2	<b>1170180000</b>
	0.56	0.82		
	0.75	0.88		
	1.00	0.95		
Crimp male 1.5 mm	0.14	0.65	3	<b>1170220000</b>
	0.25	0.68		
	0.34	0.72		
	0.56	0.81		
	0.75	0.95		
	1.00	1.07		
Crimp female 1.5 mm (0.14-0.75 mm <sup>2</sup> )	0.14	0.70		<b>1170230000</b>
	0.25	0.73		
	0.34	0.77		
	0.56	0.85		
	0.75	1.05		
Crimp female 1.5 mm (0.34-1.00 mm <sup>2</sup> )	0.34	0.88		<b>1170240000</b>
	0.56	0.95		
	0.75	1.05		
	1.00	1.13		
Crimp male 2.0 mm	0.75	1.20		<b>1170250000</b>
	1.00	1.35		
	1.50	1.45		
	2.50	1.60		
Crimp female 2.0 mm	0.75	1.25		<b>1170260000</b>
	1.00	1.35		
	1.50	1.45		
	2.50	1.60		


#### Ordering data

Type	Order No.
SAI M23 CRIMPING TOOL 2	<b>1203960000</b>

# SlimFix Clip

The SlimFix Clip combines two advantages in one: its unique closure mechanism offers the reliability of a closed marker with the ease of attaching an open marker. The Clip closure mechanism also allows quick, no fuss attachment of the markers after the wires have been installed. SlimFix Clip markers are suitable for wires and cables with external diameters up to 5 mm. Long sequences of characters are possible on the large marking surface – up to 30 mm.

- Halogen-free, flammability class V2 material
- Narrow markers with reliable attachment thanks to compensation feature
- Clip closure mechanism ensures permanent attachment following wire installation
- Rapid attachment without tools
- Three sizes for wire cross-sections from 0.5 – 10.0 mm<sup>2</sup>
- Available in lengths of 12, 21 and 30 mm
- Markers available in the proven MultiCard format
- Additional marking surface for precise assignment to projects
- Custom-printed markers supplied to your specifications



## Technical data

Material	Polyamide 66, halogen-free
UL 94 flammability rating	V2
Temperature range	-40 °C to 100 °C
Printing	black

## Ordering data

Type	Wire, ext. ø	Wire cross-section
SFC 0	1.5 - 2.5 mm	0.5 - 1.0 mm <sup>2</sup>
SFC 1	2.0 - 3.5 mm	0.75 - 2.5 mm <sup>2</sup>
SFC 2	2.5 - 5.0 mm	2.5 - 4.0 mm <sup>2</sup>
SFC 2.5	4.0 - 6.0 mm	4.0 - 10.0 mm <sup>2</sup>
SFC 3	3.5 - 7.0 mm	4.0 - 10.0 mm <sup>2</sup>
Colour	Other colours on request	

● brown      ● orange      ● green  
● violet      ● grey

Special printing      Specify special printing and colours per diskette, Excel file or using the M-Print® PRO software.

Minimum order quantity      1 pack

**Note:** SlimFix Clip markers can be printed with PrintJet.



## SFC - blank

### Technical data

Material	Polyamide
UL 94 flammability rating	V2
Min. temperature, continuous	-40 °C
Max. temperature, continuous	100 °C

### Ordering data

Type	Length	Qty.	Order No. white	Order No. yellow	Order No. blue	Order No. red	Custom printing
SFC 0/12	12	200	1813130000	1813160000	1813170000	1813150000	
SFC 1/12	12	200	1747320001	1747320004	1747320002	1747320003	
SFC 2/12	12	120	1758320001	1758320004	1758320002	1758320003	
SFC 2.5/12	12	120	1062000000	1062010000	1062030000	1062020000	1062040000
SFC 3/12	12	80	1025220000	1025230000	1025250000	1025240000	1025550000
SFC 0/21	21	200	1813190000	1813210000	1813220000	1813200000	
SFC 1/21	21	200	1779080001	1779080004	1779080002	1779080003	
SFC 2/21	21	120	1805810000	1805780000	1805770000	1805790000	
SFC 2.5/21	21	120	1062050000	1062070000	1062090000	1062080000	1062110000
SFC 3/21	21	80	1025260000	1025270000	1025300000	1025290000	1025560000
SFC 0/30	30	150	1813240000	1813260000	1813270000	1813250000	
SFC 1/30	30	150	1805760000	1805730000	1805720000	1805740000	
SFC 2/30	30	90	1805870000	1805830000	1805820000	1805850000	
SFC 3/30	30	60	1025310000	1025320000	1025340000	1025330000	1025570000


# Marker tags for sensor cables

## Sleeves for marking sensor cables

Unique marking and identification of sensor/actuator cables can be achieved with a marker tag. Each cable has a sleeve that accepts a marker tag TM-I 18. Cables open at one end have one sleeve, connecting cables have two marker sleeves. The TM-I 18 is available in various colours.

## Ordering data

Type	Colour	Order No.
<b>Sleeve</b>		
TM 203/18 VO	transparent	1798480000
TM 4/18 HF/HB	transparent	1719850000
<b>Marker</b>		
TM-I 18 NEUTRAL WS	white	1718431044
TM-I 18 NEUTRAL GE	yellow	1718431687



The Weidmüller PrintJet PRO identification system prints marker tags quickly, reliably and individually.

The PrintJet PRO inkjet printer prints markers for electric connectivity. These markers can be used for clear equipment identification on devices, cables and connectors. The labelling makes servicing, maintenance and troubleshooting much easier. Water-based ink is used for the spot colour printing. The print is crystal clear and resistant to environmental influences.

The PrintJet PRO prints plastic markers in **MultiCard** format. In combination with the user-friendly **M-Print® PRO** software and the attached loader, the printer becomes an essential part of the production. The inkjet process being used, the subsequent fusing, as well as the printer cartridge and ink have all been specially adapted by Weidmüller for industrial use. The printer has excellent long-term use capabilities, thanks to its integrated loader.

## Ordering data

PrintJet PRO	
Type	Order No.
PrintJet PRO 115V	1024050000
PrintJet PRO 230V	
Accessories	
PJ PRO TNTK INK SET COL	Ink tank starter set, colour
PJ PRO TNTK INK K	● Ink tank Black
PJ PRO TNTK INK C	● Ink tank Cyan
PJ PRO TNTK INK M	● Ink tank Magenta
PJ PRO TNTK INK Y	● Ink tank Yellow
PJ PRO TNNAW	Ink collecting tray
	1027110000
	1027040000
	1027050000
	1027060000
	1027070000
	1024140000



# Marker tags for distributors

Marker tags can be affixed to distributors to ensure unique identification. For marking our standard M12 products, ESG 9/20 tags are used. M8 and M5 distributors can be labelled with WS 10/5 and DEK 5 markers. For labelling metal distributors, self-adhesive ESG 9/17 must be used.

In the case of the SAI Active family, we differentiate between SAI Active Universal and SAI Active Line. For labelling of Active Universal, we offer ESG 8/13.5/43.3 SAI AU. For labelling of Active Line, the ESG 9/6 is used.

All of these markers are available in MultiCard format and can therefore also be printed using our innovative PrintJet PRO marking solutions.

## DEK for marking of M8 and M5 distributors



### DEK - Blank

Type	Colour	Width/Length	Qty.	Order No.
DEK 5/5 MC	white	5 mm/5 mm	1000	1609801044

### DEK - Custom printing

Type	Colour	Width/Length	Qty.	Order No.
DEK 5/5 MC	white	5 mm/5 mm	200	1609810000

## ESG for marking of M12 distributors



### Ordering data

Type for SAI Active Line	Colour	Width/Length	Qty.	Order No.
ESG 9/20 MC NEUTRAL WS	white	20 mm/9 mm	200	1609940000

## WS for marking of M8 and M5 distributors



### WS - Blank

Type	Colour	Width/Length	Qty.	Order No.
WS 10/5 MC	white	5 mm/10 mm	720	1635000000
WS 15/5 MC	white	5 mm/15 mm	480	1609880000

### WS - Custom printing

Type	Colour	Width/Length	Qty.	Order No.
WS 10/5 MC	white	5 mm/10 mm	144	1635010000
WS 15/5 MC	white	5 mm/15 mm	96	1609890000

## ESG for marking of M12 Universal distributors



### Ordering data

Type for SAI Active Universal	Colour	Width/Length	Qty.	Order No.
ESG 8/13.5/43.3 SAI AU	transparent	13.5 mm/43.3 mm/8 mm	5	1912130000

# Technical appendix

---

<b>Technical appendix</b>		
Sensor Actuator Interface Passive – Overview		W.2
Coding systems		W.4
Sensor Actuator Interface Passive – Connection plan		W.9
Cable overview		W.10
Drilling templates		W.12
Resistance Charts		W.22

---

W

# Sensor Actuator Interface Passive – Overview



## Technical data

Material data		
Insulating material	- Housing	
	- Contact carrier	
Base material	- Contact	
	- Screw socket	
Temperature range		°C
Colour	- Housing	
	- PG & contact carrier	
Cable sheathing		
Cable type		
O-ring		
Housing seal		
Type of connection, hood version		
Clamping range		mm <sup>2</sup>
AWG No.		
Stripping length, hood version		mm
Stripping length, screw version		mm
Stripping length, tension clamp version		mm
Contact surface		
- BL3.5 / B2L		
Contact base material		
- BL3.5 / B2L		
Torques		
- Hoods	Nm	
- Blanking plugs	Nm	
Mechanical data		
Ingress Protection Class*	IP	
Suitability for cable carrier	cycles at 15d	
IDC connection		
Max. connect. frequency of a cable with same cross-section		
Stripping length	mm	
Conductor cross-section (flexible)	mm <sup>2</sup>	
Smallest strand diameter	mm	
Conductor insulation material		
Conductor outside diameter	mm	
Cable outside diameter	mm	
Pin assignment		
Electrical data to VDE 110 (Apr 97)		
Operating voltage	V-	
Max. current carrying capacity per I/O signal	A	
- total with single supply	A	
- total with dual supply	A	
Rated voltage	V <sub>eff</sub>	
Test voltage	kV	
Pollution severity		
Insulation resistance	Ω	
Other data		
Dimensions	see chapter G	
Fixing holes	see chapter G	
Function indicators		
- for operating voltage	1 x LED, green	
- for I/O function	1 x LED, yellow (per function)	
Current isolation (SAI... -M)		
Cable strain relief (SAI... -M)		
Max. cable diameter (SAI... -M)	mm	

\* only when plugged in and secured

**Technical data****Material data**

Insulating material	- Housing
	- Contact carrier
Base material	- Contact
	- Screw socket
Temperature range	°C

Colour	- Housing
	- PG & contact carrier

Cable sheathing

Cable type

O-ring

Housing seal

Type of connection, hood version

Clamping range

AWG No.

Stripping length, hood version

Stripping length, screw version

Stripping length, tension clamp version

Contact surface

- BL3.5 / B2L

Contact base material

- BL3.5 / B2L

Torques

- Hoods

- Blanking plugs

Nm

Nm

Mechanical data

Ingress Protection Class\*

IP

Suitability for cable carrier

cycles at 15d

**IDC connection**

Max. connect. frequency of a cable with same cross-section

Stripping length

mm

Conductor cross-section (flexible)

mm<sup>2</sup>

Smallest strand diameter

mm

Conductor insulation material

mm

Conductor outside diameter

mm

Cable outside diameter

mm

Pin assignment

**Electrical data to VDE 110 (Apr 97)**

Operating voltage

V-

Max. current carrying capacity per I/O signal

A

- total with single supply

A

- total with dual supply

A

Rated voltage

V<sub>eff</sub>

Test voltage

kV<sub>eff</sub>

Pollution severity

Insulation resistance

Ω

**Other data**

Dimensions

see chapter G

Fixing holes

see chapter G

Function indicators

- for operating voltage

- for I/O function

Current isolation (SAI... -M)

Cable strain relief (SAI... -M)

Max. cable diameter (SAI... -M)

mm

\* only when plugged in and secured

**IDC**

PBT (UL 94 VO)

PBT (UL 94 VO)

CuZn, pre-nickelized &amp; gold-plated

CuZn, nickel-plated

-20 ... +90

grey, RAL 7032

black

PUR

PUR/PVC

Viton

foamed PUR

screw/tension clamp

0.08 ... 1.5

22 ... 14

100

7

10

tin

Cu alloy

**M12 Push-Pull**

PA 6 GF

PBT (UL 94 VO)

CuSn6

CuZn, nickel-plated

-25 ... +80

grey, RAL 7032

black

PUR

halogen-free, UL

Viton

foamed PUR

tension clamp

0.08 ... 1.5

22 ... 14

100

7

10


tin

Cu alloy

# Contact assignment


## SAI-M/SAI-F - IDC

**3-pole:**



Pole	Colour code	Assignment
1	brown	+ 24 V DC
2	white	input/output
3	blue	0 V DC


**4-pole:**




Pole	Colour code	Assignment
1	brown	+ 24 V DC
2	no colour	input/output 2
3	blue	0 V DC
4	black	input/output 1

## M23

**12-pole:**




Male




Female

Pole	Colour code	Plug-in station	Contact M12
1	white	1	4
2	green	2	4
3	yellow	3	4
4	grey	4	4
5	pink	5	4
6	red	6	4
7	black	7	4
8	violet	8	4
9	blue (-)	1- 8	3
10	blue (-)	1- 8	3
11	brown (+)	1- 8	1
12	green-yellow (PE)	1- 8	5

**19-pole:**



Male



Female

Pole	Colour code	Plug-in station	Contact M12
1	violet	8	4
2	red	6	4
3	grey	4	4
4	red/blue	2	2
5	green	2	4
7	grey/pink	1	2
8	white/green	3	2
9	white/yellow	5	2
10	white/grey	7	2
11	black	7	4
13	yellow/brown	6	2
14	brown/green	4	2
15	white	1	4
16	yellow	3	4
17	pink	5	4
18	grey/brown	8	2
6	blue (-)	1- 8	3
12	green-yellow (PE)	1- 8	5
19	brown (+)	1- 8	1

# Coding systems for round connectors



Round connectors are used for wiring sensors, actuators and data cables.

To prevent wiring errors, there are different coding systems: for M12, the plug-in connectors are coded A, B and D. The M12 A-coded plug-in connector is available with 3 to 5 pins, 6 to 8 and 9 to 12 pins. There is no coding for M8 and M5.

The arrangement of the pins in the M8 plug-in connector (asymmetrical) rules out the possibility of 3- and 4-pole M8 plug-in connectors being connected together. In the case of M5 plug-in connectors, 3- and 4-pole plug-in connectors can be connected together since the pins are symmetrically arranged.

## A-coded, M12, Sensor wiring

### 2-to 5-pole:





Pole	Colour code	Assignment
1	brown	+ 24 V DC
2	white	input/output 2*
3	blue	0 V DC
4	black	input/output 1
5	grey	FE
	Housing	shield**

\*) = only 5-pole version      \*\*) = only with shielded version

## A-coded, M12, PROFIBUS-PA

### 2-to 5-pole:





Pole	Colour code	Assignment
1	red	DATA-B
3	green	DATA-A
	Housing	shield




## A-coded, M12, CANopen/DeviceNet™

### 2-to 5-pole:




Pole	Colour code	Assignment
1		shield (drain wire)
2	red	V+
3	black	V- (CAN_GND)
4	white	CAN_H signal
5	blue	CAN_L signal

## Coding systems


**B-coded, M12, PROFIBUS-DP****3-to 5-pole:**

Male




Female

Pin	Colour code	Assignment
2	green	Data A
4	red	Data B
Housing		shield


**D-coded, M12, Industrial Ethernet****4-pole:**

Male




Female

Pin	Colour code	Assignment
1	yellow	TD+ (transmit data +)
2	white	RD+ (receive data +)
3	orange	TD- (transmit data -)
4	blue	RD- (receive data -)
Housing		shield


**M12****8-pole:**

Male




Female

Pole	Colour code	Assignment
1	white	signal
2	brown	signal
3	green	signal
4	yellow	signal
5	grey	+ 24 V DC
6	pink	signal
7	blue	0 V DC
8	red	signal


**M12****12-pole:**

Male




Female

Pole	Colour code	Assignment
1	brown	+ 24 V DC
2	blue	0 V DC
3	white	input/output 1
4	green	input/output 1
5	pink	input/output 1
6	yellow	input/output 1
7	black	input/output 1
8	grey	input/output 1
9	red	input/output 1
10	violet	input/output 1
11	grey/pink	input/output 1
12	red/blue	input/output 1


**M8 connector position****3-pole:**

Male




Female

Pin	Colour code	Assignment
1	brown	+ 24 V DC
3	blue	0 V DC
4	black	input/output 1



**M8 connector position****4-pole:**

Male




Female


Pin	Colour code	Assignment
1	brown	+ 24 V DC
2	white	input/output 2
3	blue	0 V DC
4	black	input/output 1

**M5 connector position****4-pole:**

Pin	Colour code	Assignment
1	brown	+ 24 V DC
2	white	input/output 2
3	blue	0 V DC
4	black	input/output 1


**M23****12-pole:**

Male




Female

Pole	Colour code	Assignment	Cross-section
1	white	signal	0.34
2	green	signal	0.34
3	yellow	signal	0.34
4	grey	signal	0.34
5	pink	signal	0.34
6	red	signal	0.34
7	black	signal	0.34
8	violet	signal	0.34
9	nc	nc	nc
10	blue	0 V DC	0.75
11	brown	+ 24 V DC	0.75
12	green/yellow	PE	0.75

**M23****19-pole:**

Male



Female

Pole	Colour code	Assignment	Cross-section
1	violet	signal	0.34
2	red	signal	0.34
3	grey	signal	0.34
4	red/blue	signal	0.34
5	green	signal	0.34
6	blue	0 V DC	0.75
7	grey/pink	signal	0.34
8	white/green	signal	0.34
9	white/yellow	signal	0.34
10	white/grey	signal	0.34
11	black	signal	0.34
12	green/yellow	PE	0.75
13	yellow/brown	signal	0.34
14	brown/green	signal	0.34
15	white	signal	0.34
16	yellow	signal	0.34
17	pink	signal	0.34
18	grey/brown	signal	0.34
19	brown	+ 24 V DC	0.75

# Sensor Actuator Interface Passive – Connection plan

## Connection plan

Terminal Connection No.	Connector position	M5/M8-contact		M12- contact		IDC-contact		Potential	Conductor colour	
		3-pole	4-pole	3-pole	4-pole	3-pole	4-pole		Conductor colour	Colour code
1	=	1	4	4	4	2	4	E/A 1-1	white	WH
2	=	2	4	4	4	2	4	E/A 2-1	green	GN
3	=	3	4	4	4	2	4	E/A 3-1	yellow	YE
4	=	4	4	4	4	2	4	E/A 4-1	grey	GY
5	=	5	4	4	4	2	4	E/A 5-1	pink	PK
6	=	6	4	4	4	2	4	E/A 6-1	red	RD
7	=	7	4	4	4	2	4	E/A 7-1	black	BK
8	=	8	4	4	4	2	4	E/A 8-1	violet	VT
9	=	1	-	2	2*	2		E/A 1-2	grey/pink	GYPK
10	=	2	-	2	2*	2		E/A 2-2	red/blue	RDBL
11	=	3	-	2	2*	2		E/A 3-2	white/green	WHGN
12	=	4	-	2	2*	2		E/A 4-2	brown/green	BNGN
13	=	5	-	2	2*	2		E/A 5-2	white/yellow	WHYE
14	=	6	-	2	2*	2		E/A 6-2	yellow/brown	YEBC
15	=	7	-	2	2*	2		E/A 7-2	white/grey	WHGY
16	=	8	-	2	2*	2		E/A 8-2	grey/brown	GYBN
17	=	1, 3, 5, 7	1	1	1	1		U1 + (24 V DC)	brown	BN
18	=	1, 3, 5, 7	3	3	3	3		U1 - (0 V)	blue	BU
19	=	2, 4, 6, 8	-	-	1	1		U2 + (24 V DC)	red*	RD*
20	=	2, 4, 6, 8	-	-	3	3		U2 - (0 V)	black*	BK*
21	=	1, 2, 3, 4, 5, 6, 7, 8	-	-	5	-	-	PE	green/yellow	GNYE


\* Contact used in 5-pole version only

## Plug insert, hood version

### Note:

SAI distributors with fixed cable have a single supply conductor as standard. The voltage U1 is supplied to all the sockets. An SAI distributor with fixed cable but with separate supply voltage is available on request.

### Pin assignment



### Tension clamp connection



### Screw connection




# Cable overview


Cables	Identification in article designation	Cable gland	Wire number / cross-section	Colour	Colour coding	Suitable for torsion	Wire core insulation	
<b>M8 unshielded</b>								
PVC	V	M8	3x0.25 mm <sup>2</sup>	black	BR,BL,SW	No	PVC	
	V	M8	4x0.25 mm <sup>2</sup>	black	BR,WS,BL,SW	No	PVC	
PUR halogen-free	U	M8	3x0.25 mm <sup>2</sup>	black	BR,BL,SW	No	TPM	
	U	M8	4x0.25 mm <sup>2</sup>	black	BR,WS,BL,SW	No	TPM	
PUR halogen-free yellow	UGE	M8	3x0.25 mm <sup>2</sup>	yellow	BR,BL,SW	No	TPE	
	UGE	M8	4x0.25 mm <sup>2</sup>	yellow	BR,WS,BL,SW	No	TPE	
PUR resistant to welding beads	T	M8	3x0.34 mm <sup>2</sup>	black	BR,BL,SW	Yes	TPE	
	T	M8	4x0.34 mm <sup>2</sup>	black	BR,WS,BL,SW	Yes	TPE	
<b>M8 shielded</b>								
PUR halogen-free	U	M8	3x0.34 mm <sup>2</sup>	black	BR,BL,SW	No	PP	
	U	M8	4x0.34 mm <sup>2</sup>	black	BR,WS,BL,SW	No	PP	
<b>M12 unshielded</b>								
PVC	V	M12	3x0.34 mm <sup>2</sup>	black	BR,BL,SW	No	PVC	
	V	M12	4x0.34 mm <sup>2</sup>	black	BR,WS,BL,SW	No	PVC	
	V	M12	5x0.34 mm <sup>2</sup>	black	BR,WS,BL,SW,GR	No	PVC	
PUR halogen-free	U	M12	3x0.34 mm <sup>2</sup>	black	BR,BL,SW	No	TPM	
	U	M12	4x0.34 mm <sup>2</sup>	black	BR,WS,BL,SW	No	TPM	
	U	M12	5x0.34 mm <sup>2</sup>	black	BR,WS,BL,SW,GR	No	TPM	
	U	M12	8x0.25 mm <sup>2</sup>	black	BR,WS,BL,GR,GN,GE,RS,RT	No	PP	
PUR halogen-free yellow	UGE	M12	3x0.34 mm <sup>2</sup>	yellow	BR,BL,SW	No	TPE	
	UGE	M12	4x0.34 mm <sup>2</sup>	yellow	BR,WS,BL,SW	No	TPE	
	UGE	M12	5x0.34 mm <sup>2</sup>	yellow	BR,WS,BL,SW,GR	No	TPE	
PUR resistant to welding beads	T	M12	3x0.34 mm <sup>2</sup>	black	BR,BL,SW	Yes	TPE	
	T	M12	4x0.34 mm <sup>2</sup>	black	BR,WS,BL,SW	Yes	TPE	
	T	M12	5x0.34 mm <sup>2</sup>	black	BR,WS,BL,SW,GR	Yes	TPE	
<b>M12 shielded</b>								
PUR halogen-free	U	M12	3x0.34 mm <sup>2</sup>	black	BR,BL,SW	No	TPE	
	U	M12	4x0.34 mm <sup>2</sup>	black	BR,WS,BL,SW	No	TPE	
	U	M12	5x0.34 mm <sup>2</sup>	black	BR,WS,BL,SW,GR	No	TPE	
	U	M12	8x0.25 mm <sup>2</sup>	black	BR,WS,BL,GR,GN,GE,RS,RT	No	PP	
<b>Data cables</b>								
<b>Universal Pro (SubBus)</b>								
PUR halogen-free	U-SB	M8	4x0.34 mm <sup>2</sup>	black	BR,WS,BL,SW	No	PP	
TYPE A	C5AS4VG	M12	4xAWG 22	green	WS,BL,OR,GE	No	PE	
TYPE B	C5DS4VG	M12	4xAWG 22	green	WS,BL,OR,GE	No	PE	
TYPE C	C5DD4UG	M12/RJ45	4xAWG 22	green	WS,BL,OR,GE	No	PE	
<b>EtherCat</b>								
PUR halogen-free	UIE	M8	4x0.15 mm <sup>2</sup>	green	BL,OR,WSBL,WSOR	No	PP	
<b>PROFIBUS DP</b>								
PUR halogen-free	D	M12	2x0.24 mm <sup>2</sup>	violet	RT,GN	No	TPE	
PVC	E	M12	2x0.34 mm <sup>2</sup>	violet	RT,GN	No	PVC	
<b>PROFIBUS PA</b>								
PVC	M	M12	2x1.0 mm <sup>2</sup>	black	RT,GN	No	PE	
PVC	M	M12	2x1.0 mm <sup>2</sup>	blue	RT,GN	No	PE	
<b>CANDeviceNet™</b>								
PUR halogen-free	A	M12	2x0.22 mm <sup>2</sup> + 2x0.34 mm <sup>2</sup>	black	WS,BL (0.22 mm <sup>2</sup> ), RT,SW (0.34 mm <sup>2</sup> )	No	TPE	
PVC	B	M12	2x0.22 mm <sup>2</sup> + 2x0.34 mm <sup>2</sup>	black	WS,BL (0.22mm <sup>2</sup> ), RT,SW (0.34mm <sup>2</sup> )	No	PVC	
<b>Note</b>	Additional technical data available upon request							

Outer cladding	Suitable for dragline cable carriers	Bending radius in cable Ø		Temperature range in °C		External Ø in mm	Halogen-free	UL
		Rigid	Moving	Rigid	Moving			
PVC	No	5x	10x	-30 / +80	-5 / +80	approx. 4.5	No	Yes
PVC	No	5x	10x	-30 / +80	-5 / +80	approx. 4.8	No	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 4.1	Yes	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 4.4	Yes	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 4.1	Yes	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 4.4	Yes	Yes
PUR	Yes	4x	7.5x	-40 / +105	-30 / +105	approx. 4.9	Yes	Yes
PUR	Yes	4x	7.5x	-40 / +105	-30 / +105	approx. 4.9	Yes	Yes
PUR	Yes	5x	12x	-40 / +90	-30 / +90	approx. 4.8	Yes	Yes
PUR	Yes	5x	12x	-40 / +90	-30 / +90	approx. 5.1	Yes	Yes
PVC	nein	5x	10x	-30 / +80	-5 / +80	approx. 4.9	No	Yes
PVC	nein	5x	10x	-30 / +80	-5 / +80	approx. 5.3	No	Yes
PVC	nein	5x	10x	-30 / +80	-5 / +80	approx. 5.7	No	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 4.3	Yes	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 4.7	Yes	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 5.0	Yes	Yes
PUR	Yes	5x	10x	-40 / +90	-30 / +90	approx. 5.9	Yes	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 4.3	Yes	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 4.7	Yes	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 5.0	Yes	Yes
PUR	Yes	4x	7.5x	-40 / +105	-30 / +105	approx. 4.9	Yes	Yes
PUR	Yes	4x	7.5x	-40 / +105	-30 / +105	approx. 4.9	Yes	Yes
PUR	Yes	4x	7.5x	-40 / +105	-30 / +105	approx. 5.1	Yes	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 5.0	Yes	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 5.4	Yes	Yes
PUR	Yes	5x	10x	-40 / +80	-25 / +80	approx. 5.7	Yes	Yes
PUR	Yes	5x	12x	-40 / +90	-30 / +90	approx. 6.3	Yes	Yes
PUR	Yes	5x	12x	-40 / +90	-30 / +90	approx. 5.1	Yes	Yes
PVC	No	3.5x	7.5x	-40 / +75	-20 / +60	approx. 6.5	No	Yes
PVC	No	3.5x	7.5x	-40 / +70	-20 / +60	approx. 6.5	No	Yes
PUR	Yes	5x	7.5x	-40 / +70	-20 / +60	approx. 6.5	Yes	Yes
PUR	Yes	4x	7.5x	-40 / +80	-/-	approx. 4.8	Yes	Yes
PUR	Yes	7.5x	15x	-40 / +70	-20 / +60	approx. 7.8	Yes	No
PVC	No	18x	9x	-20 / +70	-5 / +60	approx. 7.8	No	No
PVC	No	-/-	-/-	-30 / +80	-5 / +60	approx. 8.0	No	No
PVC	No	-/-	-/-	-30 / +80	-5 / +60	approx. 8.0	No	No
PUR	Yes	5x	10x	-40 / +80	-10 / +80	approx. 7.0	Yes	Yes
PVC	No	5x	10x	-40 / +80	-10 / +80	approx. 7.2	No	Yes


# Drilling templates

**SAI M12 and M12 Push-Pull:  
hood / M23 / M16 /  
fixed cable / IDC / A**




**SAI stainless steel**

Note: This page can be copied to use as a template.



**SAI wall bushing**

Note: This page can be copied to use as a template.


**SAI M8 standard**

W

Note: This page can be copied to  
use as a template.


**SAI M8 line**

Note: This page can be copied to use as a template.

**SAI M5**

W


Note: This page can be copied to  
use as a template.

**SAI Active Universal**


Note: This page can be copied to use as a template.

**SAI Active Universal Pro:**  
**Subbus modules with digital outputs**



Plan view



Side view



Note: This page can be copied to  
use as a template.

**SAI Active Universal Pro:  
Sub-bus modules without digital outputs****Plan view****Side view**

Note: This page can be copied to use as a template.

W

# Chemical resistance of nickel

The statements on the resistance of nickel to chemicals only apply when the coating is undamaged and is not subject to any mechanical loads. These statements are based on a review of the literature available and it should be noted that pure nickel is not considered in the literature – only alloyed nickel steels.

The statements on page W.15 are based on research, and once again please note that pure nickel has not been included in the testing. The findings in the research are based on undamaged alloyed nickel steels that have not been subject to any mechanical loads.

The six materials in question are:

Chlorobenzene	1
Chloroform	1
Chromic acid hydride	1
Acetic acid	1
Hydrofluoric acid	2
Concentrated hydrochloric acid	2

The findings for the two materials above marked with a "2" could have a critical impact on applications. The findings for the four materials marked with a "1" should be taken into account but would not be considered critical for applications.

A further advantage of nickel is its thermal stability. The resistance does not change up to a temperature of 120 °C.

Pure nickel:

Corrosion properties are determined by the resistance of the passive layer.

Good resistance in:

- water containing oxygen
- flowing seawater
- alkalis (very good resistance) even at high temperatures and high concentrations
- neutral and alkaline salt solutions (carbonates, phosphates, sulphates, chlorides and nitrates) even at high concentrations and temperatures

Known problems:

- corrosion attack in heavily oxidising acids and solutions containing chlorides
- in inorganic and organic acids only resistant in diluted solutions and at low temperatures
- coating is not toxic (formation of deposits by micro-organisms can lead to destruction of the passive coating)

# Chemical resistance of Pocan® (PBT)

Pocan® offers good resistance to chemicals. Organic solvents, such as aliphatic hydrocarbons, alcohols, ether, long-chain ester as well as fats, oils and perchlorinated hydrocarbons do not corrode Pocan®.

This is also true for water and aqueous solutions, neutral and acid salts, as well as diluted acids.

On the other hand, it is susceptible to alkalis, oxidising acids, ketones and phenols.

Susceptibility to universal alcohols, aromatics and ketones increases as the ambient temperature rises above 60 °C.

In the presence of water and aqueous solutions, hydrolytic degradation at higher temperatures increasingly leads to a decline in stability.

Substances like motor and transformer oils, petrol and brake fluids do not corrode Pocan®, even at higher temperatures.

Medium	23 °C	60 °C	Medium	23 °C	60 °C
Acetic acid 10%	±	±	Linseed oil	+	+
Acetone	+	-	Lubricating greases	+	+
Ammonia 10%	+	-	Methanol	+	±
Ammonia, concentrated	±	-	Methyl ethyl ketone	+	±
Benzene	+	-	Methylene chloride	-	-
Brake fluid	+	+	Mineral oils	+	+
Butane	+	+	Motor oils	+	+
Butanol	+	±	Nitric acid 10%	+	±
Butyl acetate	+	+	Nitric acid, concentrated	-	-
Calcium chloride 10%	+	+	Octane	+	+
Carbon disulphide	+	±	Olive oil	+	+
Carbon tetrachloride	+	±	Paraffin oil	+	+
Chlorobenzene	-	-	Perchloroethylene	±	-
Chloroform	-	-	Petrol, normal and lead-free	+	+
Chromic acid hydrate 10%	+	+	Petrol, super	+	+
Citric acid 10%	+	±	Petrol/methanol 85/15	+	+
Cresol	-	-	Petroleum	+	+
Curd soap	+	+	Phenol 10%	-	-
Dibutyl phthalate	+	±	Phosphoric acid 20%	+	±
Diesel oil	+	+	Potassium chloride 10%	+	+
Diethyl ether	+	±	Potassium dichromate 10%	+	+
Dioxan	+	-	Potassium hydroxide 10%	-	-
Ethanol	+	+	Potassium permanganate 10%	+	±
Ethyl acetate	±	-	Soap suds 10%	+	±
Ethyl dichloride	-	-	Sodium bisulphite 10%	+	+
Ethylene glycol	+	±	Sodium carbonate 10%	+	+
Formic acid 10%	+	±	Sodium chloride 10%	+	+
Freon 11	+	+	Sodium hydroxide 10%	-	-
Frigen 113	+	+	Sulphuric acid 10%	+	±
Glacial acetic acid 10%	-	-	Sulphuric acid, concentrated	-	-
Glycerine	+	+	Tetrahydrofuran	-	-
Heptane	+	+	Toluene	±	-
Hexane	+	+	Transformer oil	+	+
Hydraulic oil	+	+	Trichlorethane/chloroform 1/1	±	-
Hydrochloric acid 10%	+	-	Turpentine oil	+	+
Hydrochloric acid, concentrated	-	-	Vegetable oils	+	+
Hydrofluoric acid 10%	+	+	Washing liquid	+	+
Hydrogen peroxide 20%	+	±	Washing powder, synthetic	+	+
Isopropyl alcohol	+	±	Water	+	+
Kerosene	+	+	Xylool	±	-

The above values are for guidance only. A definite statement can only be made when based on the respective case in question.

+ = resistant  
- = not resistant  
± = partly resistant

W

# Index

## Index

Index Type	X.2
Index Order No.	X.8
Addresses worldwide	X.16

Type	Order No.	Page	Type	Order No.	Page	Type	Order No.	Page	Type	Order No.	Page
<b>1-9</b>			FBCon PA CG 1way Ex	8564180000	C.52	IE-C5DD4UG0050MCSMCA-E	1059770050	C.71	SAI GHDE EA 8M12 SIBL	1246510000	G.6
1/4" Handgriff	4294820000	K.5	FBCon PA CG 1way Limiter	8714200000	C.45	IE-C5DD4UG0050MCSMCS-E	1025950050	C.69	SAI JP 4P LG	1915220000	H.8
<b>A</b>			FBCon PA CG 1way OVP	8714120000	C.41	IE-C5DD4UG0050MCSXXX-X	1025940050	C.70	SAI JP 4P LG 100	8794090000	H.8
AIE multi-stripax 6-16	9202260000	K.11	FBCon PA CG 2way	8564100000	C.37	IE-C5DD4UG0100MCMACMA-E	1059890100	C.71	SAI JP 5P LG	1918520000	H.8
AIE multi-stripax ASI	9202300000	K.11	FBCon PA CG 2way Ex	8564190000	C.53	IE-C5DD4UG0100MCAXXX-X	1059750100	C.72	SAI JP 5P LG 100	8794080000	H.8
AIE multi-stripax GKWLW	9205770000	K.11	FBCon PA CG 2way Limiter	8714210000	C.46	IE-C5DD4UG0100MCSA20-E	1044470100	C.70	SAI M23 CRIMPING TOOL 1	1203840000	K.12
AM 12	9030060000	C.69	FBCon PA CG 2way OVP	8714130000	C.42	IE-C5DD4UG0100MCSMCA-E	1059770100	C.71	SAI M23 CRIMPING TOOL 2	1203960000	K.13
AM 12	9030060000	C.70	FBCon PA CG 4way	8564110000	C.38	IE-C5DD4UG0100MCSMCS-E	1025950100	C.69	SAI O-Ri 5.0x0.8 NBR	4312340000	G.10
AM 12	9030060000	C.73	FBCon PA CG 4way Ex	8564200000	C.54	IE-C5DD4UG0100MCSXXX-X	1025940100	C.70	SAI O-Ri 5.0x0.8 NBR	4312340000	G.13
AM 12	9030060000	C.74	FBCon PA CG 4way Limiter	8714220000	C.47	IE-CST	9204350000	C.69	SAI O-Ri 5.0x0.8 NBR	4312340000	G.6
AM 12	9030060000	C.8	FBCon PA CG 4way OVP	8714140000	C.43	IE-CST	9204350000	C.70	SAI O-Ri 7.5x1.5 VI	4311000000	G.10
AS-KG-GE	9455110000	C.60	FBCon PA CG 8way	8564240000	C.55	IE-CST	9204350000	C.74	SAI O-Ri 7.5x1.5 VI	4311000000	G.13
AS-KG-SW	9455120000	C.60	FBCon PA CG 8way Ex	8564123000	C.48	IEPCB-M12X-S-180	1324010000	C.79	SAI O-Ri 7.5x1.5 VI	4311000000	G.6
<b>B</b>			FBCon PA CG 8way Limiter	8714230000	C.48	IEPCB-M12X-S-180	1393080000	C.79	SAI O-Ri 7.5x1.5 VI	4311000000	G.9
B KOTR B M12 4POL D BU	2350590000	G.13	FBCon PA CG/M12 1way	8564060000	C.36	IE-PS-M12X-P-FH	1324020000	C.79	SAI RA 30 SB KU	1246660000	G.9
B KOTR B M12 4POL D BU	2350590000	G.7	FBCon PA CG/M12 1way Ex	8564150000	C.52	SAI RA 30 SB LA	1246720000	G.10			
B KOTR B M12 4POL D BU	2350600000	G.13	FBCon PA CG/M12 1way Limiter	8714160000	C.45	SAI RA 54 KU	1246530000	G.6			
B KOTR B M12 5POL A BU	2350600000	G.7	FBCon PA CG/M12 1way OVP	8714150000	C.44	SAI Y-4S M8-M8	1805660000	D.28			
B KOTR B M12 5POL A SF	2350600000	G.13	FBCon PA CG/M12 2way	8564070000	C.37	SAI-10-F 3P M8 L 10M	1828650000	I.54			
B KOTR B M12 5POL A SF	2350610000	G.10	FBCon PA CG/M12 2way Ex	8564160000	C.53	SAI-10-F 3P M8 L 5M	1828660000	I.54			
B KOTR B M12 5POL A SF	2350610000	G.13	FBCon PA CG/M12 2way Limiter	8714170000	C.46	SAI-10-S 12F P8 M8 L	1877950000	I.52			
B KOTR B M12 5POL A SF	2350620000	G.7	FBCon PA CG/M12 2way OVP	8714090000	C.42	SAI-12-F 3P M8 L 10M	1828630000	I.54			
B KOTR B M12 5POL B BU	2350620000	G.13	FBCon PA CG/M12 4way	8564080000	C.38	SAI-12-F 3P M8 L 5M	1828640000	I.54			
B KOTR B M12 5POL B BU	2350620000	G.7	FBCon PA CG/M12 4way Ex	8564170000	C.54	SAI-4 M 4P M12 UT	1705921000	I.7			
B KOTR B M12 5POL B SF	2350630000	G.13	FBCon PA CG/M12 4way Limiter	8714180000	C.47	SAI-4 F 3P IDC PUR 10M	1766730000	I.29			
B KOTR B M12 5POL B SF	2350630000	G.7	FBCon PA CG/M12 4way OVP	8714100000	C.43	SAI-4 F 3P IDC PUR 5M	1766720000	I.29			
B KOTR BUS M8 4POL BU	2350640000	G.10	FBCon PA CG/M12 8way	8564310000	C.39	SAI-4 F 3P M5 L10M	1848520000	I.58			
B KOTR BUS M8 4POL BU	2350640000	G.13	FBCon PA CG/M12 8way Ex	8564250000	C.55	SAI-4 F 3P M5 L5M	1851740000	I.58			
B KOTR BUS M8 4POL SF	2350650000	G.10	FBCon PA CG/M12 8way Limiter	8714190000	C.48	SAI-4 F 3P M8 L 10M	1828710000	I.54			
B KOTR BUS M8 4POL SF	2350650000	G.9	FBCon PA CG/M12 8way OVP	8714110000	C.44	SAI-4 F 3P M8 L 5M	1828720000	I.54			
B KOTR M12 4P D BU SAI	2341480000	G.10	FBCon SS CG 1way	8703430000	C.36	SAI-4 F 3P M8 PUR 10M	1784630000	I.50			
B KOTR M12 4P D BU SAI	2341480000	G.13	FBCon SS CG 4way	8703450000	C.38	SAI-4 F 3P M8 PUR 5M	1784640000	I.50			
B KOTR M12 4P D BU SAI	2341480000	G.6	FBCon SS CG 8way	8703470000	C.39	SAI-4 F 4P FC 10M	1848050000	I.19			
B KOTR M12 4P D BU SAI	2341480000	G.9	FBCon SS CG/M12 1way	8726020000	C.36	SAI-4 F 4P FC 2M	1848080000	I.19			
B KOTR M12 4P D BU SAI	2341480000	G.10	FBCon SS CG/M12 4way	8726040000	C.38	SAI-4 F 4P IDC PUR 10M	1766670000	I.29			
B KOTR M12 4P D BU SAI	2341480000	G.9	FBCon SS CG/M12 8way	8726050000	C.39	SAI-4 F 4P IDC PUR 5M	1766660000	I.29			
B KOTR M12 4P D BU SAI	2341480000	G.11	FBCon SS DP M12 1way	8714270000	C.23	SAI-4 F 4P M12 L 10M	1070660000	I.9			
B KOTR M12 4P D BU SAI	2341480000	G.13	FBCon SS DP M12 Term 24V	8714250000	C.24	SAI-4 F 4P M12 L 5M	1845800000	I.58			
B KOTR M12 4P D BU SAI	2341480000	G.6	FBCon SS DP PCG 1way	8714260000	C.23	SAI-4 F 4P M5 L5M	1851770000	I.58			
B KOTR M12 4P D BU SAI	2341480000	G.9	FBCon SS DP PCG Term 24V	8714240000	C.24	SAI-4 F 4P M8 L 10M	1849690000	I.54			
B KOTR M12 5P A BU SAI	2326170000	G.9	FBCon SS PCG 1way Limiter	8726110000	C.45	SAI-4 F 4P M8 L 5M	1849680000	I.54			
B KOTR M8 3P BU SAI	2323280000	G.13	FBCon SS PCG 4way	8611368000	C.38	SAI-4 F 4P M8 PUR 10M	1784590000	I.50			
B KOTR M8 3P BU SAI	2323280000	G.7	FBCon SS PCG 4way Limiter	8715126000	C.47	SAI-4 F 4P M8 PUR 5M	1784600000	I.50			
B KOTR M8 3P BU SAI	2323280000	G.13	FBCon SS PCG 8way	8640720000	C.39	SAI-4 F 4P PUR 10M	1848060000	I.19			
B KOTR M8 3P BU SAI	2323280000	G.7	FBCon SS PCG 8way Limiter	8726160000	C.48	SAI-4 F 4P PUR 10M	1845800000	I.58			
B KOTR M8 9/20 MC NEUTRAL WS	1606530000	I.43	FBCon SS PCG 8way OVP	8726090000	C.44	SAI-4 F 4P PUR 15M	1845620000	I.6			
<b>D</b>			FBCon Term.D Ex	8606190000	C.56	PA SUB-D IDC TERM PS	1919680000	C.15	PA SUB-D ZF TERM PS	1934200000	C.15
DAE M12 PA short	1868560000	C.81	FBCon Term.D Ex FM	8556460000	C.56	PA-D SUB-D	8395500000	C.14	PA-D SUB-D M12 TERM	1140650000	C.15
DEK 5/5 MC BEDRUCKT	1609810000	K.16	FBCon Term.D Ex FM/PEAN	8606180000	C.56	PA-D SUB-D M12 TERM PS	1140640000	C.17	PA-D SUB-D M12 TERM PS	1140640000	C.17
DEK 5/5 MC-10 NEUT. WS	1609801044	K.16	FBCon Term.D Ex PEAN	8606200000	C.56	PA-D SUB-D ZF TERM	8460860000	C.15	PA-D SUB-D ZF TERM	8460860000	C.15
<b>E</b>			FBCon Term.D Ex	8606190000	C.56	PA-D SUB-D ZF TERM PS	1161870000	C.21	PA-D SUB-D ZF TERM PS	1161880000	C.21
ERAN MULTI-STRIPAX	9203100000	K.11	FBCon Term.D Ex	8606190000	C.56	PA-D SUB-D ZF35TERM	1173220000	C.18	PA-D SUB-D ZF35TERM	1173240000	C.19
ERME 10 <sup>2</sup> SPX 4	1119030000	K.9	FBCon Term.D Ex	8606190000	C.56	PJ PRO TINTSET FARBE	1027110000	K.15	PJ PRO TNAW	1024140000	K.15
ERME MULTI-STRIPAX	9203070000	K.11	FBCon Term.D Ex	8606190000	C.56	PJ PRO TNWK INK C	1027050000	K.15	PJ PRO TNWK INK C	1027060000	K.15
ESG 8/13.5/43.3 SAI AU	1912130000	F.10	FBCon Term.D Ex	8606190000	C.56	PJ PRO TNWK INK K	1027070000	K.15	PJ PRO TNWK INK Y	1027070000	K.15
ESG 8/13.5/43.3 SAI AU	1912130000	F.14	FBCon Term.D Ex	8606190000	C.56	PJ PRO TNWK INK Y	1027070000	K.15	PO-4P M12 M20 150mm	8425930000	C.33
ESG 8/13.5/43.3 SAI AU	1912130000	F.18	FBCon Term.D Ex	8606190000	C.56	PO-4P M12 M20 300mm	8425940000	C.33	PO-4P M12 PG13.5 150mm	9456650000	C.33
ESG 8/13.5/43.3 SAI AU	1912130000	F.23	FBCon Term.D Ex	8606190000	C.56	PO-4P M12 PG13.5 300 mm	8425910000	C.33	PO-5P M12 M20 300 mm	1795500000	C.33
ESG 8/13.5/43.3 SAI AU	1912130000	F.25	FBCon Term.D Ex	8606190000	C.56	PRINTJET PRO 115V	1024050000	C.15	SAI-4 F 4P FC 10M	1847930000	I.19
ESG 8/13.5/43.3 SAI AU	1912130000	F.27	FBCon Term.D Ex	8606190000	C.56	PTSC 25X12 WN5452	4311430000	G.10	SAI-4 F 4P FC 2M	1847940000	I.19
ESG 8/13.5/43.3 SAI AU	1912130000	F.37	FBCon Term.D Ex	8606190000	C.56	PTSC 25X12 WN5452	4311430000	G.9	SAI-4 F 4P FC 5M	1847950000	I.19
ESG 8/13.5/43.3 SAI AU	1912130000	K.16	FBCon Term.D Ex	8606190000	C.56	PTSC 25X12 WN5452	4311430000	G.9	SAI-4 F 4P FC 5M	1847950000	I.19
ESG 9/20 MC NEUTRAL WS	1609940000	K.16	FBCon Term.D Ex	8606190000	C.56	PJ PRO TNWK INK K	1027050000	K.15	SAI-4 F 4P CNOMO 5M	1861570000	I.23
<b>F</b>			FBC PA M12 F1M	1785110100	C.28	PJ PRO TNWK INK Y	1027070000	K.15	SAI-4 F 4P FC 10M	1847930000	I.19
FBC PA M12 F1M	1785110100	C.28	FBC PA M12 FMA 1M	1076530100	C.28	PO-4P M12 M20 150mm	8425930000	C.33	SAI-4 F 4P FC 2M	1847940000	I.19
FBC PA M12 M 1M	1785120100	C.28	FBC PA M12 M-FMA 1M	1076501000	C.29	PO-4P M12 M20 300mm	8425940000	C.33	PO-4P M12 PG13.5 150mm	9456650000	C.33
FBC PA M12 M-FMA 1M	1785120100	C.29	FBC PA M12 MA 1M	1076520100	C.29	PO-4P M12 PG13.5 300 mm	8425910000	C.33	PO-5P M12 M20 300 mm	1795500000	C.33
FBC PA M12 MA 1M	1076540100	C.28	FBC PA M12 MA-FMA 1M	1075460100	C.29	PRINTJET PRO 115V	1024050000	C.15	SAI-4 F 4P PUR 10M	1846340000	I.8
FBC PA M12 MA-FMA 1M	1075460100	C.29	FBC PA M12 MA 1M	1076510000	C.29	PTSC 25X12 WN5452	4311430000	G.10	SAI-4 F 4P PUR 5M	1846330000	I.8
FBC PA M12 M-FMA 1M	1076520100	C.29	FBC PA M12 M-FMA 1M	1075460100	C.29	PTSC 25X12 WN5452	4311430000	G.9	SAI-4 F 4P PUR 10M	1846340000	I.8
FBC PA M12 M-FMA 1M	1076520100	C.29	FBC PA M12 M-FMA 1M	1075460100	C.29	PTSC 25X12 WN5452	4311430000	G.9	SAI-4 F 4P PUR 5M	1846330000	I.8
FBC PA M12 M-FMA 1M	1076520100	C.29	FBC PA M12 M-FMA 1M	1075460100	C.29	PJ PRO TNWK INK K	1027050000	K.15	SAI-4 F 4P PUR 10M	1846320000	I.8
FBC PA M12 M-FMA 1M	1076520100	C.29	FBC PA M12 M-FMA 1M	1075460100	C.29	PJ PRO TNWK INK Y	1027070000	K.15	SAI-4 F 4P PUR 5M	1846330000	I.8
FBC PA M12 M-FMA 1M	1076520100	C.29	FBC PA M12 M-FMA 1M	1075460100	C.29	PO-4P M12 M20 150mm	8425930000	C.33	SAI-4 F 4P PUR 10M	1846320000	I.8
FBC PA M12 M-FMA 1M	1076520100	C.29	FBC PA M12 M-FMA 1M	1075460100	C.29	PO-4P M12 M20 300mm	8425940000	C.33	SAI-4 F 4P PUR 5M	1846330000	I.8
FBC PA M12 M-FMA 1M	1076520100	C.29	FBC PA M12 M-FMA 1M	1075460100	C.29	PO-4P M12 PG13.5 150mm	9456650000	C.33	SAI-4 F 4P PUR 10M	1846320000	I.8
FBC PA M12 M-FMA 1M	1076520100</										

Type	Order No.	Page	Type	Order No.	Page	Type	Order No.	Page	Type	Order No.	Page
SAI-4-M23 4P M8	1784660000	J.33	SAI-6-MHD-5P M12	1701243000	I.37	SAI-8-MHD-4P M12	1705943000	I.37	SAI-AU M12 SB 8DIO	1938640000	F.27
SAI-4-MF 5P PUR 10M	1804580000	I.44	SAI-6-S 3P M8 L	1828730000	I.52	SAI-8-MHD-5P M12	1701253000	I.37	SAI-AU M12 SB 8DIO	1938640000	F.28
SAI-4-MF 5P PUR 5M	1804600000	I.44	SAI-6-S 3P M8 L_OL	1932380000	I.52	SAI-8-MM 5P M12	1783490000	I.35	SAI-AU M12 SB 8DIO	1938640000	F.4
SAI-4-MH-AP M12	1705922000	I.36	SAI-6-S 3P M8 L_SL	1057720000	I.53	SAI-8-MM 5P M12 UT	1783491000	I.35	SAI-AU M12 SB 8D0 2A	1938680000	F.23
SAI-4-MH-5P M12	1701232000	I.36	SAI-6-S 4P M12	9456010000	I.12	SAI-8-MMH 5P M12 ZF	1782740000	I.35	SAI-AU M12 SB 8D0 2A	1938680000	F.25
SAI-4-MHD-4P M12	1705923000	I.37	SAI-6-S 4P M12	9456010000	I.6	SAI-8-MMS 4P M12	1783530000	I.35	SAI-AU M12 SB 8D0 2A	1938680000	F.27
SAI-4-MHD-5P M12	1701233000	I.37	SAI-6-S 5P M12	9456010001	I.12	SAI-8-MMS 5P M12	1783510000	I.35	SAI-AU M12 SB 8D0 2A	1938680000	F.28
SAI-4-MM 5P M12	1783500000	I.35	SAI-6-S 5P M12	9456010001	I.6	SAI-8-S 3P M5	1848550000	I.58	SAI-AU M12 USB GW 8180	1962240000	F.26
SAI-4-MMS 4P M12	1783540000	I.35	SAI-6-S 12P M12_L	1265940000	I.11	SAI-8-S 4P FC	1847920000	I.20	SAI-AU M12 USB GW 8180	1962240000	F.27
SAI-4-MMS 5P M12	1783520000	I.35	SAI-8-S 4P M12 F10	1812170000	I.43	SAI-8-S 4P FC	1847920000	J.31	SAI-AU M12 USB GW 8180	1962240000	F.4
SAI-4-MMS 5P M12 1:1	1897680000	I.38	SAI-8-S 5P M12 SL	1847560000	I.41	SAI-8-S 4P M12	9456020000	I.12	SAI-AU M8 CAN 16DI	1906680000	F.12
SAI-4-S 3P M8 L	1828740000	I.52	SAI-8-F 3P IDC PUR 10M	1766770000	I.29	SAI-8-S 4P M12	9456020000	I.6	SAI-AU M8 CAN 16DI	1906680000	F.14
SAI-4-S 3P M8 L_OL	1051670000	I.52	SAI-8-F 3P IDC PUR 5M	1766676000	I.29	SAI-8-S 5P CNOMO	1861580000	I.23	SAI-AU M8 CAN 16DI	1906680000	F.4
SAI-4-S 4P FC	1847960000	I.20	SAI-8-F 3P M5 L10M	1845830000	I.58	SAI-8-S 5P FC	1848040000	I.20	SAI-AU M8 CAN 16DI/8DO	1906690000	F.12
SAI-4-S 4P FC	1847960000	J.31	SAI-8-F 3P M5 L5M	1851760000	I.58	SAI-8-S 5P FC	1848040000	J.31	SAI-AU M8 CAN 16DI/8DO	1906690000	F.14
SAI-4-S 4P M12	9456000000	I.12	SAI-8-F 3P M8 L 10M	1828670000	I.54	SAI-8-S 5P M12	1795470000	I.12	SAI-AU M8 CAN 16DI/8DO	1906690000	F.4
SAI-4-S 4P M12	9456000000	I.6	SAI-8-F 3P M8 L 5M	1828680000	I.54	SAI-8-S 12P M8 L	1871680000	I.52	SAI-AU M8 DN 16DI	1906730000	F.16
SAI-4-S 4P M5	1845840000	I.58	SAI-8-F 3P M8 PUR 10M	1784610000	I.50	SAI-8-S 16P M3	1845880000	I.59	SAI-AU M8 DN 16DI	1906730000	F.18
SAI-4-S 5P CNOMO	1861540000	I.23	SAI-8-F 3P M8 PUR 5M	1784620000	I.50	SAI-8-S 16P 4P M5	1845860000	I.59	SAI-AU M8 DN 16DI	1906730000	F.4
SAI-4-S 5P FC	1847970000	I.20	SAI-8-F 4P FC 10M	1847980000	I.19	SAI-8-S 4P FC	1859120000	I.21	SAI-AU M8 DN 16DI/8DO	1906740000	F.16
SAI-4-S 5P FC	1847970000	J.31	SAI-8-F 4P FC 2M	1847990000	I.19	SAI-8-S 4P FC	1859120000	J.32	SAI-AU M8 DN 16DI/8DO	1906740000	F.18
SAI-4-S 5P M12	9456000001	I.12	SAI-8-F 4P FC 5M	1848000000	I.19	SAI-8-S 5P FC	1859140000	I.21	SAI-AU M8 DN 16DI/8DO	1906740000	F.4
SAI-4-S 5P M12	9456000001	I.6	SAI-8-F 4P IDC PUR 10M	1766710000	I.29	SAI-8-S 5P FC	1859140000	J.32	SAI-AU M8 PB 16DI	1906550000	F.10
SAI-4-S 16P M3	1845890000	I.59	SAI-8-F 4P IDC PUR 5M	1766700000	I.29	SAI-8-SH 5P F13 FC	1872460000	I.25	SAI-AU M8 PB 16DI	1906550000	F.4
SAI-4-S 16P M5	1845870000	I.59	SAI-8-F 4P M5 L10M	1845810000	I.58	SAI-8-SH 5P FC	1872440000	I.24	SAI-AU M8 PB 16DI	1906550000	F.8
SAI-4-S 8P 4P M12 L	1267330000	I.11	SAI-8-F 4P M5 L5M	1851750000	I.58	SAI-ASI T FF small	1026090000	C.61	SAI-AU M8 PB 16DI/8DO	1906640000	F.10
SAI-4-S 8P 4P FC	1859110000	I.21	SAI-8-F 4P M5 L10M	1828610000	I.54	SAI-ASI T FRR	1924980000	C.61	SAI-AU M8 PB 16DI/8DO	1906640000	F.4
SAI-4-SH 4P FC	1859110000	J.32	SAI-8-F 4P M8 L 5M	1828620000	I.54	SAI-ASI T FRR	1925010000	C.60	SAI-AU M8 PB 16D0/8DO	1906640000	F.8
SAI-4-SH 4P FC	1859130000	I.21	SAI-8-F 4P M8 PUR 10M	1784570000	I.50	SAI-ASH-LM12-41 V3	1962680000	C.59	SAI-AU M8 PB 8D18D0 2A	1975450000	F.10
SAI-4-SH 5P FC	1859130000	J.32	SAI-8-F 4P M8 PUR 5M	1784580000	I.50	SAI-ASH-LM12-41/40 V3	1962710000	C.59	SAI-AU M8 PB 8D18D0 2A	1975450000	F.4
SAI-4/6/8 MH BLZ F3.5	1782750000	I.36	SAI-8-F 4P PUR 10M	9456760000	I.6	SAI-ASH-LM12-40 V3	1962700000	C.59	SAI-AU M8 PB 8D18D0 2A	1975450000	F.8
SAI-4/6/8 MH MH BL 3.5	1724752000	I.36	SAI-8-F 4P PUR 10M	9456760000	I.8	SAI-ASH-LM12-81 V3	1962690000	C.59	SAI-AU M8 PB 8W 16D1	1024310000	F.22
SAI-4/6/8 MH MH BL 3.5	1724753000	I.37	SAI-8-F 4P PUR 15M	9456770000	I.6	SAI-ASH-LM12-81 V3	1962640000	C.59	SAI-AU M8 SB 8D0	1938600000	F.23
SAI-4/6/8 MH-MH BL 3.5	1724754000	I.35	SAI-8-F 4P PUR 15M	9456770000	I.8	SAI-ASH-LM8-4V/40 V3	1962670000	C.59	SAI-AU M8 SB 8D0	1938600000	F.25
SAI-4/6/8 MH-BL 3.5	1724750000	I.7	SAI-8-F 4P PUR 20M	9456790000	I.6	SAI-ASH-LM8-40 V3	1962660000	C.59	SAI-AU M8 SB 8D0	1938600000	F.27
SAI-4/6/8 MH-BL 3.5 SV	1724750050	I.7	SAI-8-F 4P PUR 20M	9456790000	I.8	SAI-ASH-LM8-8V/3	1962650000	C.59	SAI-AU M8 SB 8D0	1938600000	F.28
SAI-4/6/8 MH-BLZ F3.5	1752080000	I.7	SAI-8-F 4P PUR 3M	9456740000	I.8	SAI-AU ET SET M12 A COD	1235340000	G.7	SAI-AU M8 SB 8D0	1938600000	F.4
SAI-4/6/8 MH-BLZ F3.5 SV	1752080050	I.7	SAI-8-F 4P PUR 5M	9456750000	I.6	SAI-AU M12 CAN 16DI	1906650000	F.12	SAI-AU M8 SB 8D0	1938630000	F.23
SAI-4/6/8 MH-BLZ F3.5	1783460000	I.7	SAI-8-F 4P PUR 5M	9456750000	I.8	SAI-AU M12 CAN 16DI	1906650000	F.14	SAI-AU M8 SB 8D0	1938630000	F.25
SAI-4/6/8 MHF 4P PUR 4M	1791454000	I.44	SAI-8-F 5P 10M 0.5/1.0U	9457600000	I.8	SAI-AU M12 CAN 16DI	1906650000	F.14	SAI-AU M8 SB 8D0	1938630000	F.27
SAI-4/6/8 MHF 4P PUR 6M	1791450600	I.44	SAI-8-F 5P 15M 0.5/1.0U	1784510000	I.8	SAI-AU M12 CAN 16DI/8DO	1906660000	F.12	SAI-AU M8 SB 8D0	1938630000	F.28
SAI-4/6/8 MHF 4P PUR 9M	1791450900	I.44	SAI-8-F 5P 20M 0.5/1.0U	1784500000	I.8	SAI-AU M12 CAN 16DI/8DO	1906660000	F.12	SAI-AU M8 SB 8D0	1938630000	F.4
SAI-4/6/8 MHF 4P PUR14M	1791451400	I.44	SAI-8-F 5P 2M 0.5/1.0U	7915030000	I.8	SAI-AU M12 CAN 16D0/8DO	1906670000	F.12	SAI-AU M8 SB 8D0	1938660000	F.23
SAI-4/6/8 MHF 4P PUR20M	1791452000	I.44	SAI-8-F 5P 5M 0.5/1.0U	9457590000	I.8	SAI-AU M12 CAN AI/AI/DO	1906670000	F.13	SAI-AU M8 SB 8D0	1938660000	F.25
SAI-4/6/8 MHF 5P PUR16M	1791452800	I.44	SAI-8-F 5P CNOMO 10M	1861590000	I.23	SAI-AU M12 CAN AI/AI/DO	1906670000	F.14	SAI-AU M8 SB 8D0	1938660000	F.27
SAI-4/6/8 MHF 5P PUR20M	1791462000	I.44	SAI-8-F 5P CNOMO 5M	1861550000	I.23	SAI-AU M12 CAN AI/AI/DO	1906670000	F.14	SAI-AU M8 SB 8D0	1938660000	F.28
SAI-4/6/8 MHF 5P PUR28M	1791462800	I.44	SAI-8-F 5P M10	1848010000	I.19	SAI-AU M12 DN 16DI	1906700000	F.16	SAI-AU M8 SB 8D0	1938660000	F.4
SAI-4/6/8 MHF 5P PUR34M	1791463400	I.44	SAI-8-F 5P M2	1848020000	I.19	SAI-AU M12 DN 16DI	1906700000	F.16	SAI-DCD-T007	1795200000	I.27
SAI-4/6/8 MHF 5P PUR4M	1791464000	I.44	SAI-8-F 5P M5	1848030000	I.19	SAI-AU M12 DN 16DI	1906700000	F.16	SAI-M23-BE-12	1995850000	J.14
SAI-4/6/8 MHF 5P PUR9M	1791464090	I.44	SAI-8-F 5P M12 5M VA	1865310000	I.30	SAI-AU M12 DN 16D/8DO	1906710000	F.16	SAI-M23-BE-12-10MM	1224170000	J.21
SAI-4/6/8 MHF 5P PUR14M	17914641400	I.44	SAI-8-F 5P PNP-PNP 5M	1814990000	I.40	SAI-AU M12 DN 16D/8DO	1906710000	F.16	SAI-M23-BE-12-10MM-G	1224590000	J.21
SAI-4/6/8 MHF 5P PUR55M	1791465500	I.44	SAI-8-F 5P PUR 10M	9456900000	I.6	SAI-AU M12 DN 16D/8DO	1906710000	F.16	SAI-M23-BE-12-10MM-P-E	1224610000	J.21
SAI-6-F 3P IDC PUR 10M	1766750000	I.29	SAI-8-F 5P PUR 10M	9456900000	I.8	SAI-AU M12 DN AI/AI/DO	1906720000	F.17	SAI-M23-BE-12-17MM	1224210000	J.21
SAI-6-F 3P IDC PUR 5M	1766740000	I.29	SAI-8-F 5P PUR 5M	9456890000	I.6	SAI-AU M12 DN AI/AI/DO	1906720000	F.17	SAI-M23-BE-23-3.5MM-PE	1224190000	J.21
SAI-6-F 3P M8 L 10M	1828690000	I.54	SAI-8-F 5P PUR 5M	9456890000	I.8	SAI-AU M12 DN AI/AI/DO	1906720000	F.18	SAI-M23-BE-23-6.5MM	1224200000	J.22
SAI-6-F 3P M8 L 5M	1828700000	I.54	SAI-8-F 5P PUR 15M	9456910000	I.6	SAI-AU M12 DN AI/AI/DO	1906720000	F.18	SAI-M23-BE-23-6-F	1224200000	J.22
SAI-6-F 4P PUR 10M	1849670000	I.54	SAI-8-F 5P PUR 15M	9456910000	I.8	SAI-AU M12 DN AI/AI/DO	1906720000	F.18	SAI-M23-BE-23-6-F	1224200000	J.22
SAI-6-F 4P PUR 20M	1849670000	I.54	SAI-8-F 5P PUR 20M	9456930000	I.6	SAI-AU M12 DN AI/AI/DO	1906720000	F.18	SAI-M23-BE-16	1170110000	J.15
SAI-6-F 4P PUR 5M	1849680000	I.6	SAI-8-F 5P PUR 20M	9456930000	I.8	SAI-AU M12 DN GW 16D1	1938570000	F.24	SAI-M23-BE-16	1224200000	J.15
SAI-6-F 4P PUR 15M	1849680000	I.6	SAI-8-F 5P PUR 3M	9456880000	I.8	SAI-AU M12 DN GW 16D1	1938570000	F.24	SAI-M23-BE-16-17MM	1224280000	J.22
SAI-6-F 4P PUR 15M	1849680000	I.8	SAI-8-F 5P PUR 5M	9456890000	I.6	SAI-AU M12 DN GW 16D1	1938550000	F.22	SAI-M23-BE-16-17MM	1224280000	J.22
SAI-6-F 4P PUR 20M	1849651000	I.6	SAI-8-F 5P PUR 5M	9456910000	I.6	SAI-AU M12 DN GW 16D1	1938550000	F.22	SAI-M23-BE-16-17MM	1224280000	J.22
SAI-6-F 4P PUR 100M	1849651000	I.6	SAI-8-F 5P PUR 10M	1781060000	I.7	SAI-AU M12 DN GW 16D1	1938550000	F.22	SAI-M23-BE-16-17MM	1224280000	J.22
SAI-6-F 4P PUR 10M	1849662000	I.6	SAI-8-F 5P M12 NPN ECO	1892080005	I.17	SAI-AU M12 DN GW 16D1	1938550000	F.22	SAI-M23-BE-16-17MM	1224280000	J.22
SAI-6-F 4P PUR 10M	1849662000	I.8	SAI-8								

Type	Order No.	Page	Type	Order No.	Page	Type	Order No.	Page	Type	Order No.	Page
SAI-M23-KBC-0.75/2.50	1995820000	J.29	SAI-SK-M12 BU	8425960000	D.31	SAI-BM-M8-4P(TL)	1921020000	D.21	SAI-E-M8R-4-0.5U-FPM8	1861290000	D.35
SAI-M23-KBC-0.75/2.50	1995820000	K.12	SAI-SK-M12 IDC	1794850000	D.31	SAI-BM-M8-4P(TL)	1921020000	D.6	SAI-E-M8S-3-0.5U-FPM8	1078730000	D.36
SAI-M23-KBC-1.00-1.5	1170210000	J.16	SAI-SK-M12 IDC	1794850000	I.27	SAI-BW-12/9(TL)	1925870000	D.11	SAI-E-M8S-4-0.5U-FPM8	1078720000	D.36
SAI-M23-KBC-1.5-14..56	1170230000	J.16	SAI-SK-M12 UNI	2330260000	D.31	SAI-BW-3/7	1021310000	D.5	SAIEND CAN M8 4P	1955340000	C.65
SAI-M23-KBC-1.5-14..56	1170230000	K.12	SAI-SK-M12 UNI	2330260000	F.10	SAI-BW-3/9	1021320000	D.7	SAIEND CAN M8 4P	1955340000	F.23
SAI-M23-KBC-1.5-56-1.0	1170240000	J.16	SAI-SK-M12 UNI	2330260000	F.14	SAI-BW-4-IDC M12	1812890000	D.24	SAIEND CAN M8 4P	1955340000	F.25
SAI-M23-KBC-1.5-56-1.0	1170240000	K.12	SAI-SK-M12 UNI	2330260000	F.18	SAI-BW-4/11-7/8"	1292070000	E.7	SAIEND CAN M8 4P	1955340000	F.27
SAI-M23-KBC-2-0.75-2.5	1170260000	J.17	SAI-SK-M12 UNI	2330260000	F.23	SAI-BW-4/7	9457700000	D.5	SAIEND CAN-M12 5P A-COD	1784760000	F.14
SAI-M23-KBC-2-0.75-2.5	1170260000	K.12	SAI-SK-M12 UNI	2330260000	F.25	SAI-BW-4/7	9457700000	D.7	SAIEND PB M12 5P B-COD	1784770000	F.10
SAI-M23-KBC-L-2.5-4.0	1170420000	J.29	SAI-SK-M12 UNI	2330260000	F.27	SAI-BW-4/7-(KV)	1935610000	D.10	SAI-PB-2X0-24-PUR	1232620000	C.8
SAI-M23-KBC-L-2.5-4.0	1170420000	K.12	SAI-SK-M12 UNI	2330260000	F.37	SAI-BW-4/8-S-M12 4P D-ZF	1139330000	D.18	SAI-PB-2X0-34-PVC	1933640000	C.9
SAI-M23-KS-7/12	1169900000	J.12	SAI-SSA-PG7	1983800000	D.42	SAI-BW-4/9	1807240000	D.7	SAI-PB-PA-2X1-0-PVC-BL	1232630000	C.30
SAI-M23-KS-L-7/12	1170270000	J.26	SAI-T-5-M12/M12 B-COD	1004310150	B.27	SAI-BW-4/9-7/8"	1812470000	E.6	SAI-PH-PA-2X1-0-PVC-SW	1232640000	C.30
SAI-M23-KSC-0.25-1.0	1170390000	J.29	SAI-T-5-M12/M12 B-COD	1057940000	D.29	SAI-BW-5/1-7/8"	1292030000	E.7	SAI-H-SLL-3x0,25mm²(PUR)	1902140000	B.56
SAI-M23-KSC-0.25-1.0	1170390000	K.12	SAI-T-5S-PARA	1001180001	K.15	SAI-BW-5/7	9457260000	D.8	SAI-H-SLL-3x0,25mm²(PVC)	1902190000	B.56
SAI-M23-KSC-0.08/0.56	1170140000	J.16	SAI-TS-35 MF	1917400000	I.45	SAI-BW-5/7	9457260000	D.9	SAI-H-SLL-3x0,34mm²(PUR)	1902110000	B.56
SAI-M23-KSC-0.14/1.00	1170150000	J.16	SAI-WDF 5P B M12 60mm	1820690000	D.30	SAI-BW-5/7-(KV)	1962630000	D.10	SAI-H-SLL-3x0,34mm²(PVC)	1902160000	B.56
SAI-M23-KSC-0.14/1.00	1170150000	K.12	SAI-WDF 5P M12 60mm	1819450000	D.30	SAI-BW-5/S-8-S-M12 5P A-ZF	1275750000	D.5	SAI-H-SLL-3x0,75-8x0,34	9457420000	B.57
SAI-M23-KSC-1.00-1.5	1170170000	J.16	SAI-Y-4/4-24 M12/8	1783420000	D.28	SAI-BW-5/9	1807330000	D.8	SAI-H-SLL-3X0,34 SI PUR	1357320000	B.56
SAI-M23-KSC-1.5-14..1	1170220000	J.16	SAI-Y-4S-M12/M12	1060730000	D.28	SAI-BW-5/9-7/8"	1292020000	E.6	SAI-H-SLL-3X0,34-UGE	1345520000	B.56
SAI-M23-KSC-1.5-14..1	1170220000	K.12	SAI-Y-5S B2-4 M12	1783410000	D.28	SAI-BW-5/8 M12	1803910000	C.32	SAI-H-SLL-3X0,75-16X0,34	9457560000	B.57
SAI-M23-KSC-2-0.75-2.5	1170250000	J.17	SAI-Y-5S M12/M12 2B0	1881710000	D.30	SAI-BW-5/8 M12	1803910000	D.15	SAI-H-SLL-3X1-0-16X0,5	1344720000	B.57
SAI-M23-KSC-2-0.75-2.5	1170250000	K.12	SAI-Y-5S PARA 2M12	1783430000	D.28	SAI-BW-5/S-8 M12	1803920000	C.32	SAI-H-SLL-4x0,25mm²(PUR)	1902120000	B.56
SAI-M23-KSC-L-0.75-2.5	1170400000	J.29	SAI-Y-5S PARA 2M12	1783430000	H.7	SAI-BW-5/S-8 M12	1803920000	D.15	SAI-H-SLL-4x0,34mm²(PVC)	1902170000	B.56
SAI-M23-KSC-L-0.75-2.5	1170400000	K.12	SAI-B-5/9-VB	1826880000	D.28	SAI-BW-5/S-8 M12 B-COD	1944580000	C.12	SAI-H-SLL-4x0,34mm²(PUR)	1902130000	B.56
SAI-M23-KSC-L-2-5-4.0	1170410000	J.29	SAI-B 5/9-VA	1920710000	C.31	SAI-BW-5/S-8 M12 B-COD	1944580000	D.17	SAI-H-SLL-4x0,34mm²(PVC)	1902180000	B.56
SAI-M23-KSC-L-2-5-4.0	1170410000	K.12	SAI-B 5/9-VA	1920710000	D.12	SAI-BW-5/S-8 M12 B-COD	1944580000	D.17	SAI-H-SLL-4X-34 SI PUR	1357330000	B.56
SAI-M23-KSW-L-7/12	1170290000	J.26	SAI-B 5/9-VA	1920710000	I.31	SAI-BW-5/8-3P(TL)	1920970000	D.22	SAI-H-SLL-4X-34 UGE	1345530000	B.56
SAI-M23-SE-12	1170070000	J.14	SAI-B 5/9-VA-B-COD	1920730000	C.11	SAI-BW-5/8-3P(TL)	1920970000	D.6	SAI-H-SLL-5X0,75-16X0,34	9457970000	B.57
SAI-M23-SE-12-10MM	1224220000	J.21	SAI-B 5/9-VA-B-COD	1920730000	D.12	SAI-BW-5/8-M P1	1920980000	D.22	SAI-H-SLL-5X0,34 SI PUR	1357340000	B.56
SAI-M23-SE-12-10MM-PE	1224620000	J.21	SAI-B 5/9-VA-B-COD	1920730000	I.31	SAI-BW-5/8-M P1	1920980000	D.6	SAI-H-SLL-5X0,34-UGE	1345540000	B.56
SAI-M23-SE-12-12MM-G	1224630000	J.21	SAI-B 12/9 (TL)	1924960000	D.11	SAI-E 7/8-B 3-0-2U-H	1292390000	E.8	SAIL-7/8-BG-3-1.5U	1292100150	E.11
SAI-M23-SE-12-17MM	1224230000	J.21	SAI-B 12/9 (TL)	1924960000	D.5	SAI-E 7/8-B 3-0-2U-PG11	1292370000	E.9	SAIL-7/8-BG-4-1.5U	1292140150	E.11
SAI-M23-SE-12-17MM-G	1224640000	J.21	SAI-B 3-0DC (0,75) M12	1852730000	D.25	SAI-E 7/8-B 3-0-2U-PG13.5	1292380000	E.10	SAIL-7/8-BG-5-1.5U	129210150	E.11
SAI-M23-SE-12-3.5MM	1224160000	J.21	SAI-B 3-0DC M12B-COD	1864740000	C.13	SAI-E 7/8-B 4-0-2U-H	1292450000	E.8	SAIL-7/8-BW-3-1.5U	1292110150	E.11
SAI-M23-SE-12-3.5MM-G	1224580000	J.21	SAI-B 3-0DC M12B-COD	1864740000	D.16	SAI-E 7/8-B 4-0-2U-PG11	1292430000	E.9	SAIL-7/8-BW-4-1.5U	1292150150	E.11
SAI-M23-SE-12-3.5MM-PE	1224180000	J.21	SAI-B 3-0DC M8 small	1784030000	D.26	SAI-E 7/8-B 4-0-2U-PG13.5	1292440000	E.10	SAIL-7/8-BW-5-1.5U	1292200150	E.11
SAI-M23-SE-12-F	1224140000	J.21	SAI-B 3/7	1815670300	B.7	SAI-E 7/8-B 5-0-2U-H	1292520000	E.8	SAIL-7/8-G-3-1.5U	1292080150	E.11
SAI-M23-SE-12-F	1224560000	J.21	SAI-B 3/7	1010840000	C.74	SAI-E 7/8-B 5-0-2U-PG11	1292500000	E.9	SAIL-7/8-G-4-1.5U	1292120150	E.11
SAI-M23-SE-16	1170800000	J.15	SAI-B 3/7	1021490000	D.5	SAI-E 7/8-B 5-0-2U-PG13.5	1292510000	E.10	SAIL-7/8-G-5-1.5U	1292170150	E.11
SAI-M23-SE-16-10MM	1224290000	J.22	SAI-B 3/7	1021490000	D.7	SAI-E 7/8-S-3-0-2U-H	1292350000	E.8	SAIL-7/8-W-3-1.5U	1292090150	E.11
SAI-M23-SE-16-17MM	1224310000	J.22	SAI-B 3/7	1224020000	J.20	SAI-E 7/8-S-3-0-2U-PG11	1292330000	E.9	SAIL-7/8-B-4-1.5U	1292130150	E.11
SAI-M23-SE-16-3.5MM	1224260000	J.22	SAI-B 3/9	1021510000	D.5	SAI-E 7/8-S-3-0-2U-PG13.5	1292440000	E.10	SAIL-7/8-B-5-1.5U	1292180150	E.11
SAI-M23-SE-16-F	1224240000	J.22	SAI-B 4-1DC (0,75) M12	1852750000	D.25	SAI-E 7/8-S-4-0-2U-H	1292420000	E.8	SAIL-7/8-M2BG-12-1.5U	1879710150	B.14
SAI-M23-SE-17	1170100000	J.15	SAI-B 4-1DC M12 small	1781540000	D.24	SAI-E 7/8-S-4-0-2U-PG11	1292400000	E.9	SAIL-M2BG-3-1.5UGE	1092910150	B.11
SAI-M23-SE-17-10MM	1224370000	J.22	SAI-B 4-1DC M8 small	1784050000	D.26	SAI-E 7/8-S-4-0-2U-PG13.5	1292410000	E.10	SAIL-M2BG-3-1.5	1968850150	B.11
SAI-M23-SE-17-10MM-G	1224710000	J.22	SAI-B 4/11-1.5	1353730000	D.9	SAI-E 7/8-S-5-0-2PG11	1292470000	E.9	SAIL-M2BG-3-1.5U	19457820150	B.11
SAI-M23-SE-17-17MM	1224380000	J.22	SAI-B 4/11-7/8"	1292050000	E.7	SAI-E 7/8-S-5-0-2U-H	1292490000	E.8	SAIL-M2BG-3-1.5U	19457820150	B.6
SAI-M23-SE-17-17MM-G	1224720000	J.22	SAI-B 4/7	9457240000	D.5	SAI-E 7/8-S-5-0-2U-PG13.5	1292480000	E.10	SAIL-M2BG-3-5-0.5U	1925570150	B.11
SAI-M23-SE-17-3.5MM	1224670000	J.22	SAI-B 4/7	9457240000	D.7	SAI-E 7/8-S-5-0-2U-PG16	1292480000	E.10	SAIL-M2BG-3-5-0.5V	1925570500	B.6
SAI-M23-SE-17-3.5MM-G	1224760000	J.22	SAI-B 4/7 (KV)	1921080000	D.10	SAI-E 7/8-S-4-0-2U-PG11	1292500000	E.34	SAIL-M2BG-3-10U	9457821000	B.6
SAI-M23-SE-17-F	1224320000	J.22	SAI-B 4/9	1807230000	D.7	SAI-E 7/8-S-4-0-2U-PG13.5	1292510000	E.37	SAIL-M2BG-3-10V	1925571000	B.6
SAI-M23-SE-17-F-G	1224650000	J.22	SAI-B 4/9-7/8"	1812480000	E.6	SAI-E 7/8-S-4-0-2U-PG16	1292410000	E.33	SAIL-M2BG-3-3.0U	9457820300	B.6
SAI-M23-SE-19	1170120000	J.15	SAI-B 5/11-1.5	1353730000	D.9	SAI-E 7/8-S-4-0-5U-M16	1861120000	D.33	SAIL-M2BG-3-3.0V	1925570300	B.6
SAI-M23-SE-19-10MM	1224160000	J.22	SAI-B 5/11-7/8"	1292050000	E.7	SAI-E 7/8-S-4-0-5U-P69	1861250000	D.35	SAIL-M2BG-4-1.5UGE	1092920150	B.11
SAI-M23-SE-19-10MM-G	1224410000	J.23	SAI-B 5/11-7/8	1921070000	D.10	SAI-E 7/8-S-4-0-5U-P69	1861210000	D.33	SAIL-M2BG-4-1.5	1867410150	B.11
SAI-M23-SE-19-10MM-PE	1224440000	J.23	SAI-B 4/7	9457240000	D.5	SAI-E 7/8-S-4-0-5U-PG16	1861240000	D.33	SAIL-M2BG-4-1.5V	1925580500	B.6
SAI-M23-SE-19-F	1224390000	J.23	SAI-B 5/7-ZF	1924970000	D.19	SAI-E 7/8-S-4-0-5U-P69	1861270000	D.35	SAIL-M2BG-4-1.5UGE	1092920150	B.11
SAI-M23-SE-6	1170000000	J.14	SAI-B 5/7-ZF	1924970000	D.5	SAI-E 7/8-S-4-0-5U-PG16	1861270000	D.33	SAIL-M2BG-4-1.5	1968580150	B.11
SAI-M23-SE-6-10MM	1224050000	J.20	SAI-B 5/9	1807250000	D.8	SAI-E 7/8-S-4-0-5U-PG16	1861190000	D.33	SAIL-M2BG-4-3-XU	9457820000	B.6
SAI-M23-SE-6-17MM	1224060000	J.20	SAI-B 8/9	1836960000	D.8	SAI-E 7/8-S-5-0-5U-M16	1861140000	D.33	SAIL-M2BG-4-3-XV	1925570000	B.6
SAI-M23-SE-7	1170030000	J.14	SAI-B 5/8-S M12 5P A-COD	1784750000	C.32	SAI-E 7/8-S-5-0-5U-AEH-V4	1861220000	D.33	SAIL-M2BG-4-3.0U	1057740150	B.43
SAI-M23-SE-7-10MM	1224540000	J.21	SAI-B 5/8-S M12 5P A-COD	1838380000	D.20	SAI-E 7/8-S-5-0-5U-P69	1861210000	D.33	SAIL-M2BG-4-3.0V	1925580150	B.43
SAI-M23-SE-7-10MM-G	1224770000	J.21	SAI-B 5/8-S M12 5P A-COD	1784750000	D.15	SAI-E 7/8-S-5-0-5U-PG16					

Type	Order No.	Page	Type	Order No.	Page	Type	Order No.	Page	Type	Order No.	Page			
SAIL-M12BW-3-1.5T	1968560150	B.11	SAIL-M12G-4-1.5U	9456100150	B.11	SAIL-M12G-4-1.5U	9456100150	B.4	SAIL-M12GM12G-5S1.5U	1058510150	B.28	SAIL-M12GM8G-3-1.5U	9457770150	B.4
SAIL-M12BW-3-1.5U	9457320150	B.11	SAIL-M12G-4-1.5U	9456100150	B.4	SAIL-M12G-4-1.5V	1925440150	B.11	SAIL-M12GM12G-8S1.5U	1279440150	B.14	SAIL-M12GM8G-3-1.5V	1938170150	B.29
SAIL-M12BW-3-1.5U	9457320150	B.7	SAIL-M12G-4-1.5V	1925440150	B.4	SAIL-M12G-4-1.5V	1925440150	B.4	SAIL-M12GM12G-CD-1.5A	1964710150	C.63	SAIL-M12GM8G-3-10U	9457771000	B.4
SAIL-M12BW-3-1.5V	1925630150	B.11	SAIL-M12G-4-10U	9456101000	B.4	SAIL-M12G-4-10V	1925441000	B.4	SAIL-M12GM12G-CD-1.5B	1060130150	C.63	SAIL-M12GM8G-3-10V	1938171000	B.4
SAIL-M12BW-3-10U	9457321000	B.7	SAIL-M12G-4-10V	1925441000	B.4	SAIL-M12G-4-10V	1925441000	B.4	SAIL-M12GM12G-PB-1.5D	1873310150	C.7	SAIL-M12GM8G-3-30U	9457770300	B.4
SAIL-M12BW-3-10V	1925631000	B.7	SAIL-M12G-4-3.0U	9456100300	B.4	SAIL-M12G-4-3.0U	9456100300	B.4	SAIL-M12GM12W-2/4-1.5UGE	1093040150	B.26	SAIL-M12GM8G-3-3.0V	1938170300	B.4
SAIL-M12BW-3-3.0U	9457320300	B.7	SAIL-M12G-4-3.0V	9456100300	B.4	SAIL-M12G-4-3.0V	9456100300	B.4	SAIL-M12GM12W-2/4-1.5U	9457890150	B.26	SAIL-M12GM8G-3-3.0U	9457770500	B.4
SAIL-M12BW-3-3.0V	1925630300	B.7	SAIL-M12G-4-5.0U	9456100500	B.4	SAIL-M12G-4-5.0U	9456100500	B.4	SAIL-M12GM12W-2/4-1.5V	1925370150	B.26	SAIL-M12GM8G-3-3.0V	1938170500	B.4
SAIL-M12BW-3-5.0U	9457320500	B.7	SAIL-M12G-4-5.0V	1925440500	B.4	SAIL-M12G-4-XU	9456100000	B.4	SAIL-M12GM12W-3-1.5UGE	1093050150	B.25	SAIL-M12GM8G-3-XXU	9457770000	B.4
SAIL-M12BW-3-5.0V	1925630500	B.7	SAIL-M12G-4-XU	9456100000	B.4	SAIL-M12G-4-XV	1925440000	B.4	SAIL-M12GM12W-3-1.5T	1021720150	B.25	SAIL-M12GM8G-3-XV	1938170000	B.4
SAIL-M12BW-3-XXU	9457320000	B.7	SAIL-M12G-4-XV	1925440000	B.4	SAIL-M12G-4-1.5U	1057780150	B.43	SAIL-M12GM12W-3-1.5U	9457390150	B.7	SAIL-M12GM8G-4-1.5U	9456660150	B.29
SAIL-M12BW-3-XXV	1925630000	B.7	SAIL-M12G-4-1.5U	1061890150	B.43	SAIL-M12G-4-1.5U	1061890150	B.43	SAIL-M12GM12W-3-1.5V	1925340150	B.25	SAIL-M12GM8G-4-1.5V	1938200150	B.29
SAIL-M12BW-3-1.5U	1061890150	B.43	SAIL-M12G-4-1.5U	1114880150	B.16	SAIL-M12G-4-1.5U	1114880150	B.16	SAIL-M12GM12W-3-1.5V	1925340150	B.25	SAIL-M12GM8G-4-1.5V	1938200150	B.29
SAIL-M12BW-3L1.5U	9457800150	B.16	SAIL-M12G-5-1.5U	1092990150	B.11	SAIL-M12G-5-1.5T	1021650150	B.11	SAIL-M12GM12W-3-10U	9457391000	B.7	SAIL-M12GM8G-4-10U	9456661000	B.5
SAIL-M12BW-3L1.5U	9457800150	B.8	SAIL-M12G-5-1.5U	945610150	B.11	SAIL-M12G-5-1.5U	945610150	B.4	SAIL-M12GM12W-3-10V	1925341000	B.7	SAIL-M12GM8G-4-10V	1938201000	B.5
SAIL-M12BW-3L1.5V	1925460150	B.16	SAIL-M12G-5-1.5U	9457610150	B.4	SAIL-M12G-5-1.5U	9457610150	B.4	SAIL-M12GM12W-3-3.0U	9457390300	B.25	SAIL-M12GM8G-4-3.0U	9456660300	B.5
SAIL-M12BW-3L1.5V	1925460150	B.8	SAIL-M12G-5-1.5V	1925460150	B.11	SAIL-M12G-5-1.5V	1925460150	B.4	SAIL-M12GM12W-3-3.0V	1925340300	B.7	SAIL-M12GM8G-4-3.0V	1938200300	B.5
SAIL-M12BW-3L10U	9457801000	B.8	SAIL-M12G-5-1.5V	1925460150	B.4	SAIL-M12G-5-1.5V	1925460150	B.4	SAIL-M12GM12W-3-5.0U	9457390500	B.7	SAIL-M12GM8G-4-5.0U	9456660500	B.5
SAIL-M12BW-3L10V	1925461000	B.8	SAIL-M12G-5-10U	9457611000	B.4	SAIL-M12G-5-10V	1925461000	B.4	SAIL-M12GM12W-3-5.0V	1925340500	B.7	SAIL-M12GM8G-4-5.0V	1938200500	B.5
SAIL-M12BW-3L3.0U	9457803000	B.8	SAIL-M12G-5-10V	1925461000	B.4	SAIL-M12G-5-10V	1925461000	B.4	SAIL-M12GM12W-3-XU	9457390000	B.7	SAIL-M12GM8G-4-XU	9456660000	B.5
SAIL-M12BW-3L3.0V	1925460300	B.8	SAIL-M12G-5-3.0U	9457610300	B.4	SAIL-M12G-5-3.0U	9457610300	B.4	SAIL-M12GM12W-3-XV	1925340000	B.7	SAIL-M12GM8G-4-XV	1938200000	B.5
SAIL-M12BW-3L5.0U	9457805000	B.8	SAIL-M12G-5-3.0V	1925460300	B.4	SAIL-M12G-5-3.0V	1925460300	B.4	SAIL-M12GM12W-3-XV	1818090100	J.30	SAIL-M12GM8G-3-1.5U	9457980150	B.29
SAIL-M12BW-3L5.0V	1925460500	B.8	SAIL-M12G-5-5.0U	1925460500	B.4	SAIL-M12G-5-5.0U	1925460500	B.4	SAIL-M12GM12W-3B-1.5U	1057900150	B.44	SAIL-M12GM8G-3-1.5U	9457980150	B.5
SAIL-M12BW-3LX.XU	9457800000	B.8	SAIL-M12G-5-XU	9457610000	B.4	SAIL-M12G-5-XU	9457610000	B.4	SAIL-M12GM12W-3L1.5U	9457790150	B.27	SAIL-M12GM8G-3-1.5V	1938180150	B.29
SAIL-M12BW-3S1.5U	19096850150	B.17	SAIL-M12G-5-XV	1925460000	B.4	SAIL-M12G-5-XV	1925460000	B.4	SAIL-M12GM12W-3L1.5V	9457790150	B.27	SAIL-M12GM8G-3-1.5V	1938180150	B.29
SAIL-M12BW-4-1.5UGE	1092960150	B.11	SAIL-M12G-58-1.5U	1057790150	B.43	SAIL-M12G-58-1.5U	1057790150	B.43	SAIL-M12GM12W-3L1.5V	1925410150	B.27	SAIL-M12GM8G-3-10U	9457981000	B.5
SAIL-M12BW-4-1.5T	1968570150	B.11	SAIL-M12G-58-1.5U	1926690150	B.17	SAIL-M12G-58-1.5U	1926690150	B.17	SAIL-M12GM12W-3L1.5V	1925410150	B.27	SAIL-M12GM8G-3-10V	1938181000	B.5
SAIL-M12BW-4-1.5U	9457740150	B.11	SAIL-M12G-8-1.5U	1279410150	B.14	SAIL-M12G-8-1.5U	1279410150	B.14	SAIL-M12GM12W-310U	9457791000	B.8	SAIL-M12GM8G-3-3.0U	9457980300	B.5
SAIL-M12BW-4-1.5U	9457740150	B.7	SAIL-M12G-8-1.5U	1279430150	B.18	SAIL-M12G-8-1.5U	1279430150	B.18	SAIL-M12GM12W-310V	1925411000	B.8	SAIL-M12GM8G-3-3.0V	1938180300	B.5
SAIL-M12BW-4-1.5V	1925640150	B.11	SAIL-M12G-CD-1.5A	1964700150	C.62	SAIL-M12G-CD-1.5B	1060110150	C.62	SAIL-M12GM12W-3L3.0U	9457790300	B.27	SAIL-M12GM8G-3-3.0U	9457980500	B.5
SAIL-M12BW-4-1.5V	1925640150	B.7	SAIL-M12G-CD-1.5B	1060110150	C.62	SAIL-M12G-CD-1.5T	1021710150	B.25	SAIL-M12GM12W-3L3.0V	1925410300	B.8	SAIL-M12GM8G-3-3.0V	1938180500	B.5
SAIL-M12BW-4-10U	9457741000	B.7	SAIL-M12G-PB-1.50	1873300150	C.6	SAIL-M12G-PB-1.50	1873300150	C.6	SAIL-M12GM12W-3L5.0U	9457790500	B.8	SAIL-M12GM8G-3-XU	9457980000	B.5
SAIL-M12BW-4-10V	1925641000	B.7	SAIL-M12G-2/4-1.5UGE	1093000150	B.26	SAIL-M12G-2/4-1.5UGE	1093000150	B.26	SAIL-M12GM12W-3L5.0V	9457790500	B.8	SAIL-M12GM8G-3-XV	1938180000	B.5
SAIL-M12BW-4-2L1.5U	1092950150	B.16	SAIL-M12GM12G-2/4-1.5U	9456990150	B.26	SAIL-M12GM12G-2/4-1.5U	9456990150	B.26	SAIL-M12GM12W-3LX.XU	9457790000	B.8	SAIL-M12GM8G-3-3.0U	1093110150	B.31
SAIL-M12BW-4-2L1.5U	1092950150	B.16	SAIL-M12GM12G-2/4-1.5U	1925330150	B.26	SAIL-M12GM12G-2/4-1.5U	1925330150	B.26	SAIL-M12GM12W-3LX.XV	1925410000	B.8	SAIL-M12GM8G-3-3.0V	1938180300	B.5
SAIL-M12BW-4-2L1.5V	1925470150	B.16	SAIL-M12GM12G-3-1.5T	1021710150	B.25	SAIL-M12GM12G-3-1.5T	1021710150	B.25	SAIL-M12GM12W-3L1.5U	9457791050	B.27	SAIL-M12GM8G-3-1.5U	9457791050	B.31
SAIL-M12BW-4-2L1.5V	1925470150	B.8	SAIL-M12GM12G-3-1.5U	9457230150	B.25	SAIL-M12GM12G-3-1.5U	9457230150	B.25	SAIL-M12GM12W-3L1.5V	1925410150	B.27	SAIL-M12GM8G-3-1.5V	1938180100	B.5
SAIL-M12BW-4-2L1.5U	9456381000	B.8	SAIL-M12GM12G-3-1.5U	9457230150	B.25	SAIL-M12GM12G-3-1.5U	9457230150	B.25	SAIL-M12GM12W-3L1.5V	1925410150	B.27	SAIL-M12GM8G-3-1.5V	1938180100	B.5
SAIL-M12BW-4-2L1.5U	9456380300	B.8	SAIL-M12GM12G-3-1.5V	1925330150	B.26	SAIL-M12GM12G-3-1.5V	1925330150	B.26	SAIL-M12GM12W-3L1.5U	9457790000	B.8	SAIL-M12GM8G-3-1.5U	9457790000	B.31
SAIL-M12BW-4-2L3.0U	1925470300	B.8	SAIL-M12GM12G-3-1.5V	1093010150	B.25	SAIL-M12GM12G-3-1.5V	1093010150	B.25	SAIL-M12GM12W-3LX.XU	1291940000	E.7	SAIL-M12GM8G-3-3.0U	1093160150	B.31
SAIL-M12BW-4-2L5.0U	9456380500	B.8	SAIL-M12GM12G-3-1.5V	1093010150	B.25	SAIL-M12GM12G-3-1.5V	1093010150	B.25	SAIL-M12GM12W-3LX.XV	1291940000	E.7	SAIL-M12GM8G-3-3.0V	1093160150	B.31
SAIL-M12BW-4-2L5.0V	1925470500	B.8	SAIL-M12GM12G-3-3.0U	9457230300	B.6	SAIL-M12GM12G-3-3.0U	9457230300	B.6	SAIL-M12GM12W-4-1.5UGE	1093070150	B.25	SAIL-M12GM8G-4-1.5UGE	1093070150	B.31
SAIL-M12BW-4-2L5.0V	1925470500	B.8	SAIL-M12GM12G-3-3.0U	1925303000	B.6	SAIL-M12GM12G-3-3.0U	1925303000	B.6	SAIL-M12GM12W-4-1.5U	1093070150	B.25	SAIL-M12GM8G-4-1.5U	1093070150	B.31
SAIL-M12BW-4-2LX.XU	9456380000	B.8	SAIL-M12GM12G-3-3.0V	1925303000	B.6	SAIL-M12GM12G-3-3.0V	1925303000	B.6	SAIL-M12GM12W-4-1.5V	1093070150	B.25	SAIL-M12GM8G-4-1.5V	1093070150	B.31
SAIL-M12BW-4-2LX.XV	1925470000	B.8	SAIL-M12GM12G-3-3.0V	1925303000	B.6	SAIL-M12GM12G-3-3.0V	1925303000	B.6	SAIL-M12GM12W-4-1.5V	1093070150	B.25	SAIL-M12GM8G-4-1.5V	1093070150	B.31
SAIL-M12BW-4-3.0U	9457740300	B.7	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12W-4-1.5V	1093070150	B.25	SAIL-M12GM8G-4-1.5V	1093070150	B.31
SAIL-M12BW-4-3.0V	1925470300	B.7	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12W-4-1.5V	1093070150	B.25	SAIL-M12GM8G-4-1.5V	1093070150	B.31
SAIL-M12BW-4-3.0U	9457740300	B.7	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12W-4-1.5V	1093070150	B.25	SAIL-M12GM8G-4-1.5V	1093070150	B.31
SAIL-M12BW-4-3.0V	1925470300	B.7	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12W-4-1.5V	1093070150	B.25	SAIL-M12GM8G-4-1.5V	1093070150	B.31
SAIL-M12BW-4-3.0U	9457740300	B.7	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12W-4-1.5V	1093070150	B.25	SAIL-M12GM8G-4-1.5V	1093070150	B.31
SAIL-M12BW-4-3.0V	1925470300	B.7	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12W-4-1.5V	1093070150	B.25	SAIL-M12GM8G-4-1.5V	1093070150	B.31
SAIL-M12BW-4-3.0U	9457740300	B.7	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12G-3-3.0V	1093010150	B.25	SAIL-M12GM12W-4-1.5V					

Type	Order No.	Page	Type	Order No.	Page	Type	Order No.	Page	Type	Order No.	Page
SAIL-M12W-5-1.5V	1925530150	B.4	SAIL-M12WM8W-4-3.0U	1906340300	B.5	SAIL-M8G-3-1.5U	1824590150	B.19	SAIL-M8GM8G-4S-0.2-CAN	1216820020	C.64
SAIL-M12W-5-10U	9457671000	B.4	SAIL-M12WM8W-4-3.0V	1938220300	B.5	SAIL-M8G-3-1.5V	1927230150	B.19	SAIL-M8GM8G-4S-0.25-CAN	1004330150	B.16
SAIL-M12W-5-10V	1925531000	B.4	SAIL-M12WM8W-4-5.0U	1906340500	B.5	SAIL-M8G-3-1.5V	1927230150	B.4	SAIL-M8GM8G-4S-0.25-CAN	1216820025	C.64
SAIL-M12W-5-3.0U	9457670300	B.4	SAIL-M12WM8W-4-5.0V	1938220500	B.5	SAIL-M8G-3-10U	1824591000	B.4	SAIL-M8GM8G-4S-0.3-CAN	1005270150	B.37
SAIL-M12W-5-3.0V	1925530300	B.4	SAIL-M12WM8W-4-X.XU	1906340000	B.5	SAIL-M8G-3-10V	1927231000	B.4	SAIL-M8GM8G-4S-0.3-CAN	1216820030	C.64
SAIL-M12W-5-5.0U	9457670500	B.4	SAIL-M12WM8W-4-X.XV	1938220000	B.5	SAIL-M8G-3-3.0U	1824590300	B.4	SAIL-M8GM8G-4S-0.30-SB	1981900030	C.65
SAIL-M12W-5-5.0V	1925530500	B.4	SAIL-M16BW-12-1.5U	1259010150	B.40	SAIL-M8G-3-3.0V	1927230300	B.4	SAIL-M8GM8G-4S-0.5-CAN	1005460150	B.37
SAIL-M12W-5-X.XU	9457670000	B.4	SAIL-M23-KSW-7/12	1169930000	J.12	SAIL-M8G-3-5.0U	1824590500	B.4	SAIL-M8GM8G-4S-0.5-CAN	1058530150	C.6
SAIL-M12W-5-X.XV	1925530000	B.4	SAIL-M5BG-3P-1.5U	1873290150	B.23	SAIL-M8G-3-5.0V	1927230500	B.4	SAIL-M8GM8G-4S-0.5-CAN	1216820050	C.64
SAIL-M12W-5B-1.5U	1057820150	B.43	SAIL-M5BG-4P-1.5U	1873250150	B.23	SAIL-M8G-3-X.XU	1824590000	B.4	SAIL-M8GM8G-4S-0.8-CAN	1058540150	C.6
SAIL-M12W-5S-1.5U	1906520150	B.17	SAIL-M5BW-3P-1.5U	1873260150	B.23	SAIL-M8G-3-X.XV	1927230000	B.4	SAIL-M8GM8G-4S-0.8-CAN	1216820080	C.64
SAIL-M12W-8-1.5U	1279420150	B.14	SAIL-M5BW-4P-1.5U	1873270150	B.23	SAIL-M8G-3S1.5U	1906560150	B.22	SAIL-M8GM8G-4S-0.8-CAN	1006920000	F.39
SAIL-M12W-8S-1.5U	1276060150	B.15	SAIL-M5G-3P-1.5U	1854060150	B.23	SAIL-M8G-4-1.5U	1906270150	B.19	SAIL-M8GM8G-4S-1.0-CAN	1216820100	C.64
SAIL-M12W-CD-1.5A	1062220150	C.62	SAIL-M5G-4P-1.5U	1871700150	B.23	SAIL-M8G-4-1.5U	1906270150	B.4	SAIL-M8GM8G-4S-1.0-CAN	1058570150	C.7
SAIL-M12W-CO-1.5B	1062170150	C.62	SAIL-M5W-3P-1.5U	1873280150	B.23	SAIL-M8G-4-1.5V	1927250150	B.19	SAIL-M8GM8G-4S-1.0-CAN	1006930000	F.38
SAIL-M12W-PB-1.5D	1061970150	C.6	SAIL-M5W-4P-1.5U	1873240150	B.23	SAIL-M8G-4-1.5V	1927250150	B.4	SAIL-M8GM8G-4S-1.00-SB	1981900100	C.65
SAIL-M12W-PB-1.5E	1062340150	C.6	SAIL-M8BG-3-1.5UGE	1093190150	B.19	SAIL-M8G-4-10U	1906271000	B.4	SAIL-M8GM8G-4S-1.5-CAN	1216820150	C.64
SAIL-M12W-12G-3-1.5U	1821050150	B.6	SAIL-M8BG-3-1.5U	9457450150	B.19	SAIL-M8G-4-10V	1927250100	B.4	SAIL-M8GM8G-4S-1.5-CAN	1058630000	C.66
SAIL-M12W-12G-3-10U	1821051000	B.6	SAIL-M8BG-3-1.5U	9457450150	B.4	SAIL-M8G-4-3.0U	1906270300	B.4	SAIL-M8GM8G-4S-1.5-CAN	1006940000	F.38
SAIL-M12W-12G-3-3.0U	1821050300	B.6	SAIL-M8BG-3-1.5V	1927240150	B.19	SAIL-M8G-4-3.0V	1927250300	B.4	SAIL-M8GM8G-4S-1.50-SB	1981900150	C.65
SAIL-M12W-12G-3-5.0U	1821050500	B.6	SAIL-M8BG-3-1.5V	1927240150	B.4	SAIL-M8G-4-5.0U	1906270500	B.4	SAIL-M8GM8G-4S-10-CAN	1279400300	C.10
SAIL-M12W-12G-3-XXU	1815670150	B.25	SAIL-M8BG-3-10U	9457451000	B.4	SAIL-M8G-4-5.0V	1927250500	B.4	SAIL-M8GM8G-4S-10-CAN	1279400500	C.10
SAIL-M12W-12G-3-XXV	1821050000	B.6	SAIL-M8BG-3-10V	1927241000	B.4	SAIL-M8G-4-X.XU	1906270000	B.4	SAIL-M8GM8G-4S-10-CAN	1279409300	C.10
SAIL-M12W-12G-3-XXU	1279490200	C.10	SAIL-M8BG-3-3.0U	9457450300	B.4	SAIL-M8G-4-X.XV	1927250000	B.4	SAIL-M8GM8G-4S-10-CAN	1216821000	C.64
SAIL-M12W-12G-3-XXV	1010840030	C.74	SAIL-M8BG-3-3.0V	1927240300	B.4	SAIL-M8G-4S1.0UIE	1160820010	C.68	SAIL-M8GM8G-4S-10-CAN	1058394015	C.73
SAIL-M12W-12G-3-XXU	1224010000	J.20	SAIL-M8BG-3-5.0U	9457450500	B.4	SAIL-M8G-4S0.3UIE	1160820030	C.68	SAIL-M8GM8G-4S-10-CAN	1059340030	C.73
SAIL-M12W-12G-3B-1.5U	1057870150	B.44	SAIL-M8BG-3-5.0V	1927240500	B.4	SAIL-M8G-4S0.5UIE	1160820050	C.68	SAIL-M8GM8G-4S-10-CAN	1010700000	D.21
SAIL-M12W-12G-4B-1.5U	1057880150	B.44	SAIL-M8BG-3S1.5U	1906601500	B.22	SAIL-M8G-4S1.0UIE	1160820100	C.68	SAIL-M8GM8G-4S-10-CAN	1010800000	D.21
SAIL-M12W-12G-5-1.5U	9456500150	B.7	SAIL-M8BG-4-1.5UGE	1093200150	B.19	SAIL-M8G-4S1.5U	1906570150	B.22	SAIL-M8GM8G-4S-10-CAN	1010900000	D.21
SAIL-M12W-12G-5-10U	9456501000	B.7	SAIL-M8BG-4-1.5U	9457850150	B.19	SAIL-M8G-4S10UIE	1160821000	C.68	SAIL-M8GM8G-4S-10-CAN	1222270500	D.38
SAIL-M12W-12G-5-3.0U	9456500300	B.7	SAIL-M8BG-4-1.5U	9457850150	B.5	SAIL-M8G-4S2.0UIE	1160820200	C.68	SAIL-M8GM8G-4S-10-CAN	1223650050	D.38
SAIL-M12W-12G-5-5.0U	9456500500	B.7	SAIL-M8BG-4-1.5V	1927260150	B.19	SAIL-M8G-4S3.0UIE	1160820300	C.68	SAIL-M8GM8G-4S-100-SB	1981901000	C.65
SAIL-M12W-12G-5-XXU	9456500000	B.7	SAIL-M8BG-4-5.0V	1927260150	B.5	SAIL-M8G-4S4.0UIE	1160820400	C.68	SAIL-M8GM8G-4S-150-SB	1981901500	C.65
SAIL-M12W-12G-5B-1.5U	1057890150	B.44	SAIL-M8BG-4-10U	9457851000	B.5	SAIL-M8G-4S5.0UIE	1160820500	C.68	SAIL-M8GM8G-4S-200-SB	1981902000	C.65
SAIL-M12W-12G-3-1.5V	1925380150	B.25	SAIL-M8BG-4-10V	1927261000	B.5	SAIL-M8G-4S7.5UIE	1160820750	C.68	SAIL-M8GM8G-4S-3.0-CAN	1216820300	C.64
SAIL-M12W-12G-3-1.5V	1925380150	B.7	SAIL-M8BG-4-3.0U	9457853000	B.5	SAIL-M8G12M2-3-1.5U	1937950150	B.6	SAIL-M8GM8G-4S-3.0-CAN	1059330015	C.69
SAIL-M12W-12G-3-10V	1925381000	B.7	SAIL-M8BG-4-3.0V	1927260300	B.5	SAIL-M8G12M2-3-3.5U	1937950500	B.6	SAIL-M8GM8G-4S-5.0-CAN	1216820500	C.64
SAIL-M12W-12G-3-3.0V	1925380300	B.7	SAIL-M8BG-4-5.0U	9457855000	B.5	SAIL-M8G12M2-3-3.5V	1938230150	B.6	SAIL-M8GM8G-4S-3.0-CAN	1069880000	F.36
SAIL-M12W-12G-3-X.V	1925380000	B.7	SAIL-M8BG-4-5.0V	9457855000	B.5	SAIL-M8G12M2-3-10U	1937951000	B.6	SAIL-M8GM8G-4S-3.00-SB	1981903000	C.65
SAIL-M12W-12G-3-X.XV	1291910000	E.6	SAIL-M8BG-4-5.0V	1927260500	B.5	SAIL-M8G12M2-3-10V	1938231000	B.6	SAIL-M8GM8G-4S-3.5-CAN	1007000150	B.16
SAIL-M12W-12G-3B-1.5U	1061910150	B.44	SAIL-M8BG-4-5.1U	182720150	B.20	SAIL-M8G12M2-3-X.V	1937950300	B.6	SAIL-M8GM8G-4S-3.5-CAN	1216820350	C.64
SAIL-M12W-12G-3B-1.5V	1061910150	B.44	SAIL-M8BG-3-1.5UGE	1948710150	B.20	SAIL-M8G12M2-4-1.5U	1937980150	B.6	SAIL-M8GM8G-4S-7.0-CAN	1059330100	C.69
SAIL-M12W-12G-4-1.5U	1061931050	B.25	SAIL-M8BG-4-1.5U	1948530150	B.20	SAIL-M8G12M2-4-1.5V	1938260150	B.6	SAIL-M8GM8G-4S-7.0-CAN	1010060000	D.21
SAIL-M12W-12G-4-1.5V	1061931050	B.7	SAIL-M8BG-4-1.5V	1948730150	B.20	SAIL-M8G12M2-4-10U	1937981000	B.6	SAIL-M8GM8G-4S-7.0-CAN	1948740150	B.33
SAIL-M12W-12G-4-3.0V	1061931050	C.74	SAIL-M8BG-3-3.0U	9457850500	B.6	SAIL-M8G12M2-4-10V	1938261000	B.6	SAIL-M8GM8G-4S-7.5-CAN	1009370000	D.29
SAIL-M12W-12G-4-3.0V	1224000000	J.20	SAIL-M8BG-4S-5.0U	1981910500	B.6	SAIL-M8G12M2-4-X.V	1938230000	B.6	SAIL-M8GM8G-4S-5.00-SB	198190500	C.65
SAIL-M12W-12G-4-3-X.V	1925380000	B.7	SAIL-M8BG-4S-5.0V	1981910500	B.6	SAIL-M8G12M2-4-X.XU	1937950000	B.6	SAIL-M8GM8G-4S-5.00-SB	198190500	C.65
SAIL-M12W-12G-4-3-X.XU	1291910000	E.6	SAIL-M8BG-4S-5.0V	1927260500	B.5	SAIL-M8G12M2-4-X.XV	1938230000	B.6	SAIL-M8GM8G-4S-5.00-SB	198190500	C.65
SAIL-M12W-12G-4-3-X.XV	1061910150	B.44	SAIL-M8BG-3-1.5UGE	1093220150	B.19	SAIL-M8G12M2-4-X.XV	1937980500	B.6	SAIL-M8GM8G-4S-5.00-SB	198190500	C.65
SAIL-M12W-12G-4-10U	1061831000	B.7	SAIL-M8BW-3-1.5U	9457830150	B.19	SAIL-M8G12M2-4-5.0V	1938260500	B.6	SAIL-M8GM8G-4S-5.00-SB	198190500	C.65
SAIL-M12W-12G-4-10V	1061831000	B.7	SAIL-M8BW-3-1.5V	9457830150	B.5	SAIL-M8G12M2-4-5.0V	1938260500	B.6	SAIL-M8GM8G-4S-5.00-SB	198190500	C.65
SAIL-M12W-12G-4-10V	1279490100	C.10	SAIL-M8BW-4-1.5U	9457830150	B.5	SAIL-M8G12M2-4-X.XU	1937980000	B.6	SAIL-M8GM8G-4S-5.00-SB	1160930300	C.68
SAIL-M12W-12G-4-3.0B	1010840015	C.74	SAIL-M8BW-4-1.5V	9457830150	B.5	SAIL-M8G12M2-4-X.XV	1938260000	B.6	SAIL-M8GM8G-4S-5.00-SB	1160930300	C.68
SAIL-M12W-12G-4-3.0V	1061910150	B.7	SAIL-M8BW-4-3.0U	9457830300	B.5	SAIL-M8G12M2-4-X.XU	1937980300	B.6	SAIL-M8GM8G-4S-5.00-SB	1160930300	C.68
SAIL-M12W-12G-4-3.0V	1224000000	J.20	SAIL-M8BW-4-3.0V	9457830300	B.5	SAIL-M8G12M2-4-X.XV	1938260000	B.6	SAIL-M8GM8G-4S-5.00-SB	1160930300	C.68
SAIL-M12W-12G-4-3-X.V	1925380000	B.7	SAIL-M8BW-4-3.0V	9457830300	B.5	SAIL-M8G12M2-4-X.XU	1937980300	B.6	SAIL-M8GM8G-4S-5.00-SB	1160930300	C.68
SAIL-M12W-12G-4-3-X.XU	1291910000	E.6	SAIL-M8BW-4-3.0V	9457830300	B.5	SAIL-M8G12M2-4-X.XV	1938260000	B.6	SAIL-M8GM8G-4S-5.00-SB	1160930300	C.68
SAIL-M12W-12G-4-3-X.XV	1061910150	B.29	SAIL-M8BW-4-4.0UIE	1093230150	B.21	SAIL-M8G12M2-4-X.XV	1938270300	B.4	SAIL-M8GM8G-4-3.0-SU	124581000	B.5
SAIL-M12W-12G-4-3-X.XV	1906330150	B.5	SAIL-M8BW-4-3.0U	9456150300	B.5	SAIL-M8G12M2-4-3.0V	1938270300	B.4	SAIL-M8GM8G-4-3.0-SU	124581000	B.5
SAIL-M12W-12G-4-3-X.XV	1906330150	B.5	SAIL-M8BW-4-3.0V	9456150300	B.5	SAIL-M8G12M2-4-3.0V	1938270300	B.4	SAIL-M8GM8G-4-3.0-SU	124581000	B.5
SAIL-M12W-12G-4-3-X.V	1938190150	B.29	SAIL-M8BW-4-4.0V	1093230150	B.21	SAIL-M8G12M2-4-4.5U	1938273000	B.4	SAIL-M8GM8G-4-3.0-SU	124581000	B.5
SAIL-M12W-12G-4-3-X.V	1938190150	B.5	SAIL-M8BW-4-4.0V	1093230150	B.21	SAIL-M8G12M2-4-4.5U	1938273000	B.4	SAIL-M8GM8G-4-3.0-SU	124581000	B.5
SAIL-M12W-12G-4-5.0U	1938190150	B.29	SAIL-M8BW-4-4.5U	1093230150	B.21	SAIL-M8G12M2-4-4.5U	1938273000	B.4	SAIL-M8GM8G-4-3.0-SU	124581000	B.5
SAIL-M12W-12G-4-5.0V	1938190150	B.5	SAIL-M8BW-4-4.5U	1093230150	B.21	SAIL-M8G12M2-4-4.5U	1938273000	B.4	SAIL-M8GM8G-4-3.0-SU	124581000	B.5
SAIL-M12W-12G-4-5.0V	1938190150	B.5	SAIL-M8BW-4-4								

Type	Order No.	Page	Type	Order No.	Page	Type	Order No.	Page	Type	Order No.	Page
SAIL-M8GMW8-4L1.5U	1906450150	B.34	SAIL-VSC-M12W-1.5U	1857720150	B.49	SAISW-4/9	1807360000	D.7	SFC 3/30 MC SDR	1025570000	K.14
SAIL-M8GMW8-4L1.5V	1927200150	B.34	SAIL-VSC-M8G-0.15U	1309680015	B.55	SAISW-4/9-7/8"	1808830000	E.6	SIBL GH SAI	1966200000	G.13
SAIL-M8GMW8R-3-1.5U	1948490150	B.33	SAIL-VSCD-1.5U	9456240150	B.49	SAISW-5/11-7/8"	1291990000	E.7	SIBL GH SAI	1966200000	G.6
SAIL-M8GMW8R-3-1.5V	1948660150	B.33	SAIL-VSCD-M12G-1.5U	9456170150	B.49	SAISW-5/7	9456950000	D.5	STRIPAX	9005000000	K.9
SAIL-M8GMW8R-4-1.5U	1948510150	B.33	SAIL-VSCD-M12W-1.5U	1857730150	B.49	SAISW-5/7	9456950000	D.8	STRIPAX ZERT	9017330000	K.9
SAIL-M8GMW8R-4-1.5V	1948690150	B.33	SAIL-VSCD-M8G-3-1.5U	1916700150	B.55	SAISW-5/7-(KV)	1962610000	D.10	STRIPPER 6-16 RED-LINE	9203110000	K.8
SAIL-M8GRJ45-4S10UIE	1201211000	C.68	SAIL-ZW-3.15U	1964310150	B.18	SAISW-5/9-7/8"	1291980000	E.6			
SAIL-M8GRJ45-4S2.0UIE	1201212020	C.68	SAIL-ZW-M12BG-2/4-1.5U	1812550150	B.38	SAISW-M-4/8 M12	1803930000	C.32			
SAIL-M8GRJ45-4S7.5UIE	1201212050	C.68	SAIL-ZW-M12BW-2/4-1.5U	1964280150	B.38	SAISW-M-4/8 M12	1803930000	D.15			
SAIL-M8W-3-1.5U	1867550150	B.19	SAIL-ZW-M12BW-2/4L1.5U	1964290150	B.38	SAISW-M-5/8 M12	1803940000	C.32			
SAIL-M8W-3-1.5V	1927310150	B.19	SAIL-ZW-M12BW-3L1.5U	1912110150	B.37	SAISW-M-5/8 M12	1803940000	D.15			
SAIL-M8W-3-1.5V	1927310150	B.4	SAIL-ZW-M8BG-3-1.5UGE	1093250150	B.39	SAISW-M-5/8 M12 B-COD	1944570000	D.17	TM 203/18 VO	1798480000	K.15
SAIL-M8W-3-10U	1867551000	B.4	SAIL-ZW-M8BG-3-1.5UGE	9457490150	B.39	SAISW-M-5/8 M12 B-COD	1944570000	D.5	TM 4/12 HF/HB	1719840000	C.69
SAIL-M8W-3-10V	1927311000	B.4	SAIL-ZW-M8BG-3-1.5UGE	1093260150	B.39	SAISW-M-5/8 M12 B-COD	1944570000	D.5	TM 4/18 HF/HB	1719850000	C.69
SAIL-M8W-3-3.0U	1867550300	B.4	SAIL-ZW-M8BW-3-1.5U	1964300150	B.39	SAISW-M-8P(TL)	1920990000	D.6	TM 1-12 NEUTRAL GE	1718411687	C.69
SAIL-M8W-3-3.0V	1927310300	B.4	SAIL-ZW-M8BW-3L1.5U	9457410150	B.39	SAISW-M-8P(TL)	1921000000	D.22	TM-I 1-8 NEUTRAL GE	1718431687	C.69
SAIL-M8W-3-5.0U	1857550500	B.4	SAIP-M12BG-3-1.5U	1108730150	B.12	SAISW-M-8P(TL)	1921000000	D.6	TM-I 18 NEUTRAL WS	1718431044	K.15
SAIL-M8W-3-5.0V	1927310500	B.4	SAIP-M12BG-4-1.5U	1108740150	B.12						
SAIL-M8W-3-XU	1867550000	B.4	SAIP-M12BG-5-1.5U	1108750150	B.12						
SAIL-M8W-3-XV	1927310000	B.4	SAIP-M12BW-3-1.5U	1108770150	B.12						
SAIL-M8W-3S-1.5U	1906850150	B.22	SAIP-M12BW-4-1.5U	1108780150	B.12						
SAIL-M8W-4-1.5U	1867560150	B.19	SAIP-M12BW-5-1.5U	1108790150	B.12						
SAIL-M8W-4-1.5V	1927330150	B.19	SAIP-M12G-3-1.5U	1108800150	B.12						
SAIL-M8W-4-1.5V	1927330150	B.4	SAIP-M12G-4-1.5U	1108810150	B.12						
SAIL-M8W-4-1.5V	1927330150	B.4	SAIP-M12G-5-1.5U	1108820150	B.12						
SAIL-M8W-4-10U	1867561000	B.4	SAIP-M12W-3-1.5U	11088670150	B.12						
SAIL-M8W-4-10V	1927331000	B.4	SAIP-M12W-4-1.5U	11088680150	B.12						
SAIL-M8W-4-3.0U	1867560300	B.4	SAIP-M12W-5-1.5U	11088690150	B.12						
SAIL-M8W-4-3.0V	1927330300	B.4	SAIS 5/9-VA	1920700000	C.31						
SAIL-M8W-4-5.0U	1857560500	B.4	SAIS 5/9-VA	1920700000	D.12						
SAIL-M8W-4-5.0V	1927330500	B.4	SAIS 5/9-VA D-COD	1920700001	C.78						
SAIL-M8W-4-XXU	1867560000	B.4	SAIS 5/9-VA B-COD	1920720000	C.11						
SAIL-M8W-4-XXV	1927330000	B.4	SAIS 5/9-VA C-D	1920720000	C.11						
SAIL-M8W-4S-1.5U	1906850150	B.22	SAIS 5/9-VA D-COD	1920720000	C.11						
SAIL-M8WM12W-3-1.5U	1937970150	B.7	SAIS 5/9-VA B-COD	1920720000	D.12						
SAIL-M8WM12W-3-1.5V	1938250150	B.7	SAIS 5/9-VA B-COD	1920720000	I.31						
SAIL-M8WM12W-3-10U	1937971000	B.7	SAIS-12/9-(TL)	1924950000	D.11						
SAIL-M8WM12W-3-10V	1938251000	B.7	SAIS-12/9-(TL)	1924950000	D.5						
SAIL-M8WM12W-3-3.0U	1937970300	B.7	SAIS-3-IDC (0,75) M12	1852720000	D.28						
SAIL-M8WM12W-3-3.0V	1938250300	B.7	SAIS-3-IDC M8 small	1784040001	D.28						
SAIL-M8WM12W-3-3.0V	1938250300	B.7	SAIS-3-IDC M12-B COD	1864730000	C.13						
SAIL-M8WM12W-3-5.0U	1937970500	B.7	SAIS-3-IDC M12-B COD	1864730000	D.16						
SAIL-M8WM12W-3-5.0V	1938250500	B.7	SAIS-3/7	1021470000	D.9						
SAIL-M8WM12W-3-XU	1937970000	B.7	SAIS-4/7	9457550000	D.8						
SAIL-M8WM12W-3-XV	1938250000	B.7	SAIS-4/7	9457550000	D.7						
SAIL-M8WM12W-3-XXU	1937970000	B.7	SAIS-4/7-(KV)	1921060000	D.10						
SAIL-M8WM12W-3-XXV	1938250300	B.7	SAIS-4/9	1807340000	D.7						
SAIL-M8WM12W-4-1.5U	1938000150	B.7	SAIS-4/9-7/8"	1808840000	E.6						
SAIL-M8WM12W-4-1.5V	1938280150	B.7	SAIS-5/11-1.5	1353740000	D.9						
SAIL-M8WM12W-4-10U	1938001000	B.7	SAIS-5/11-7/8"	1291970000	E.7						
SAIL-M8WM12W-4-10V	1938281000	B.7	SAIS-5/9	1807350000	D.8						
SAIL-M8WM12W-4-3.0U	1938003000	B.7	SAIS-5/9	1807350000	D.7						
SAIL-M8WM12W-4-3.0V	1938280300	B.7	SAIS-5/9-7/8"	1301220000	E.6						
SAIL-M8WM12W-4-4.5U	1938005000	B.7	SAIS-8/9	1836970000	D.8						
SAIL-M8WM12W-4-4.5V	1938005000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-5.0U	1938280500	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-5.0V	1938280500	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXU	1938000000	B.7	SAIS-5/11-7/(KV)	1921050000	D.10						
SAIL-M8WM12W-4-XXV	1938280000	B.7	SAIS-5/11-7/(KV)								

Order No.	Type	Page
<b>10000000000</b>		
1001180001	SAIT-5S-PARA	K.15
1004310150	SAIT-5-M12/M12-B-COD	B.27
1004320150	SAIL-M8GM8G-4S-0.2-CAN	B.27
1004330150	SAIL-M8GM8G-4S-0.25-CAN	B.16
1005270150	SAIL-M8GM8G-4S-0.3-CAN	B.37
1005460150	SAIL-M8GM8G-4S-0.5-CAN	B.37
1006920000	SAIL-M8GM8G-4S-0.8-CAN	F.39
1006930000	SAIL-M8GM8G-4S-1.0-CAN	F.38
1006940000	SAIL-M8GM8G-4S-1.5-CAN	F.38
1006980000	SAIL-M8GM8G-4S-3.0-CAN	F.36
1007000150	SAIL-M8GM8G-4S-3.5-CAN	B.16
1009370000	SAIL-M8GM8G-4S-5.0-CAN	D.29

Order No.	Type	Page
<b>10100000000</b>		
1010060000	SAIL-M8GM8G-4S-7.0-CAN	D.21
1010070000	SAIL-M8GM8G-4S-10-CAN	D.21
1010080000	SAIL-M8GM8G-4S-10-CAN	D.21
1010090000	SAIL-M8GM8G-4S-10-CAN	D.21
1010840015	SAIL-M12WM12W-3-X-XU	C.74
1010840030	SAIL-M12WM12G-3-X-XU	C.74
1010840050	SAIB-3/7	C.74
1010840100	IE-C5D04RE0100MCSXXX-X	C.74
1010850015	IE-C5D04RE0015MCSMCSE	C.73
1010850030	IE-C5D04RE0030MCSMCSE	C.73
1010850050	IE-C5D04RE0050MCSMCSE	C.73
10111970150	SAIL-M12GM12G-5-1.5T	B.25
1011990150	SAIL-M12GM12W-5-1.5T	B.25

Order No.	Type	Page
<b>10200000000</b>		
1020930150	SAIL-M12GM12W-4-3LW1.5T	B.27
1021280000	SAISW-3/7	D.5
1021290000	SAISW-3/9	D.7
1021310000	SAIBW-3/7	D.5
1021320000	SAIBW-3/9	D.7
1021470000	SAIS-3/7	D.5
1021480000	SAIS-3/9	D.5
1021490000	SAIB-3/7	D.7
1021510000	SAIB-3/9	D.5
1021650150	SAIL-M12G-5-1.5T	B.11
1021660150	SAIL-M12W-5-1.5T	B.11
1021670150	SAIL-M12B-5-1.5T	B.11
1021690150	SAIL-M12BW-5-1.5T	B.11
1021710150	SAIL-M12GM12B-3-1.5T	B.25
1021720150	SAIL-M12GM12W-3-1.5T	B.25
1021730150	SAIL-M12GM12G-4-1.5T	B.25
1021740150	SAIL-M12GM12W-4-1.5T	B.25
1021750150	SAIL-M12G-3-1.5T	B.11
1021760150	SAIL-M12W-3-1.5T	B.11
1021770150	SAIL-M12G-4-1.5T	B.11
1021790150	SAIL-M12W-4-1.5T	B.11
1024050000	PRINTJET PRO 115V	K.15
1024140000	PJ PRO TNAW	K.15
1024310000	IE-AU-M8 PB GW 16DI	F.22
1025220000	SFC 3/12 MC NE WS	K.14
1025230000	SFC 3/12 MC NE GE	K.14
1025240000	SFC 3/12 MC NE RT	K.14
1025250000	SFC 3/12 MC NE BL	K.14
1025260000	SFC 3/21 MC NE WS	K.14
1025270000	SFC 3/21 MC NE GE	K.14
1025290000	SFC 3/21 MC NE RT	K.14
1025300000	SFC 3/21 MC NE BL	K.14
1025310000	SFC 3/30 MC NE WS	K.14
1025320000	SFC 3/30 MC NE GE	K.14
1025330000	SFC 3/30 MC NE RT	K.14
1025340000	SFC 3/30 MC NE BL	K.14
1025560000	SFC 3/12 MC SDR	K.14
1025570000	SFC 3/21 MC SDR	K.14
1025940015	IE-C5D04UG0015MCSXXXX	C.70
1025940030	IE-C5D04UG0030MCSXXXX	C.70
1025940050	IE-C5D04UG0050MCSXXXX	C.70
1025941000	IE-C5D04UG0100MCSXXXX	C.70
1025950015	IE-C5D04UG0055MCSMCSE	C.69
1025950015	IE-C5D04UG0015MCSMCSE	C.69
1025950030	IE-C5D04UG0030MCSMCSE	C.69
1025950050	IE-C5D04UG0050MCSMCSE	C.69
1025951000	IE-C5D04UG0100MCSMCSE	C.69
1026090000	SAI-AS1 FF small	C.61
1027040000	PJ PRO TNK INK K	K.15
1027050000	PJ PRO TNK INK C	K.15
1027060000	PJ PRO TNK INK M	K.15
1027070000	PJ PRO TNK INK Y	K.15
1027110000	PJ PRO TINTSET FARBE	K.15

Order No.	Type	Page
<b>10400000000</b>		
1044470010	IE-C5D04UG0010MCSA20-E	C.70
1044470015	IE-C5D04UG0015MCSA20-E	C.70
1044470030	IE-C5D04UG0030MCSA20-E	C.70
1044470050	IE-C5D04UG0050MCSA20-E	C.70
1044470100	IE-C5D04UG0100MCSA20-E	C.70

Order No.	Type	Page
<b>10500000000</b>		
1051760000	SAI-4S 3P M8 L0L	I.52
1057720000	SAI-6S 3P M8 L SL	I.53
1057740150	SAIL-M12B6-3B-1.5U	B.43
1057750150	SAIL-M12B6-4B-1.5U	B.43
1057760150	SAIL-M12B6-5B-1.5U	B.43
1057770150	SAIL-M12G-3B-1.5U	B.43
1057780150	SAIL-M12G-4B-1.5U	B.43
1057790150	SAIL-M12G-5B-1.5U	B.43
1057800150	SAIL-M12W-3B-1.5U	B.43
1057810150	SAIL-M12W-4B-1.5U	B.43
1057820150	SAIL-M12W-5B-1.5U	B.43
1057830150	SAIL-M12GM12G-3B-1.5U	B.44
1057840150	SAIL-M12GM12G-4B-1.5U	B.44
1057850150	SAIL-M12GM12G-5B-1.5U	B.44
1057870150	SAIL-M12W-3B-1.5U	B.44
1057880150	SAIL-M12W-4B-1.5U	B.44
1057890150	SAIL-M12W-5B-1.5U	B.44
1057900150	SAIL-M12GM12W-3B-1.5U	B.44
1057910150	SAIL-M12GM12W-4B-1.5U	B.44
1057920150	SAIL-M12GM12W-5B-1.5U	B.44
1057940000	SAIT-M7-M12-B-CDD	D.29
1058490150	SAIL-M12GM12G-351.5U	B.28
1058650150	SAIL-M12GM12G-451.5U	B.28
1058651050	SAIL-M12GM12W-351.5U	B.28
1058651050	SAIL-M12GM12W-451.5U	B.28
1058651050	SAIL-M12GM12W-551.5U	B.28
1058510150	SAIL-M12GM12W-45.5U	B.28
1058530150	SAIL-M8GM8G-4S-0.5-CAN	C.6
1058540150	SAIL-M8GM8G-4S-0.8-CAN	C.6
1058550150	SAIL-M8GM8G-4S-1.0-CAN	C.7
1058630000	SAIL-M8GM8G-4S-1.5-CAN	C.66
1059330150	SAIL-M8GM8G-4S-3.0-CAN	C.69
105933030	SAIL-M8GM8G-4S-3.5-CAN	C.69
105933050	SAIL-M8GM8G-4S-5.0-CAN	C.69
105933100	SAIL-M8GM8G-4S-7.0-CAN	C.69
1059340150	SAIL-M8GM8G-4S-10-CAN	C.73
105934030	SAIL-M8GM8G-4S-10-CAN	C.73
105934050	IE-C5D04RE0050MSSMCSE	C.73
105934100	IE-C5D04RE0100MSSMCSE	C.73
1059430000	IE-C5D04UG0015MCAXXX	C.72
105950030	IE-C5D04UG0030MCAXXX	C.72
105970500	IE-C5D04UG0050MCAXXX	C.72
105975000	IE-C5D04UG0100MCAXXX	C.72
1059770015	IE-C5D04UG0150MCSMCMA-E	C.71
10597770030	IE-C5D04UG0300MCSMCMA-E	C.71
10597790050	IE-C5D04UG0500MCSMCMA-E	C.71
1059800015	IE-C5D04UG0100MCACMCA-E	C.71
105980030	IE-C5D04UG0030MCACMCA-E	C.71
105980050	IE-C5D04UG0050MCACMCA-E	C.71
105980070	IE-C5D04UG0100MCACMCA-E	C.71
1059800915	IE-C5D04UG0150MCACMCA-E	C.71
105980300	IE-C5D04UG0300MCACMCA-E	C.71
105980500	IE-C5D04UG0500MCACMCA-E	C.71
105980700	IE-C5D04UG0100MCACMCA-E	C.71
1059809015	IE-C5D04UG0150MCACMCA-E	C.71
105981100	IE-C5D04UG0300MCACMCA-E	C.71
105981300	IE-C5D04UG0500MCACMCA-E	C.71
105981500	IE-C5D04UG0100MCACMCA-E	C.71
105981700	IE-C5D04UG0150MCACMCA-E	C.71
105981900	IE-C5D04UG0300MCACMCA-E	C.71
105982100	IE-C5D04UG0500MCACMCA-E	C.71
105982300	IE-C5D04UG0100MCACMCA-E	C.71
105982500	IE-C5D04UG0150MCACMCA-E	C.71
105982700	IE-C5D04UG0300MCACMCA-E	C.71
105982900	IE-C5D04UG0500MCACMCA-E	C.71
105983100	IE-C5D04UG0100MCACMCA-E	C.71
105983300	IE-C5D04UG0150MCACMCA-E	C.71
105983500	IE-C5D04UG0300MCACMCA-E	C.71
105983700	IE-C5D04UG0500MCACMCA-E	C.71
105983900	IE-C5D04UG0100MCACMCA-E	C.71
105984100	IE-C5D04UG0150MCACMCA-E	C.71
105984300	IE-C5D04UG0300MCACMCA-E	C.71
105984500	IE-C5D04UG0500MCACMCA-E	C.71
105984700	IE-C5D04UG0100MCACMCA-E	C.71
105984900	IE-C5D04UG0150MCACMCA-E	C.71
105985100	IE-C5D04UG0300MCACMCA-E	C.71
105985300	IE-C5D04UG0500MCACMCA-E	C.71
105985500	IE-C5D04UG0100MCACMCA-E	C.71
105985700	IE-C5D04UG0150MCACMCA-E	C.71
105985900	IE-C5D04UG0300MCACMCA-E	C.71
105986100	IE-C5D04UG0500MCACMCA-E	C.71
105986300	IE-C5D04UG0100MCACMCA-E	C.71
105986500	IE-C5D04UG0150MCACMCA-E	C.71
105986700	IE-C5D04UG0300MCACMCA-E	C.71
105986900	IE-C5D04UG0500MCACMCA-E	C.71
105987100	IE-C5D04UG0100MCACMCA-E	C.71
105987300	IE-C5D04UG0150MCACMCA-E	C.71
105987500	IE-C5D04UG0300MCACMCA-E	C.71
105987700	IE-C5D04UG0500MCACMCA-E	C.71
105987900	IE-C5D04UG0100MCACMCA-E	C.71
105988100	IE-C5D04UG0150MCACMCA-E	C.71
105988300	IE-C5D04UG0300MCACMCA-E	C.71
105988500	IE-C5D04UG0500MCACMCA-E	C.71
105988700	IE-C5D04UG0100MCACMCA-E	C.71
105988900	IE-C5D04UG0150MCACMCA-E	C.71
105989100	IE-C5D04UG0300MCACMCA-E	C.71
105989300	IE-C5D04UG0500MCACMCA-E	C.71
105989500	IE-C5D04UG0100MCACMCA-E	C.71
105989700	IE-C5D04UG0150MCACMCA-E	C.71
105989900	IE-C5D04UG0300MCACMCA-E	C.71
105990100	IE-C5D04UG0500MCACMCA-E	C.71
105990300	IE-C5D04UG0100MCACMCA-E	C.71
105990500	IE-C5D04UG0150MCACMCA-E	C.71
105990700	IE-C5D04UG0300MCACMCA-E	C.71
105990900	IE-C5D04UG0500MCACMCA-E	C.71
105991100	IE-C5D04UG0100MCACMCA-E	C.71
105991300	IE-C5D04UG0150MCACMCA-E	C.71
105991500	IE-C5D04UG0300MCACMCA-E	C.71
105991700	IE-C5D04UG0500MCACMCA-E	C.71
105991900	IE-C5D04UG0100MCACMCA-E	C.71
105992100	IE-C5D04UG0150MCACMCA-E	C.71
105992300	IE-C5D04UG0300MCACMCA-E	C.71
105992500	IE-C5D04UG0500MCACMCA-E	C.71
105992700	IE-C5D04UG0100MCACMCA-E	C.71
105992900	IE-C5D04UG0150MCACMCA-E	C.71
105993100	IE-C5D04UG0300MCACMCA-E	C.71
105993300	IE-C5D04UG0500MCACMCA-E	C.71
105993500	IE-C5D04UG0100MCACMCA-E	C.71
105993700	IE-C5D04UG0150MCACMCA-E	C.71
105993900	IE-C5D04UG0300MCACMCA-E	C.71
105994100	IE-C5D04UG0500MCACMCA-E	C.71
105994300	IE-C5D04UG0100MCACMCA-E	C.71
105994500	IE-C5D04UG0150MCACMCA-E	C.71
105994700	IE-C5D04UG0300MCACMCA-E	C.71
105994900	IE-C5D04UG0500MCACMCA-E	C.71
105995100	IE-C5D04UG0100MCACMCA-E	C.71
105995300	IE-C5D04UG0150M	

Order No.	Type	Page	Order No.	Type	Page	Order No.	Type	Page	Order No.	Type	Page
<b>1190000000</b>			1224680000	SAI-M23-BE-17-10MMG	J.22	1292010000	SAI-B/5-11/7/8"	E.7	1635010000	WS 10/5 MC BEDRUCKT	K.16
1191020000	SAI-B/5-6S M12 5P A-COD	C.32	1224690000	SAI-M23-BE-17-17MMG	J.22	1292020000	SAI-BW/5-9/7/8"	E.6	<b>1680000000</b>		
1191020000	SAI-B/5-6S M12 5P A-COD	D.15	1224710000	SAI-M23-SE-17-10MMG	J.22	1292030000	SAI-BW/5/11/7/8"	E.7	1689470001	VT SF 5/21 NEUTRAL WS VO	C.69
1191030000	SAISM-5/6S M12 5P A-COD	D.5	1224720000	SAI-M23-SE-17-17MMG	J.22	1292040000	SAISW/4/11/7/8"	E.7	<b>1700000000</b>		
<b>1200000000</b>			1224730000	SAI-M23-SE-9-F-G	J.21	1292050000	SAI-B/4/11/7/8"	E.7	1701230000	SAI-4-M 5P M12	L.7
1201210200	SAIL-M8GRJ45-A52.0UIE	C.68	1224740000	SAI-M23-BE-9-F-G	J.21	1292070000	SAI-BW/4/11/7/8"	E.7	1701231000	SAI-4-M 5P M12 UT	L.7
1201210500	SAIL-M8GRJ45-A55.0UIE	C.68	1224750000	SAI-M23-BE-9-10MMG	J.21	1292080150	SAIL/7/8-G3-1.5U	E.11	1701232000	SAI-4-MH-5P M12	I.36
1201210750	SAIL-M8GRJ45-A57.5UIE	C.68	1224760000	SAI-M23-BE-9-17MMG	J.21	129210150	SAIL/7/8-BG3-1.5U	E.11	1701233000	SAI-4-MHD-5P M12	I.37
1201211100	SAIL-M8GRJ45-A51.0UIE	C.68	1224770000	SAI-M23-SE-9-10MMG	J.21	129211050	SAIL/7/8-BW3-1.5U	E.11	1701240000	SAI-6-M 5P M12	L.7
1203840000	SAI-M23 CRIMPING TOOL 1	K.12	1224780000	SAI-M23-SE-9-17MMG	J.21	129212050	SAIL/7/8-BW4-1.5U	E.11	1701241000	SAI-6-M 5P M12 UT	L.7
1203960000	SAI-M23 CRIMPING TOOL 2	K.13	1232620000	SAI-PB-2X0.24-PUR	C.8	1292140150	SAIL/7/8-BW4-1.5U	E.11	1701242000	SAI-6-MH-5P M12	I.36
<b>1210000000</b>			1232630000	SAIHP-B-PA-2X1.0.PVC-BL	C.30	1292150150	SAIL/7/8-BG5-1.5U	E.11	1701243000	SAI-6-MHD-5P M12	I.37
1216820020	SAIL-M8GM8G-4S-0.2 CAN	C.64	1232640000	SAIHP-B-PA-2X1.0.PVC-SW	C.30	1292180150	SAIL/7/8-W5-1.5U	E.11	1701250000	SAI-8-M 5P M12	L.7
1216820025	SAIL-M8GM8G-4S-0.25 CAN	C.64	1235340000	SAI-AU ET SET M12 A COD	G.7	1292190150	SAIL/7/8-BG5-1.5U	E.11	1701251000	SAI-8-M 5P M12 UT	L.7
1216820030	SAIL-M8GM8G-4S-0.3 CAN	C.64	1246490000	SAI GHDE EA 8M12	G.6	1292200150	SAIL/7/8-BV5-1.5U	E.11	1705920000	SAI-4-M 4P M12	L.7
1216820050	SAIL-M8GM8G-4S-0.5 CAN	C.64	1246510000	SAI GHDE EA 8M12 SIBL	G.6	1292330000	SAIE/7/8-S-3.0-2U-PG11	E.9	1705921000	SAI-4-M 4P M12 UT	L.7
1216820080	SAIL-M8GM8G-4S-0.8 CAN	C.64	1246520000	SAI GHDE EA 16M8 O.SIBL	G.6	1292340000	SAIE/7/8-S-3.0-2U-PG13.5	E.10	1705922000	SAI-4-MH-4P M12	I.36
1216821000	SAIL-M8GM8G-4S-1.0 CAN	C.64	1246530000	SAI RA 54 KU	G.6	1292390000	SAIE/7/8-B-3.0-2U-H	E.8	1705923000	SAI-4-MHD-4P M12	I.37
1216821050	SAIL-M8GM8G-4S-1.5 CAN	C.64	1246540000	SAI GHDE 3M12 1M8 SAI	G.8	1292400000	SAIE/7/8-S-4.0-2U-PG11	E.9	1705930000	SAI-6-M 4P M12	L.7
1216820300	SAIL-M8GM8G-4S-3.0 CAN	C.64	1246550000	SAI GHDE 3M12 1S2B	G.8	1292410000	SAIE/7/8-S-4.0-2U-PG13.5	E.10	1705931000	SAI-6-M 4P M12 UT	L.7
1216820350	SAIL-M8GM8G-4S-3.5 CAN	C.64	1246560000	SAI GHDE 4M12 1S3B	G.8	1292420000	SAIE/7/8-S-4.0-2U-H	E.8	1705932000	SAI-6-MH-4P M12	I.36
1216820500	SAIL-M8GM8G-4S-5.0 CAN	C.64	1246570000	SAI GHDE 4M12 2S2B	G.8	1292430000	SAIE/7/8-B-4.0-2U-PG11	E.9	1705933000	SAI-6-MHD-4P M12	I.37
1216820700	SAIL-M8GM8G-4S-7.0 CAN	C.64	1246580000	SAI GHDE 4M12 2X1S1B	G.8	1292440000	SAIE/7/8-B-4.0-2U-PG13.5	E.10	1705940000	SAI-8-M 4P M12	L.7
1216821000	SAIL-M8GM8G-4S-10 CAN	C.64	1246590000	SAI GHDE 4M12 3S1B	G.8	1292450000	SAIE/7/8-B-4.0-2U-H	E.8	1705941000	SAI-8-M 4P M12 UT	L.7
<b>1220000000</b>			1246610000	SAI GHDE 3M12 1PG9	G.13	1292470000	SAIE/7/8-S-5.0-2P611	E.9	1705942000	SAI-8-MH-4P M12	I.36
1246660000	SAI RA 30 SB KU	G.9	1246660000	SAI RA 30 SB KU	G.9	1292480000	SAIE/7/8-S-5.0-2U-PG13.5	E.10	1705943000	SAI-8-MHD-4P M12	I.37
1246670000	SAI GHDE 30 SB LA M12	G.10	1246680000	SAI GHDE 30 SB LA SIBL	G.10	1292490000	SAIE/7/8-S-5.0-2U-H	E.8	<b>1710000000</b>		
1246690000	SAI GHDE 30 SB LA M8	G.10	1246700000	SAI GHDE 30 SB LA M8	G.10	1292500000	SAIE/7/8-B-5.0-2U-PG11	E.9	17118411687	TM-12 NEUTRAL GE	C.69
1246710000	SAI BP 30 SB LA	G.10	1246720000	SAI RA 30 SB LA	G.10	1292510000	SAIE/7/8-B-5.0-2U-PG13.5	E.10	17118431044	TM-14 NEUTRAL WS	K.15
1246730000	SAI RA 30 SB LA	G.10	1246740000	SAI RA 30 SB LA	G.10	1292520000	SAIE/7/8-B-5.0-2U-H	E.8	17118431687	TM-18 NEUTRAL GE	C.69
1246810000	SAI GHDE 30 S KU M12	G.9	1246820000	SAI GHDE 30 S KU SI	G.9	12926730000	SAI-M23-BE-12-G	J.14	1719840000	TM 4/12 HF/HB	C.69
1246830000	SAI GHDE 30 S KU M8	G.9	1246840000	SAI GHDE 30 S KU M8	G.9	1299390000	SAI-M23-GS-L11/17	J.12	1719850000	TM 4/18 HF/HB	C.69
1246860000	SAI-M23-SE-6-17MM	J.20	<b>1250000000</b>			<b>1310000000</b>			<b>1720000000</b>		
1246870000	SAI-M23-SE-7-F	J.20	1258930000	SAIBM-8/9S-M12	D.14	1311690150	SAIL-M12W-12-1.5U	B.14	1724750000	SAI-4/6-8/MH BL3.5	L.7
1246880000	SAI-M23-SE-7-F	J.20	1258940000	SAISM-8/9S-M12	D.14	1311700150	SAIL-M12G-12-1.5U	B.14	1724750500	SAI-4/6-8/MH BL3.5 SV	L.7
1246900000	SAI-M23-SE-7-3.5MM	J.20	1259010150	SAIL-M16BW-12-1.5U	B.40	1312970000	SAIE-M12B-5LP	D.37	1724752000	SAI-4/6-8/MH-MH BL 3.5	I.36
1246910000	SAI-M23-SE-7-17MM	J.20	<b>1260000000</b>			1312980000	SAIE-M12S-5LP	D.37	1724753000	SAI-4/6-8/MH-MHD BL 3.5	I.37
1246920000	SAI-M23-SE-7-17MM	J.20	1265920000	SAI-F-4P M12 L 5M	I.10	<b>1320000000</b>			1724754000	SAI-4/6-8/MH-MM BL 3.5	I.35
1246930000	SAI-M23-SE-12-10MM	J.21	1265930000	SAI-F-4P M12 L 10M	I.10	1321700000	SAIS-5/9-7/8"	E.6	<b>1730000000</b>		
1246940000	SAI-M23-SE-12-16.5MM	J.21	1265940000	SAI-S-12 4P M12 L	I.11	1324010000	IE-PCB-M12X-S180	C.79	1730560001	VT SF 6/21 NEUTRAL WS VO	C.69
1246950000	SAI-M23-SE-12-17.5MM	J.21	1267330000	SAI-S-8 4P M12 L	I.11	1324020000	IE-PS-M12X-P-FH	C.79	1736230000	GWDR M16NP	C.81
1246960000	SAI-M23-SE-12-17.5MM	J.21	1267900000	SAIE-M16S-5HW	D.39	1326720000	SAIE-M16B-4L	D.39	1737070000	VP M16-EXE SW	C.81
1246970000	SAI-M23-SE-12-17MM	J.21	1271590015	SAIL-VSB-M8-3.0-1.5U	B.54	1326730000	SAIE-M16B-5L	D.39	1737120000	VG M16-EXE MS	C.81
1246980000	SAI-M23-SE-12-17MM	J.21	1275470150	SAIL-M12B-8W-81.5U	B.15	1326740000	SAIE-M16B-7L	D.39	<b>1740000000</b>		
1246990000	SAI-M23-SE-12-17F	J.21	1275750000	SABW/5-8/5-M12 5P A-ZF	D.5	1327170000	SAIS-12/8-1.5U	B.14	1740191000	SAI-8-M 5P M12 OL UT	L.7
1247000000	SAI-M23-SE-12-17.5MM	J.21	1276060150	SAIL-M12W-8S1.5U	B.15	1327620000	SAIE-M16B-8L	D.39	1747320001	SFC 1/12 NEUTRAL WS	K.14
1247010000	SAI-M23-SE-16-17MM	J.21	1276450150	SAIL-VSB-180-M8C-3-1.5U	B.54	1327630000	SAIE-M16B-8L	D.39	1747320002	SFC 1/12 NEUTRAL BL	K.14
1247020000	SAI-M23-SE-16-17MM	J.21	1279410150	SAIL-M12G-8-1.5U	B.14	1327640000	SAIE-M16B-8L	D.39	1747320003	SFC 1/12 NEUTRAL RT	K.14
1247030000	SAI-M23-SE-16-17MM	J.21	1279420150	SAIL-M12W-8-1.5U	B.14	1327650000	SAIE-M16B-8L	D.39	1747320004	SFC 1/12 NEUTRAL GE	K.14
1247040000	SAI-M23-SE-16-17MM	J.21	1279430150	SAIL-M12G-8S1.5U	B.15	<b>1340000000</b>			<b>1750000000</b>		
1247050000	SAI-M23-SE-16-17MM	J.21	1279440150	SAIL-M12G-12-8-1.5U	B.14	1341230050	SAIE-M12S-5S0.5U HW	D.38	1752080000	SAI-4/6-8/MH BLZF3.5	L.7
1247060000	SAI-M23-SE-16-17MM	J.21	1279450150	SAIL-M12G-12W-8-1.5U	B.14	1341240050	SAIE-M12S-8S0.5U HW	D.38	1752080500	SAI-4/6-8/MH BLZF3.5 SV	L.7
1247070000	SAI-M23-SE-16-17MM	J.21	1279460150	SAIL-M12G-12W-8S1.5U	B.15	1344720000	SAIH-SLL-3X1.0-16X0.5	B.57	1758320001	SFC 2/12 NEUTRAL WS	K.14
1247080000	SAI-M23-SE-16-17MM	J.21	1279470150	SAIL-M12G-12W-8S1.5U	B.15	1345520000	SAIH-SLL-3X0.34-UQE	B.56	1758320002	SFC 2/12 NEUTRAL BL	K.14
1247090000	SAI-M23-SE-16-17MM	J.21	1279480050	SAIE-M12B-PB-0.5U HW	C.10	1345530000	SAIH-SLL-4X0.34-UQE	B.56	1758320003	SFC 2/12 NEUTRAL RT	K.14
1247100000	SAI-M23-SE-16-17MM	J.21	1279480200	SAIE-M12B-PB-2.0U HW	C.10	1345540000	SAIH-SLL-5X0.34-UQE	B.56	1758320004	SFC 2/12 NEUTRAL GE	K.14
1247110000	SAI-M23-SE-19-3.5MM	J.23	1279480300	SAIE-M12B-PB-2.0U HW	C.10	<b>1350000000</b>			<b>1760000000</b>		
1247120000	SAI-M23-SE-19-10MM	J.23	1279490050	SAI-M8GM8G-4S-10-CAN	C.10	1353700000	SAIS-4/11-1.5	D.9	1760040000	SAI-4-M 3P IDC	I.28
1247130000	SAI-M23-SE-19-10MM-PE	J.23	1279490100	SAI-M12W-12W-3-X-XU	C.10	1353740000	SAIS-5/11-1.5	D.9	1760041000	SAI-4-M 3P IDC UT	I.28
1247140000	SAI-M23-SE-19-3.5MM-PE	J.23	1279490200	SAI-M12W-12G-3-X-XU	C.10	1353750000	SAIB-5/11-1.5	D.9	1760050000	SAI-6-M 3P IDC	I.28
1247150000	SAI-M23-SE-19-17MM	J.23	1279490300	SAI-M8GM8G-4S-10-CAN	C.10	1353770000	SAIE-M12S-4.0-5U P9 1.5	D.34	1760051000	SAI-6-M 3P IDC UT	I.28
1247160000	SAI-M23-SE-19-17MM	J.23	1279490400	SAI-M12W-12G-4-X-XV	E.6	1353780000	SAIE-M12B-4.0-5U P9 1.5	D.34	1760060000	SAI-8-M 3P IDC	I.28
1247170000	SAI-M23-SE-19-17MM	J.23	1279490500	SAI-M12W-12G-5-X-XV	E.7	1353790000	SAIE-M12B-4.0-5U P9 1.5	D.34	1760061000	SAI-8-M 3P IDC UT	I.28
1247180000	SAI-M23-SE-19-17MM	J.23	1279490600	SAI-M12W-12G-5-X-XV	E.7	1353730000	SAIH-SLL-4X0.34 SI PUR	B.56	1766660000	SAI-4-F 4P IDC PUR 5M	I.29
1247190000	SAI-M23-SE-19-17MM	J.23	1279490700	SAI-M12W-12G-5-X-XV	E.7	1353740000	SAIH-SLL-5X0.34 SI PUR	B.56	1766670000	SAI-4-F 3P IDC PUR 10M	I.29
1247200000	SAI-M23-SE-19-17MM	J.23	1279490800	SAI-M12W-12G-5-X-XV	E.7	<b>1360000000</b>			1766680000	SAI-6-F 4P IDC PUR 5M	I.29

Order No.	Type	Page	Order No.	Type	Page	Order No.	Type	Page	Order No.	Type	Page
1766810000	SAI-SA-4-DC	I.26	1795900000	SAI-8-M16 3P M8	I.51	1824570000	SAIL-M8GM8G-3-X.XU	B.4	1856140000	SAI-M8B-4-0.5U-FP-M8	D.36
1767880000	SAI-8-M 5P M12 ZF III	I.7	1798480000	TM 203/18 VO	K.15	1824570150	SAIL-M8GM8G-3-1.5U	B.32	1857550000	SAIL-M8W-3-X.XU	B.4
<b>17700000000</b>											
1777730000	VP M16-MS65	C.81	1800000000	SAI-4-M 5P M12 0L	I.7	1824570300	SAIL-M8GM8G-3.3U	B.4	1857550150	SAIL-M8W-3-1.5U	B.19
1779080001	SFC 1/21 NEUTRAL WS	K.14	1802750000	SAI-SK M12 MT	D.31	1824570500	SAIL-M8GM8G-3-5.0U	B.4	1857550300	SAIL-M8W-3-3.0U	B.4
1779080002	SFC 1/21 NEUTRAL BL	K.14	1802760000	SAI-SK M8	C.59	1824571000	SAIL-M8GM8G-3-10U	B.4	1857550500	SAIL-M8W-3-5.0U	B.4
1779080003	SFC 1/21 NEUTRAL RT	K.14	1802760000	SAI-SK M8	D.31	1824580000	SAIL-M8GM8W-3-X.XU	B.5	1857551000	SAIL-M8W-3-10U	B.4
1779080004	SFC 1/21 NEUTRAL GE	K.14	1802760000	SAI-SK M8	F.10	1824580150	SAIL-M8GM8W-3-1.5U	B.5	1857560000	SAIL-M8W-4-X.XU	B.4
<b>17800000000</b>											
1781060000	SAI-8-M 5P M12 NPN	I.7	1803860000	SAIS-M8-3P	D.20	1824590000	SAIL-M8G-3-3.0U	B.4	1857560150	SAIL-M8W-4-1.5U	B.19
1781520000	SAI-SK Stecker M12	D.31	1803870000	SAIB-M8-3P	D.20	1824590500	SAIL-M8G-3-5.0U	B.4	1857560300	SAIL-M8W-4-5.0U	B.4
1781520000	SAI-SK Stecker M12	F.10	1803880000	SAI-SM8-4P	D.20	1824591000	SAIL-M8G-3-10U	B.4	1857561000	SAIL-M8W-4-10U	B.4
1781540001	SAI-B-4-DC-M12 small	D.24	1803910000	SAIBW-M-4/8 M12	C.32	1826680000	SAI-Y-5S-M12/M12	D.28	1857660000	SAIL-M8GM8W-4-X.XU	B.5
1781550001	SAI-S-4-DC M12 small	D.24	1803910000	SAIBW-M-4/8 M12	D.15	1827010150	SAIL-M8BWR-3-1.5U	B.20	1857670000	SAIL-M8WM8W-3-X.XU	B.5
1782740000	SAI-8-MMH 5P M12 ZF	I.35	1803920000	SAIBW-M-5/M 8 M12	C.32	1827020150	SAIL-M8GR-3-1.5U	B.20	1857670150	SAIL-M8WM8W-3-1.5U	B.32
1782750000	SAI-4/6/8 MH MH BLZF3,5	I.36	1803920000	SAIBW-M-5/M 8 M12	D.15	1828610000	SAI-F-4P M8 L 10M	I.54	1857670300	SAIL-M8WM8W-3-3.0U	B.5
1782760000	SAI-8-MH-5P M12 ZF III	I.36	1803930000	SAISW-M-4/8 M12	C.32	1828620000	SAI-F-4P M8 L 5M	I.54	1857670500	SAIL-M8WM8W-3-5.0U	B.5
1783410000	SAI-Y-5S B2-4 2M12	D.28	1803930000	SAISW-M-4/8 M12	D.15	1828630000	SAI-F-2P M8 L 10M	I.54	1857671000	SAIL-M8WM8W-3-10U	B.5
1783420000	SAI-Y-4/4-2/4 M12/8	D.28	1803940000	SAISW-M-5/M 8 M12	C.32	1828640000	SAI-F-2P M8 L 5M	I.54	1857680000	SAIL-M8WM8W-4-X.XU	B.5
1783430000	SAI-Y-5S PARA 2M12	D.28	1803940000	SAISW-M-5/M 8 M12	D.15	1828650000	SAI-F-10P M8 L 10M	I.54	1857680150	SAIL-M8WM8W-4-1.5U	B.32
1783430000	SAI-Y-5S PARA 2M12	H.7	1804580000	SAI-F-4M 5P PUR 10M	I.44	1828660000	SAI-F-3P M8 L 10M	I.54	1857680300	SAIL-M8WM8W-4-3.0U	B.5
1783460000	SAI-4/6/8 MH LEER	I.7	1804590000	SAI-F-8M 5P PUR 5M	I.44	1828670000	SAI-F-3P M8 L 5M	I.54	1857680500	SAIL-M8WM8W-4-5.0U	B.5
1783490000	SAI-8-MM 5P M12	I.35	1804600000	SAI-F-4M 5P PUR 5M	I.44	1828680000	SAI-F-3P M8 L 5M	I.54	1857681000	SAIL-M8WM8W-4-10U	B.5
1783491000	SAI-8-MM 5P M12 UT	I.35	1805660000	SAI-Y-4S M8-M8	D.28	1828690000	SAI-F-5P M8 L 10M	I.54	1857690150	SAIL-VSA-M12W-1.5U	B.47
1783500000	SAI-4-MM 5P M12	I.35	1805720000	SFC 1/30 NEUTRAL BL	K.14	1828700000	SAI-F-6P M8 L 5M	I.54	1857700150	SAIL-VSD-M12W-1.5U	B.48
1783510000	SAI-8-MMS 5P M12	I.35	1805730000	SFC 1/30 NEUTRAL GE	K.14	1828710000	SAI-F-4P M8 L 10M	I.54	1857710150	SAIL-VSC-M12W-1.5U	B.49
1783520000	SAI-4-MMS 5P M12	I.35	1805740000	SFC 1/30 NEUTRAL RT	K.14	1828720000	SAI-F-5P M8 L 5M	I.54	1857730150	SAIL-VCD-M12W-1.5U	B.49
1783530000	SAI-8-MMS 4P M12	I.35	1805760000	SFC 1/30 NEUTRAL WS	K.14	1828740000	SAI-F-3P M8 L	I.52	1859110000	SAI-4SH 4P FC	I.21
1783540000	SAI-4-MMS 4P M12	I.35	1805770000	SFC 2/21 NEUTRAL BL	K.14	1828750000	SAI-F-2P M8 L 10M	I.54	1859110000	SAI-4SH 4P FC	J.32
1784030001	SAI-B-3-DC M8 small	D.26	1805780000	SFC 2/21 NEUTRAL GE	K.14	1828770000	SAI-F-3P M8 L 5M	I.54	1859120000	SAI-8SH 4P FC	I.21
1784040001	SAI-S-3-DC M8 small	D.26	1805790000	SFC 2/21 NEUTRAL RT	K.14	1828780000	SAI-F-3P M8 L 5M	I.54	1859130000	SAI-4SH 5P FC	I.21
1784050001	SAI-B-4-DC M8 small	D.26	1805810000	SFC 2/21 NEUTRAL WS	K.14	1828790000	SAI-F-3P M8 L 5M	I.54	1859130000	SAI-4SH 5P FC	J.32
1784060001	SAI-S-4-DC M8 small	D.26	1805820000	SFC 2/30 NEUTRAL BL	K.14	1828800000	SAI-F-3P M8 L 5M	I.54	1859140000	SAI-8SH 5P FC	I.21
1784500000	SAI-B-8 F 20M 0.5/1.0U	I.8	1805830000	SFC 2/30 NEUTRAL GE	K.14	1828810000	SAI-F-3P M8 L 5M	I.54	1859140000	SAI-8SH 5P FC	J.32
1784510000	SAI-B-8 F 20M 0.5/1.0U	I.8	1805850000	SFC 2/30 NEUTRAL RT	K.14	1828820000	SAI-F-3P M8 L 5M	I.54	1859150000	SAI-4SH 4P FC	I.21
1784570000	SAI-8-F 4P M8 PUR 10M	I.50	1805870000	SFC 2/30 NEUTRAL WS	K.14	1828830000	SAI-F-3P M8 L	I.50	1859160000	SAI-4SH 4P FC	J.32
1784580000	SAI-8-F 4P M8 PUR 5M	I.50	1806010000	SAI-4-M 5P M12 1:1	I.38	1828840000	SAI-F-3P M8 L	I.50	1859170000	SAI-4SH 4P FC	I.21
1784600000	SAI-4-F 4P M8 PUR 5M	I.50	1807230000	SAIB-4/9	D.7	1828850000	SAI-F-3P M8 L	I.50	1859180000	SAI-4SH 4P FC	J.32
1784610000	SAI-8-F 3P M8 PUR 10M	I.50	1807240000	SAIBW-4/9	D.7	1828860000	SAI-F-3P M8 L	I.50	1859190000	SAI-4SH 4P FC	I.21
1784620000	SAI-8-F 3P M8 PUR 5M	I.50	1807250000	SAIB-5/9	D.8	1828870000	SAI-F-3P M8 L	I.50	1859191000	SAI-4SH 4P FC	J.32
1784630000	SAI-4-F 3P M8 PUR 10M	I.50	1807330000	SAIBW-5/9	D.8	1828880000	SAI-F-3P M8 L	I.50	1859192000	SAI-4SH 4P FC	I.21
1784640000	SAI-4-F 3P M8 PUR 5M	I.50	1807340000	SAIS-4/9	D.7	1828890000	SAI-F-3P M8 L	I.50	1859193000	SAI-4SH 4P FC	J.32
1784650000	SAI-B-8 M23 4P M6	I.51	1807350000	SAIS-5/9	D.8	1828900000	SAI-F-3P M8 L	I.50	1859194000	SAI-4SH 4P FC	I.21
1784650000	SAI-B-8 M23 4P M8	J.33	1807360000	SAISW-4/9	D.7	1828910000	SAI-F-3P M8 L	I.50	1859195000	SAI-4SH 4P FC	J.32
1784660000	SAI-A-23 4P M8	I.51	1807370000	SAISW-5/9	D.8	1828920000	SAI-F-3P M8 L	I.50	1859196000	SAI-4SH 4P FC	I.21
1784660000	SAI-A-23 4P M8	J.33	1807640000	SAI-4-M 8P M12	I.39	1828930000	SAI-F-4S 3P M5	I.58	1859197000	SAI-4SH 4P FC	J.32
1784670000	SAI-B-8 3P M8	I.50	1807641000	SAI-4-M 8P M12 UT	I.39	1828940000	SAI-F-4S 3P M5	I.58	1859198000	SAI-4SH 4P FC	I.21
1784680000	SAI-A-4-M 3P M8	I.50	1808830000	SAISW-4/9-7/8"	E.6	1828950000	SAI-F-4S 3P M5	I.58	1859199000	SAI-4SH 4P FC	J.32
1784690000	SAI-B-8 4P M8	I.50	1808840000	SAIS-4/9-7/8"	E.6	1828960000	SAI-F-4S 3P M5	I.58	1859200000	SAI-4SH 4P FC	I.21
1784700000	SAI-A-4-M 4P M8	I.50	1808970150	SAIL-M12BW4S1.5U	B.17	1828970000	SAI-F-4S 3P M5	I.58	1859201000	SAI-4SH 4P FC	J.32
1784740000	SAIS-5/8S M12 5P A-COD	C.32	181012170000	SAI-B-8 4P M12 F10	I.43	1829000000	SAI-F-4S 3P M5	I.58	1859202000	SAI-4SH 4P FC	I.21
1784740000	SAIB-M-4/8S M12 4P ZF	D.5	1812474000	SAIB-4/9-7/8"	E.6	1829010000	SAI-F-4S 3P M5	I.58	1859203000	SAI-4SH 4P FC	J.32
1784750000	SAIB-M-5/8S M12 5P A-COD	C.32	1812480000	SAIB-4/9-7/8"	E.6	1829020000	SAI-F-4S 3P M5	I.58	1859204000	SAI-4SH 4P FC	I.21
1784760000	SAIEND CAN-12 5P A-COD	F.14	1812540150	SAIL-M12BG-4S1.5U	B.17	1829030000	SAI-F-4S 3P M5	I.58	1859205000	SAI-4SH 4P FC	J.32
1784770000	SAIEND PB M12 5P B-COD	F.10	1812550150	SAIL-ZW-M12BG/2A-1.5U	B.38	1829040000	SAI-F-4S 3P M5	I.58	1859206000	SAI-4SH 4P FC	I.21
1784780000	SAIB-M 5/8S M12 5P B-COD	C.12	1812870000	SAISW-4/4C M12	D.24	1829050000	SAI-F-4S 3P M5	I.58	1859207000	SAI-4SH 4P FC	J.32
1784780000	SAIB-M 5/8S M12 5P B-COD	D.16	1812890000	SAIBW-4/4C M12	D.24	1829060000	SAI-F-4S 3P M5	I.58	1859208000	SAI-4SH 4P FC	I.21
1784790000	SAISM 5/8S M12 5P B-COD	C.12	1813130000	SAF 0/12 NEUTRAL WS	K.14	1829070000	SAI-F-4S 3P M5	I.58	1859209000	SAI-4SH 4P FC	J.32
1785100100	FBC PA M12 M-FM 1M	C.29	1813150000	SFC 0/12 NEUTRAL RT	K.14	1829080000	SAI-F-4S 3P M5	I.58	1859210000	SAI-4SH 4P FC	I.21
1785110100	FBC PA M12 FM 1M	C.28	1813160000	SFC 0/12 NEUTRAL GE	K.14	1829090000	SAI-F-4S 3P M5	I.58	1859211000	SAI-4SH 4P FC	J.32
1785120100	FBC PA M12 M 1M	C.28	1813170000	SFC 0/12 NEUTRAL BL	K.14	1829100000	SAI-F-4S 3P M5	I.58	1859212000	SAI-4SH 4P FC	I.21
1785130100	FBC EX PA M12 M-FM 1M	C.29	1813190000	SFC 0/21 NEUTRAL WS	K.14	1829110000	SAI-F-4S 3P M5	I.58	1859213000	SAI-4SH 4P FC	J.32
1785140100	FBC EX PA M12 FM 1M	C.28	1813200000	SFC 0/21 NEUTRAL RT	K.14	1829120000	SAI-F-4S 3P M5	I.58	1859214000	SAI-4SH 4P FC	I.21
1785150100	FBC EX PA M12 M 1M	C.28	1813210000	SFC 0/21 NEUTRAL GE	K.14	1829130000	SAI-F-4S 3P M5	I.58	1859215000	SAI-4SH 4P FC	J.32
1785190000	SAI-8-MF 5P PUR10M M12	I.44	1813220000	SFC 0/21 NEUTRAL BL	K.14	1829140000	SAI-F-4S 3P M5	I.58	1859216000	SAI-4SH 4P FC	I.21
1785194000	SAI-8-MF 4P PUR14M	I.44	1813240000	SFC 0/30 NEUTRAL GE	K.14	1829150000	SAI-F-4P M5 FC	I.58	1859217000	SAI-4SH 4P FC	J.32
1785195000	SAI-8-MF 4P PUR28M	I.44	1813260000	SFC 0/30 NEUTRAL BL	K.14	1829160000	SAI-F-4P M5 FC	I.58	1859218000	SAI-4SH 4P FC	I.21
1785195200	SAI-8-MF 4P PUR34M	I.44	1813270000	SFC 0/30 NEUTRAL GE	K.14	1829170000	SAI-F-4P M5 FC	I.58	1859219000	SAI-4SH 4P FC	J.32
1785196000	SAI-8-MF 4P PUR4										

Order No.	Type	Page	Order No.	Type	Page	Order No.	Type	Page	Order No.	Type	Page
1873180000	SAIB-VSB-3P/24/9/LD	D.40	1906290100	SAIS-M23-12P-AN-1.0M	J.30	1912130000	ESG 8/13.5/43.3 SAI AU	F.18	1925380500	SAIL-M12WM12W-3-5.0V	B.7
1873190000	SAIB-VSD-3P/250/9-0B	D.40	1906300000	SAIL-M12GM12G-4-XU	B.6	1912130000	ESG 8/13.5/43.3 SAI AU	F.23	1925381000	SAIL-M12WM12W-3-10V	B.7
1873200000	SAIB-VSC-3P/250/7-0B	D.40	1906300030	SAIL-M12GM12G-4-0.3U	H.7	1912130000	ESG 8/13.5/43.3 SAI AU	F.25	1925390000	SAIL-M12WM12W-4-X XV	B.7
1873210000	SAIB-VSC-4P/250/7-0B	D.40	1906300050	SAIL-M12GM12G-4-0.5U	H.7	1912130000	ESG 8/13.5/43.3 SAI AU	F.27	1925390150	SAIL-M12WM12W-4-1.5V	B.25
1873220000	SAIB-VSCD-3P/250/7-0B	D.40	1906300150	SAIL-M12GM12G-4-1.5U	B.28	1912130000	ESG 8/13.5/43.3 SAI AU	F.37	1925390150	SAIL-M12WM12W-4-1.5V	B.7
1873230000	SAIB-VSCD-4P/250/7-0B	D.40	1906300150	SAIL-M12GM12G-4-1.5U	B.6	1912130000	ESG 8/13.5/43.3 SAI AU	K.16	1925390300	SAIL-M12WM12W-4-3.0V	B.7
1873240150	SAIL-M5W-4P-1.5U	B.23	1906300300	SAIL-M12GM12G-4-3.0U	B.6	1915220000	SAI JP 4P LG	H.8	1925390500	SAIL-M12WM12W-4-5.0V	B.7
1873250150	SAIL-M5BG-4P-1.5U	B.23	1906300500	SAIL-M12GM12G-4-5.0U	B.6	1916700150	SAIL-VSCD-M8G-3-1.5U	B.55	1925391000	SAIL-M12WM12W-4-10V	B.7
1873260150	SAIL-M5BW-3P-1.5U	B.23	1906301000	SAIL-M12GM12G-4-10U	B.6	1917400000	SAI-TS35 MF	I.45	1925400000	SAIL-M12WM12W-5-XV	B.7
1873270150	SAIL-M5BW-4P-1.5U	B.23	1906310000	SAIL-M12WM12W-4-XU	B.7	1918520000	SAI JP 5P LG	H.8	1925400150	SAIL-M12WM12W-5-1.5V	B.25
1873280150	SAIL-M5W-3P-1.5U	B.23	1906310000	SAIL-M12WM12W-4-XU	B.7	1919680000	PB SUB-D IDC TERM PS	C.15	1925400300	SAIL-M12WM12W-5-3.0V	B.7
1873290150	SAIL-M5BG-3P-1.5U	B.23	1906310150	SAIL-M12WM12W-4-1.5U	B.25				1925401000	SAIL-M12WM12W-5-10V	B.7
1873300000	SAIL-M12G-PB-1.5D	C.6	1906310150	SAIL-M12WM12W-4-1.5U	B.7				1925401000	SAIL-M12GM12W-3LX XV	B.8
1873310150	SAIL-M12GM12G-PB-1.5D	C.7	1906310300	SAIL-M12WM12W-4-3.0U	B.7	1920000000	Screwty Set -DM	K.5	1925410150	SAIL-M12GM12W-3L1.5V	B.27
1873320150	SAIL-M12BG-PB-1.5D	C.6	1906310500	SAIL-M12WM12W-4-5.0U	B.7	1920700000	SAIS 5/9-VA	C.31	1925410150	SAIL-M12GM12W-3L1.5V	B.27
1877250000	SAIL-M8GM8W-3LXU	B.5	1906311000	SAIL-M12WM12W-4-10U	B.7	1920700000	SAIS 5/9-VA	D.12	1925410150	SAIL-M12GM12W-3L1.5V	B.8
1877250150	SAIL-M8GM8W-3L1.5U	B.34	1906330000	SAIL-M12WM8W-3-XU	B.5	1920700000	SAIS 5/9-VA	I.31	1925410300	SAIL-M12GM12W-3L3.0V	B.8
1877250300	SAIL-M8GM8W-3L3.0U	B.5	1906330150	SAIL-M12WM8W-3-1.5U	B.29	1920700000	SAIS 5/9-VA	C.78	1925410500	SAIL-M12GM12W-3L5.0V	B.8
1877250500	SAIL-M8GM8W-3L5.0U	B.5	1906330150	SAIL-M12WM8W-3-1.5U	B.5	1920710000	SAIB 5/9-VA	C.31	1925411000	SAIL-M12GM12W-3L10V	B.8
1877251000	SAIL-M8GM8W-3L10U	B.5	1906330300	SAIL-M12WM8W-3-3.0U	B.5	1920710000	SAIB 5/9-VA	D.12	1925420000	SAIL-M12GM12W-4-2LXXV	B.8
1877440100	SAIB-M23-12P-AN-1,0M	J.30	1906330500	SAIL-M12WM8W-3-5.0U	B.5	1920710000	SAIB 5/9-VA	I.31	1925420150	SAIL-M12GM12W-4-2L1.5V	B.27
1877950000	SAI-S12 3P M8 L	I.52	1906331000	SAIL-M12WM8W-3-10U	B.5	1920720000	SAIS 5/9-VA-B-COD	C.11	1925420150	SAIL-M12GM12W-4-2L1.5V	B.8
1879710150	SAIL-M12BG-12.15U	B.14	1906340150	SAIL-M12WM8W-4-1.5U	B.29	1920720000	SAIS 5/9-VA-B-COD	D.12	1925420300	SAIL-M12GM12W-4-2L3.0V	B.8
<b>18800000000</b>											
1880470000	SAIL-M8GM8G-4-XU	B.5	1906340300	SAIL-M12WM8W-4-3.0U	B.5	1920720000	SAIB 5/9-VA-B-COD	C.11	1925420500	SAIL-M12GM12W-4-2L5.0V	B.8
1880470150	SAIL-M8GM8G-4-1.5U	B.32	1906340500	SAIL-M12WM8W-4-5.0U	B.5	1920730000	SAIB 5/9-VA-B-COD	D.12	1925421000	SAIL-M12GM12W-4-2L10V	B.8
1880470300	SAIL-M8GM8G-4-3.0U	B.5	1906341000	SAIL-M12WM8W-4-10U	B.5	1920730000	SAIB 5/9-VA-B-COD	I.31	1925430000	SAIL-M12G-3-X-XV	B.4
1880470500	SAIL-M8GM8G-4-5.0U	B.5	1906341500	SAIL-M12WM8W-4-10U	B.5	1920730000	SAIB 5/9-VA-B-COD	J.22	1925430150	SAIL-M12G-3-1.5V	B.4
1880470700	SAIL-M8GM8G-4-10U	B.5	1906341500	SAIL-M12WM8W-4-10U	B.5	1920770000	SAIBW-M8-3P(TL)	D.6	1925430300	SAIL-M12G-3-3.0V	B.4
1880471000	SAIL-M8GM8G-4-10U	B.5	1906341500	SAIL-M12WM8W-4-10U	B.21	1920800000	SAIBW-M8-4P(TL)	D.22	1925430500	SAIL-M12G-3-5.0V	B.4
1881710000	SAI-Y-5S M12/M12 2Bo	D.30	1906410000	SAIL-M12GM12W-4-2LXXU	B.8	1920800000	SAIBW-M8-4P(TL)	D.6	1925431000	SAIL-M12G-3-10V	B.4
1883460150	SAIL-M12BW-8-1.5U	B.14	1906410150	SAIL-M12GM12W-4-2L1.5U	B.27	1920990000	SAISW-M8-3P(TL)	D.22	1925440000	SAIL-M12G-4-X-XV	B.4
1886440100	SAIB-M23-12P-ST-1,0M	J.30	1906410500	SAIL-M12GM12W-4-2L1.5U	B.8	1920990000	SAISW-M8-3P(TL)	D.6	1925440150	SAIL-M12G-4-1.5V	B.4
<b>18900000000</b>											
18900000000	SAI-AU M12 PB AI/AO/DI	F.9	1906410500	SAIL-M8GM8W-4L1.5U	B.31	1921010000	SAIB 5/9-VA-B-COD	D.21	1925440500	SAIL-M12G-5-X-XV	B.4
1890010000	SAI-AU M12 PB 16D/8D0	F.8	1906450150	SAIL-M8GM8W-4L1.5U	B.34	1921020000	SAIB 5/9-VA-B-COD	I.31	1925450150	SAIL-M12G-3-1.5V	B.11
1890020000	SAI-AU M12 PB 16D1	F.8	1906470150	SAIL-M12G-3S1.5U	B.17	1921020000	SAIB 5/9-VA-B-COD	J.22	1925450150	SAIL-M12G-3-1.5V	B.4
1890520150	SAIL-M12BG-8S1.5U	B.15	1906480150	SAIL-M12G-4S1.5U	B.17	1921070000	SAIBW-M8-3P(TL)	D.6	1925460300	SAIL-M12G-3-3.0V	B.4
1892080000	SAI-8-M 5P M12 ECO	I.17	1906500150	SAIL-M12W-3S1.5U	B.17	1920970000	SAIBW-M8-3P(TL)	D.6	1925460300	SAIL-M12G-3-3.0V	B.4
1892080005	SAI-8-M 5P M12 NPN ECO	I.17	19065020150	SAIL-M12W-5S1.5U	B.17	1920980000	SAIBW-M8-4P(TL)	D.22	1925460500	SAIL-M12G-3-5.0V	B.4
1892081000	SAI-8-M 5P M12 ECO UT	I.17	1906540150	SAIL-M12BW-5S1.5U	B.17	1920980000	SAIBW-M8-4P(TL)	D.6	1925461000	SAIL-M12G-3-10V	B.4
1892090000	SAI-6-M 5P M12 ECO	I.17	1906550000	SAI-AU M8 PB 16D1	F.10	1921050000	SAIS 5/7(KV)	D.10	1925460000	SAIL-M12BW-3LX XV	B.8
1892091000	SAI-6-M 5P M12 ECO UT	I.17	1906550000	SAI-AU M8 PB 16D1	F.4	1921060000	SAIS 4/7(KV)	D.10	1925460150	SAIL-M12BW-3L1.5V	B.16
1892100000	SAI-4-M 5P M12 ECO	I.17	1906550000	SAI-AU M8 PB 16D1	F.8	1921070000	SAIB 5/7-(KV)	D.10	1925460150	SAIL-M12BW-3L1.5V	B.8
1892100005	SAI-4-M 5P M12 NPN ECO	I.17	1906560150	SAIL-M8S-3S1.5U	B.22	1921080000	SAIB 4/7-(KV)	D.10	1925460300	SAIL-M12BW-3L3.0V	B.8
1892101000	SAI-4-M 5P M12 ECO UT	I.17	1906570150	SAIL-M8S-4S1.5U	B.22	1921090000	SAIS 4/8-(TL)	D.21	1925460500	SAIL-M12G-4-5.0V	B.4
1892120000	SAISM-4/8S-M12-4P D-COD	C.77	1906580150	SAIL-M8W-3S1.5U	B.22	1921090000	SAIS 4/8-(TL)	D.6	1925461000	SAIL-M12G-4-10V	B.4
1892120000	SAISM-4/8S-M12-4P D-COD	D.16	1906590150	SAIL-M8W-4S1.5U	B.22	1921090000	SAIS 5/7(KV)	D.10	1925460000	SAIL-M12BW-3LX XV	B.8
1892120000	SAISM-4/8S-M12-4P D-COD	D.18	1906600150	SAIL-M8W-3S1.5U	B.22	1921090000	SAIS 4/7(KV)	D.10	1925460150	SAIL-M12BW-3L1.5V	B.16
1892130000	SAIBM-4/8S-M12-4P D-COD	C.77	1906610150	SAIL-M8B-4S1.5U	B.22	1921090000	SAIB 5/7-(KV)	D.10	1925460150	SAIL-M12G-3-1.5V	B.4
1892130000	SAIBM-4/8S-M12-4P D-COD	D.16	1906620150	SAIL-M8B-3S1.5U	B.22	1921090000	SAIB 5/7-(KV)	D.19	1925460300	SAIL-M12G-3-3.0V	B.4
1892130000	SAIBM-4/8S-M12-4P D-COD	D.18	1906630150	SAIL-M8B-4S1.5U	B.22	1921090000	SAIB 5/7-(KV)	D.22	1925460500	SAIL-M12G-4-2L5.0V	B.8
1894380000	SAI-8-M 4P Exi Z1 0L	I.61	1906640000	SAI-AU M8 PB 16D/800	F.10	1921040000	SAISM-8-4P(TL)	D.21	1925461000	SAIL-M12G-4-10V	B.4
1896050000	SAI-6-M 5P M12 Ex ia	I.61	1906640000	SAI-AU M8 PB 16D/800	F.4	1921040000	SAISM-8-4P(TL)	D.6	1925460000	SAIL-M12BW-4-2LXXV	B.8
1896070000	SAI-6-M 5P M12 Ex ia	I.61	1906640000	SAI-AU M8 PB 16D/800	F.8	1921050000	SAIS 12/9-(TL)	D.5	1925460000	SAIL-M12BW-4-2LXXV	B.8
1896090000	SAI-8-M 5P M12 Ex ia	I.61	1906650000	SAI-AU M8 PB 16D/800	F.4	1921060000	SAIS 4/7(KV)	D.10	1925460150	SAIL-M12BW-3-1.5V	B.16
1897680000	SAI-4-MMS 5P M12 1:1	I.38	1906650000	SAI-AU M8 PB 16D/800	F.14	1921060000	SAIS 4/7(KV)	D.10	1925460150	SAIL-M12BW-3-1.5V	B.8
1898240150	SAIL-M12BW-12-1.5U	B.14	1906650000	SAI-AU M8 PB 16D/800	F.4	1921060000	SAIS 4/7(KV)	D.6	1925460300	SAIL-M12BW-3-3.0V	B.4
<b>19000000000</b>											
19000000000	Screwty-M12	K.5	1906660000	SAI-AU M12 CAN 16D/800	F.14	1921060000	SAIS 12/9-(TL)	D.11	1925470150	SAIL-M12BW-4-2L1.5V	B.16
1900010000	Screwty-M12-DM	H.7	1906670000	SAI-AU M12 CAN AI/AO/DI	F.13	1921070000	SAIB 12/9-(TL)	D.5	1925470150	SAIL-M12BW-4-2L1.5V	B.8
1900010000	Screwty-M12-DM	I.27	1906670000	SAI-AU M12 CAN AI/AO/DI	F.14	1921070000	SAIB 12/9-(TL)	D.19	1925470300	SAIL-M12BW-4-2L3.0V	B.8
1900010000	Screwty-M12-DM	K.5	1906680000	SAI-AU M8 CAN 16D1	F.12	1921070000	SAIB 12/9-(TL)	D.22	1925470500	SAIL-M12BW-4-2L5.0V	B.8
1900010000	Screwty-M8-MB	K.5	1906680000	SAI-AU M8 CAN 16D1	F.14	1921090000	SAIB 12/9-(TL)	D.6	1925500000	SAIL-M12BW-5-XV	B.4
1900011000	Screwty-M8-DM	K.5	1906680000	SAI-AU M8 CAN 16D1	F.4	1921090000	SAIB 12/9-(TL)	B.7	1925530000	SAIL-M12BW-5-1.5V	B.11
1900020000	Screwty-M12 F	K.5	1906690000	SAI-AU M8 CAN 16D1/800	F.12	1921090000	SAIB 12/9-(TL)	B.7	1925530150	SAIL-M12BW-5-1.5V	B.4
1900020000	Screwty-M12 F-DM	K.5	1906690000	SAI-AU M8 CAN 16D1/800	F.14	1921090000	SAIB 12/9-(TL)	B.7	1925530300	SAIL-M12BW-5-3.0V	B.4
1											

Order No.	Type	Page	Order No.	Type	Page	Order No.	Type	Page	Order No.	Type	Page
1925640150	SAIL-M12BW-4-1.5V	B.11	1927340150	SAIL-M8BW-4-1.5V	B.19	1938251000	SAIL-M8WM12W-3-10V	B.7	1948650150	SAIL-M8GM8GR-3-1.5V	B.33
1925640150	SAIL-M12BW-4-1.5V	B.7	1927340150	SAIL-M8BW-4-1.5V	B.5	1938260000	SAIL-M8GM12G-4-X.V	B.6	1948660150	SAIL-M8GM8WR-3-1.5V	B.33
1925640300	SAIL-M12BW-4-3.0V	B.7	1927340300	SAIL-M8BW-4-3.0V	B.5	1938260150	SAIL-M8GM12G-4-1.5V	B.6	1948670150	SAIL-M8WM8VR-3-1.5V	B.33
1925640500	SAIL-M12BW-4-5.0V	B.7	1927340500	SAIL-M8BW-4-5.0V	B.5	1938260300	SAIL-M8GM12G-4-3.0V	B.6	1948680150	SAIL-M8GM8GR-4-1.5V	B.33
1925641000	SAIL-M12BW-4-10V	B.7	1927341000	SAIL-M8BW-4-10V	B.5	1938260500	SAIL-M8GM12G-4-5.0V	B.6	1948690150	SAIL-M8GM8WR-4-1.5V	B.33
1925650000	SAIL-M12BW-5-XV	B.7	1927350000	SAIL-M8BW-3XL.XV	B.5	1938261000	SAIL-M8GM12G-4-10V	B.6	1948700150	SAIL-M8WM8VR-4-1.5V	B.33
1925650150	SAIL-M12BW-5-1.5V	B.11	1927350150	SAIL-M8BW-3L1.5V	B.21	1938270000	SAIL-M8GM12W-4-X.V	B.7	1948710150	SAIL-M8BGR-3-1.5V	B.20
1925650150	SAIL-M12BW-5-1.5V	B.7	1927350150	SAIL-M8BW-3L1.5V	B.5	1938270150	SAIL-M8GM12W-4-1.5V	B.7	1948720150	SAIL-M8BWR-3-1.5V	B.20
1925650300	SAIL-M12BW-5-3.0V	B.7	1927350300	SAIL-M8BW-3L3.0V	B.5	1938270300	SAIL-M8GM12W-4-3.0V	B.7	1948730150	SAIL-M8BGR-4-1.5V	B.20
1925650500	SAIL-M12BW-5-5.0V	B.7	1927350500	SAIL-M8BW-3L5.0V	B.5	1938270500	SAIL-M8GM12W-4-5.0V	B.7	1948740150	SAIL-M8BWR-4-1.5V	B.20
1925651000	SAIL-M12BW-5-10V	B.7	1927351000	SAIL-M8BW-3L10V	B.5	1938271000	SAIL-M8GM12W-4-10V	B.7			
1925870000	SAIL-BW-12/9-(TL)	D.11	1927360150	SAIL-M8BW-4L1.5V	B.21	1938280000	SAIL-M8WM12W-4-X.V	B.7			
1926690150	SAIL-M12G-6S1.5U	B.17				1938280150	SAIL-M8WM12W-4-1.5V	B.7			
1927150000	SAIL-M8GM8G-3-X.XV	B.4				1938280300	SAIL-M8WM12W-4-3.0V	B.7			
1927150150	SAIL-M8GM8G-3-1.5V	B.32				1938280500	SAIL-M8WM12W-4-5.0V	B.7			
1927150150	SAIL-M8GM8G-3-1.5V	B.4	1932380000	SAI-6 S 3P M8 L 0L	I.52	1938281000	SAIL-M8WM12W-4-10V	B.7			
1927150300	SAIL-M8GM8G-3-3.0V	B.4	1933640000	SAI-HP-2X0.34-PVC	C.9	1938300000	SAI-SSA-PG7	D.42			
1927150500	SAIL-M8GM8G-3-5.0V	B.4	1934200000	PB SUB-0 ZF TERM PS	C.15	1938550000	SAI-AU-M12 PB GW 16DI	F.22			
1927151000	SAIL-M8GM8G-3-10V	B.4	1935610000	SAI-BW-4/7-(KV)	D.10	1938550000	SAI-AU-M12 PB GW 16DI	F.23			
1927160000	SAIL-M8GM8G-4-X.V	B.5	1937950000	SAIL-M8GM12G-3-X.XU	B.6	1938550000	SAI-AU-M12 PB GW 16DI	F.23			
1927160150	SAIL-M8GM8G-4-1.5V	B.32	1937950150	SAIL-M8GM12G-3-1.5U	B.6	1938570000	SAI-AU-M12 DN GW 16DI	F.24			
1927160150	SAIL-M8GM8G-4-1.5V	B.5	1937950300	SAIL-M8GM12G-3-3.0U	B.6	1938570000	SAI-AU-M12 DN GW 16DI	F.25			
1927160300	SAIL-M8GM8G-4-3.0V	B.5	1937950500	SAIL-M8GM12G-3-5.0U	B.6	1938570000	SAI-AU-M12 DN GW 16DI	F.24			
1927160500	SAIL-M8GM8G-4-5.0V	B.5	1937951000	SAIL-M8GM12G-3-10U	B.6	1938600000	SAI-AU-M8 SB 8DI	F.25			
1927161000	SAIL-M8GM8G-4-10V	B.5	1937960000	SAIL-M8GM12W-3-X.XU	B.7	1938600000	SAI-AU-M8 SB 8DI	F.27			
1927170000	SAIL-M8GM8W-3-X.V	B.5	1937960150	SAIL-M8GM12W-3-1.5U	B.7	1938600000	SAI-AU-M8 SB 8DI	F.27			
1927170150	SAIL-M8GM8W-3-1.5V	B.32	1937960300	SAIL-M8GM12W-3-3.0U	B.7	1938600000	SAI-AU-M8 SB 8DI	F.28			
1927170150	SAIL-M8GM8W-3-1.5V	B.5	1937960500	SAIL-M8GM12W-3-5.0U	B.7	1938600000	SAI-AU-M8 SB 8DI	F.28			
1927170300	SAIL-M8GM8W-3-3.0V	B.5	1937961000	SAIL-M8GM12W-3-10U	B.7	1938610000	SAI-AU-M12 SB 8DI	F.23			
1927170500	SAIL-M8GM8W-3-5.0V	B.5	1937970000	SAIL-M8WM12W-3X.XU	B.7	1938610000	SAI-AU-M12 SB 8DI	F.25			
1927171000	SAIL-M8GM8W-3-10V	B.5	1937970150	SAIL-M8WM12W-3-1.5U	B.7	1938610000	SAI-AU-M12 SB 8DI	F.27			
1927171000	SAIL-M8GM8W-3-X.V	B.5	1937970300	SAIL-M8WM12W-3-3.0U	B.7	1938610000	SAI-AU-M12 SB 8DI	F.28			
1927180000	SAIL-M8GM8W-4-X.V	B.5	1937970500	SAIL-M8WM12W-3-5.0U	B.7	1938610000	SAI-AU-M12 SB 8DI	F.28			
1927180150	SAIL-M8GM8W-4-1.5V	B.32	1937971000	SAIL-M8WM12W-3-10U	B.7	1938630000	SAI-AU-M8 SB 8DI	F.23			
1927180150	SAIL-M8GM8W-4-1.5V	B.5	1937980000	SAIL-M8GM12G-4-X.XU	B.6	1938630000	SAI-AU-M8 SB 8DI	F.25			
1927180300	SAIL-M8GM8W-4-3.0V	B.5	1937980150	SAIL-M8GM12G-4-1.5U	B.6	1938630000	SAI-AU-M8 SB 8DI	F.25			
1927180500	SAIL-M8GM8W-4-5.0V	B.5	1937990000	SAIL-M8GM12G-4-3.0U	B.7	1938640000	SAI-AU-M8 SB 8DI	F.27			
1927181000	SAIL-M8GM8W-4-10V	B.5	1937990300	SAIL-M8GM12G-4-5.0U	B.6	1938640000	SAI-AU-M8 SB 8DI	F.28			
1927190000	SAIL-M8GM8W-3XL.XV	B.5	1937990500	SAIL-M8GM12G-4-5.0U	B.6	1938640000	SAI-AU-M8 SB 8DI	F.28			
1927190150	SAIL-M8GM8W-3-1.5V	B.34	1937991000	SAIL-M8GM12W-4-10U	B.6	1938640000	SAI-AU-M12 SB 8DI	F.23			
1927190150	SAIL-M8GM8W-3-1.5V	B.5	1937990000	SAIL-M8GM12W-4-X.XU	B.7	1938660000	SAI-AU-M12 SB 8DI	F.25			
1927190300	SAIL-M8GM8W-3-3.0V	B.5	193799150	SAIL-M8GM12W-4-1.5U	B.7	1938660000	SAI-AU-M12 SB 8DI	F.25			
1927190500	SAIL-M8GM8W-3L5.0V	B.5	1937990300	SAIL-M8GM12W-4-3.0U	B.7	1938660000	SAI-AU-M12 SB 8DI	F.27			
1927191000	SAIL-M8GM8W-3L10V	B.5	1937990500	SAIL-M8GM12W-4-5.0U	B.7	1938660000	SAI-AU-M12 SB 8DI	F.27			
1927200000	SAIL-M8GM8W-3-X.XU	B.5	1937991000	SAIL-M8GM12W-4-10U	B.7	1938660000	SAI-AU-M12 SB 8DI	F.27			
1927210000	SAIL-M8WM8W-3-1.5V	B.32	1938000150	SAIL-M8WM12W-4-1.5V	B.7	1938660000	SAI-AU-M12 SB 8DI	F.27			
1927210150	SAIL-M8WM8W-3-1.5V	B.5	1938003000	SAIL-M8WM12W-4-3.0U	B.7	1938660000	SAI-AU-M12 SB 8DI	F.28			
1927210300	SAIL-M8WM8W-3-3.0V	B.5	1938005000	SAIL-M8WM12W-4-5.0U	B.7	1938660000	SAI-AU-M12 SB 8DI	F.28			
1927210500	SAIL-M8WM8W-3-5.0V	B.5	1938010000	SAIL-M8WM12W-4-10U	B.7	1938660000	SAI-AU-M12 SB 8DI	F.28			
1927220000	SAIL-M8WM8W-3-X.V	B.5	19380150	SAIL-M12GM8G-3-1.5V	B.29	1938680000	SAI-AU-M12 SB 8DI	F.25			
1927220150	SAIL-M8WM8W-4-X.V	B.5	19380150	SAIL-M12GM8G-3-1.5V	B.4	1938680000	SAI-AU-M12 SB 8DI	F.27			
1927220150	SAIL-M8WM8W-4-1.5V	B.32	1938017000	SAIL-M12GM8G-3-3.0V	B.4	1938680000	SAI-AU-M12 SB 8DI	F.27			
1927220150	SAIL-M8WM8W-4-1.5V	B.5	1938017000	SAIL-M12GM8G-3-3.0V	B.4	1938680000	SAI-AU-M12 SB 8DI	F.28			
1927220300	SAIL-M8WM8W-4-3.0V	B.5	1938017500	SAIL-M12GM8G-3-5.0V	B.4	1938690000	SAI-AU-M12 SB 8DI	F.23			
1927220500	SAIL-M8WM8W-4-5.0V	B.5	1938017700	SAIL-M12GM8G-3-10V	B.5	1938690000	SAI-AU-M12 SB 8DI	F.27			
1927221000	SAIL-M8WM8W-4-10V	B.5	1938018000	SAIL-M12GM8W-3-X.XV	B.5	1938690000	SAI-AU-M12 SB 8DI	F.27			
1927230000	SAIL-M8BG-3-X.V	B.4	1938018000	SAIL-M12GM8W-3-1.5V	B.29	1938700000	SAI-AU-M12 SB 8DI	F.25			
1927230150	SAIL-M8BG-3-1.5V	B.19	1938018000	SAIL-M12GM8W-3-1.5V	B.5	1938700000	SAI-AU-M12 SB 8DI	F.27			
1927230150	SAIL-M8BG-3-1.5V	B.4	1938180300	SAIL-M12GM8W-3-3.0V	B.5	1938700000	SAI-AU-M12 SB 8DI	F.25			
1927230300	SAIL-M8BG-3-3.0V	B.4	1938190500	SAIL-M12GM8W-3-5.0V	B.5	1938700000	SAI-AU-M12 SB 8DI	F.27			
1927230400	SAIL-M8BG-3-5.0V	B.4	1938190700	SAIL-M12GM8W-3-10V	B.5	1938700000	SAI-AU-M12 SB 8DI	F.27			
1927241000	SAIL-M8BG-3-10V	B.4	1938200000	SAIL-M12GM8G-4-X.V	B.5	1938700000	SAI-AU-M12 SB 8DI	F.27			
1927250000	SAIL-M8BG-4-X.V	B.4	1938200150	SAIL-M12GM8G-4-1.5V	B.29	1938720000	SAI-AU-M12 SB 4Thermo	F.23			
1927250150	SAIL-M8BG-4-1.5V	B.19	1938200150	SAIL-M12GM8G-4-1.5V	B.5	1938720000	SAI-AU-M12 SB 4Thermo	F.25			
1927250150	SAIL-M8BG-4-1.5V	B.4	1938200300	SAIL-M12GM8G-4-3.0V	B.5	1938720000	SAI-AU-M12 SB 4Thermo	F.27			
1927250300	SAIL-M8BG-4-3.0V	B.4	1938200500	SAIL-M12GM8G-4-5.0V	B.5	1938720000	SAI-AU-M12 SB 4Thermo	F.27			
1927250500	SAIL-M8BG-4-5.0V	B.4	1938201000	SAIL-M12GM8G-4-10V	B.5	1938720000	SAI-AU-M12 SB 4Thermo	F.27			
1927251000	SAIL-M8BG-4-10V	B.4	1938210000	SAIL-M12GM8W-4-X.XV	B.5	1938730000	SAI-AU-M12 SB 2Counter	F.23			
1927260000	SAIL-M8BG-4-X.XV	B.5	1938210150	SAIL-M12GM8W-4-1.5V	B.29	1938730000	SAI-AU-M12 SB 2Counter	F.25			
1927260150	SAIL-M8BG-4-1.5V	B.19	1938210150	SAIL-M12GM8W-4-1.5V	B.5	1938730000	SAI-AU-M12 SB 2Counter	F.27			
1927260150	SAIL-M8BG-4-1.5V	B.5	1938210300	SAIL-M12GM8W-4-3.0V	B.5	1938730000	SAI-AU-M12 SB 2Counter	F.30			
1927260300	SAIL-M8BG-4-3.0V	B.5	1938210500	SAIL-M12GM8W-4-5.0V	B.5	1938730000	SAI-AU-M12 SB 2Counter	F.4			
1927260500	SAIL-M8BG-4-5.0V	B.5	1938211000	SAIL-M12GM8W-4-10V	B.5	1939170000	SAI-SCREWTY TOOL BOX	K.6			
1927261000	SAIL-M8BG-4-10V	B.5	1938220000	SAIL-M12WM8W-4-X.XV	B.5	1939180000	SAI-SCREWTY BOX	K.6			
1927310000	SAIL-M8W-3-X.V	B.4	1938220150	SAIL-M12WM8W-4-1.5V	B.29	19393370150	SAIV-M12BW-2/4-1.5U	B.13			
1927310150	SAIL-M8W-3-1.5V	B.19	1938220150	SAIL-M12WM8W-4-1.5V	B.5	19393410150	SAIV-M12BW-2/4-1.5U	B.13			
1927310150	SAIL-M8W-3-1.5V	B.4	1938220300	SAIL-M12WM8W-4-3.0V	B.5	1939410000	SAIV-M12BW-2/4-1.5U	B.13			
1927310300	SAIL-M8W-3-3.0V	B.4	1938220500	SAIL-M12WM8W-4-5.0V	B.5	1939450000	SAIV-M12BW-2/4-1.5U	B.13			
1927310500	SAIL-M8W-3-5.0V	B.4	1938221000	SAIL-M12WM8W-4-1							

Order No.	Type	Page	Order No.	Type	Page	Order No.	Type	Page	Order No.	Type	Page
<b>2320000000</b>			<b>8560000000</b>			<b>8830000000</b>			9456230000	SAI-F 4P PUR 20M	1.8
2326170000 B KOTR M12 5P A BU SAI	G.10		8564060000 FBCon PA CG/M12 1way	C.36		8836630000 JPTA100MS 24VDC PNP M12	H.4		9456240150	SAIL-VSCD 1.5U	B.49
2326170000 B KOTR M12 5P A BU SAI	G.13		8564070000 FBCon PA CG/M12 2way	C.37					9456320000	SAI-F 5P PUR 3M	1.8
2326170000 B KOTR M12 5P A BU SAI	G.6		8564080000 FBCon PA CG/M12 4way	C.38					9456330000	SAI-F 5P PUR 5M	1.8
2326170000 B KOTR M12 5P A BU SAI	G.9		8564090000 FBCon PA CG 1way	C.36					9456340000	SAI-F 5P PUR 10M	1.6
<b>2330000000</b>			8564100000 FBCon PA CG 2way	C.37					9456340000	SAI-F 5P PUR 10M	1.8
2330260000 SAI-SK-M12-UNI	D.31		8564110000 FBCon PA CG 4way	C.38					9456350000	SAI-F 5P PUR 15M	1.6
2330260000 SAI-SK-M12-UNI	F.10		8564150000 FBCon PA CG/M12 1way Ex	C.52					9456350000	SAI-F 5P PUR 15M	1.8
2330260000 SAI-SK-M12-UNI	F.14		8564160000 FBCon PA CG/M12 2way Ex	C.53					9456370000	SAI-F 5P PUR 20M	1.6
2330260000 SAI-SK-M12-UNI	F.18		8564170000 FBCon PA CG/M12 4way Ex	C.54					9456370000	SAI-F 5P PUR 20M	1.8
2330260000 SAI-SK-M12-UNI	F.23		8564180000 FBCon PA CG 1way Ex	C.52					9456380000	SAIL-M12BW4-2LXXU	B.8
2330260000 SAI-SK-M12-UNI	F.25		8564190000 FBCon PA CG 2way Ex	C.53					9456380150	SAIL-M12BW4-2L1.5U	B.16
2330260000 SAI-SK-M12-UNI	F.27		8564200000 FBCon PA CG 4way Ex	C.54					9456380150	SAIL-M12BW4-2L1.5U	B.8
2332380000 B KOTR M8 3P BU SAI	G.13		8564240000 FBCon PA CG 8way Ex	C.55					9456380300	SAIL-M12BW4-2L3.0U	B.8
2332380000 B KOTR M8 3P BU SAI	G.7		8564250000 FBCon PA CG/M12 8way Ex	C.55					9456380500	SAIL-M12BW4-2L5.0U	B.8
<b>2340000000</b>			8564290000 FBCon DP CG Term 24V	C.24					9456381000	SAIL-M12BW4-2L10U	B.8
2341480000 B KOTR M12 4P D BU SAI	G.10		8564300000 FBCon PA CG 8way	C.39					9456460000	SAI-F 4P PUR 3M	1.8
2341480000 B KOTR M12 4P D BU SAI	G.13		8564310000 FBCon PA CG/M12 8way	C.39					9456470000	SAI-F 4P PUR 5M	1.6
2341480000 B KOTR M12 4P D BU SAI	G.6		8564330000 FBCon DP M12 Term 24V	C.24					9456480000	SAI-F 4P PUR 10M	1.6
2341480000 B KOTR M12 4P D BU SAI	G.9		8564340000 FBCon DP CG 1way	C.23					9456480000	SAI-F 4P PUR 10M	1.8
<b>2350000000</b>			8564350000 FBCon DP M12 1way	C.23					9456490000	SAI-F 4P PUR 15M	1.6
2350590000 B KOTR B M12 4POL D BU	G.13		<b>8600000000</b>						9456490000	SAI-F 4P PUR 15M	1.8
2350590000 B KOTR B M12 4POL D BU	G.7		8606180000 FBCon Term.D Ex FM/PEAN	C.56					9456490000	SAI-F 4P PUR 15M	1.8
2350600000 B KOTR B M12 5POL A BU	G.13		8606190000 FBCon Term.D Ex	C.56					9456500000	SAIL-M12WM12G-5-XU	B.7
2350600000 B KOTR B M12 5POL A BU	G.7		8606200000 FBCon Term.D Ex PEAN	C.56					9456500150	SAIL-M12WM12G-5.1U	B.7
<b>8610000000</b>									9456500300	SAIL-M12WM12G-5.3U	B.7
2350600000 B KOTR B M12 5POL A SF	G.10		<b>8640000000</b>						9456500500	SAIL-M12WM12G-5.5U	B.7
2350610000 B KOTR B M12 5POL A SF	G.13		8640720000 FBCon SS PCG 8way	C.39					9456500100	SAIL-M12WM12G-5.10U	B.7
2350610000 B KOTR B M12 5POL A SF	G.7		<b>8700000000</b>						9456510000	SAI-F 4P PUR 20M	1.6
2350620000 B KOTR B M12 5POL B BU	G.13		8703430000 FBCon SS CG 1way	C.36					9456510000	SAI-F 4P PUR 20M	1.8
2350620000 B KOTR B M12 5POL B BU	G.7		8703450000 FBCon SS CG 4way	C.38					9456510000	SAI-F 4P PUR 10M	1.6
2350640000 B KOTR B M8 4POL BU	G.10		8703470000 FBCon SS CG 8way	C.39					9456510000	SAI-F 4P PUR 10M	1.8
2350650000 B KOTR B M8 4POL SF	G.10		<b>8710000000</b>						9456510000	SAI-F 4P PUR 20M	1.6
2350650000 B KOTR B M8 4POL SF	G.13		8714080000 FBCon PA CG/M12 1way OVP	C.41					9456510000	SAI-F 4P PUR 20M	1.8
2350650000 B KOTR B M8 4POL SF	G.9		8714090000 FBCon PA CG/M12 2way OVP	C.42					9456510000	SAI-F 4P PUR 20M	1.8
2350650000 B KOTR B M8 4POL SF	G.7		8714100000 FBCon PA CG/M12 4way OVP	C.43					9456510000	SAI-F 4P PUR 20M	1.8
2350650000 B KOTR B M8 4POL SF	G.6		8714110000 FBCon PA CG/M12 8way OVP	C.44					9456510000	SAI-F 4P PUR 20M	1.8
2350650000 B KOTR B M8 4POL SF	G.9		8714120000 FBCon PA CG 1way OVP	C.41					9456510000	SAI-F 4P PUR 20M	1.8
<b>4290000000</b>			8714130000 FBCon PA CG 2way OVP	C.42					9456510000	SAI-F 4P PUR 20M	1.8
4294820000 1/4" Handgriff	K.5		8714140000 FBCon PA CG 4way OVP	C.43					9456510000	SAI-F 4P PUR 20M	1.8
<b>4310000000</b>			8714150000 FBCon PA CG 8way OVP	C.44					9456510000	SAI-F 4P PUR 20M	1.8
4310920000 SAI-BFSC M3x10	G.13		8714160000 FBCon PA CG/M12 1way Limiter	C.45					9456510000	SAI-F 4P PUR 20M	1.8
4310920000 SAI-BFSC M3x10	G.6		8714170000 FBCon PA CG/M12 2way Limiter	C.46					9456510000	SAI-F 4P PUR 20M	1.8
4311000000 SAI-O-RI 7.5X1.5 VI	G.10		8714180000 FBCon PA CG/M12 4way Limiter	C.47					9456510000	SAI-F 4P PUR 20M	1.8
4311000000 SAI-O-RI 7.5X1.5 VI	G.13		8714190000 FBCon PA CG/M12 8way Limiter	C.48					9456510000	SAI-F 4P PUR 20M	1.8
4311000000 SAI-O-RI 7.5X1.5 VI	G.6		8714200000 FBCon PA CG 1way Limiter	C.45					9456510000	SAI-F 4P PUR 20M	1.8
4311000000 SAI-O-RI 7.5X1.5 VI	G.9		8714210000 FBCon PA CG 2way Limiter	C.46					9456510000	SAI-F 4P PUR 20M	1.8
4311430000 PTSC 25X12 WN5452	G.10		8714220000 FBCon PA CG 4way Limiter	C.47					9456510000	SAI-F 4P PUR 20M	1.8
4311430000 PTSC 25X12 WN5452	G.6		8714230000 FBCon PA CG 8way Limiter	C.48					9456510000	SAI-F 4P PUR 20M	1.8
4311240000 SAI-O-RI 5.0X0.8 NBR	G.10		8714240000 FBCon SS DP PCG Term 24V	C.24					9456510000	SAI-F 4P PUR 20M	1.8
4312340000 SAI-O-RI 5.0X0.8 NBR	G.13		8714250000 FBCon SS DP M12 Term 24V	C.24					9456510000	SAI-F 4P PUR 20M	1.8
4312340000 SAI-O-RI 5.0X0.8 NBR	G.13		8714260000 FBCon SS DP PCG 1way	C.23					9456510000	SAI-F 4P PUR 20M	1.8
4312340000 SAI-O-RI 5.0X0.8 NBR	G.6		8714270000 FBCon SS DP M12 1way	C.23					9456510000	SAI-F 4P PUR 20M	1.8
4312340000 SAI-O-RI 5.0X0.8 NBR	G.9		8714280000 FBCon SS PCG 4way Limiter	C.47					9456510000	SAI-F 4P PUR 20M	1.8
<b>4320000000</b>			8714290000 FBCon SS PCG 2way OVP	C.41					9456510000	SAI-F 4P PUR 20M	1.8
4322750000 GWHUE BUS M12 BU SAI	G.7		<b>8720000000</b>						9456510000	SAI-F 4P PUR 20M	1.8
4322760000 GWHUE BUS M12 SF SAI	G.7		8726020000 FBCon SS CG/M12 1way	C.36					9456510000	SAI-F 4P PUR 20M	1.8
7915030000 SAI-F 5P 2M 0.5/1.0U	I.8		8726040000 FBCon SS CG/M12 4way	C.38					9456510000	SAI-F 4P PUR 20M	1.8
<b>8390000000</b>			8726050000 FBCon SS CG/M12 8way	C.39					9456510000	SAI-F 4P PUR 20M	1.8
8395500000 PB-DP SUB-D	C.14		8726080000 FBCon SS PCG 4way OVP	C.43					9456510000	SAI-F 4P PUR 20M	1.8
<b>8420000000</b>			8726090000 FBCon SS PCG 8way OVP	C.44					9456510000	SAI-F 4P PUR 20M	1.8
8425930000 POS-4P M12 PG13.5 300 mm	C.33		8726110000 FBCon SS PCG 2way Limiter	C.45					9456510000	SAI-F 4P PUR 20M	1.8
8425930000 POS-4P M12 M20 150mm	C.33		8726160000 FBCon SS PCG 4way Limiter	C.48					9456510000	SAI-F 4P PUR 20M	1.8
8425940000 POS-4P M12 M20 300mm	C.33		8771140000 JPR 24VDC 1CO M12	H.3					9456510000	SAI-F 4P PUR 20M	1.8
8425960000 SAI-SK-M12 BU	D.31		8771143000 JPR 24VDC ISO 1CO M12	H.3					9456510000	SAI-F 4P PUR 20M	1.8
8426220000 FBCon M12 4P FM EMC	C.32		8771144000 JPTA 50MS 24VDC PNP M12	H.4					9456510000	SAI-F 4P PUR 20M	1.8
8426220000 FBCon M12 4P FM EMC	D.15		8778490000 JP CLIP M	H.7					9456510000	SAI-F 4P PUR 20M	1.8
8426220000 FBCon M12 4P FM EMC	D.5		<b>8780000000</b>						9456510000	SAI-F 4P PUR 20M	1.8
<b>8460000000</b>			8788580000 RS PB-DP T SUB-D	C.25					9456510000	SAI-F 4P PUR 20M	1.8
8460860000 PB-DP SUB-D TERM	C.15		8794080000 SAI JP 5P LG 100	H.8					9456510000	SAI-F 4P PUR 20M	1.8
<b>8550000000</b>			8794090000 SAI JP 4P LG 100	H.8					9456510000	SAI-F 4P PUR 20M	1.8
8556460000 FBCon Term.D Ex FM	C.56		8794120000 JP TEST	H.8					9456510000	SAI-F 4P PUR 20M	1.8
<b>8800000000</b>			8800040000 RS PB-DP T	C.25					9456510000	SAI-F 4P PUR 20M	1.8
8800040000 RS PB-DP T	C.25		8800040000 SAI-F 4P PUR 20M	C.25					9456510000	SAI-F 4P PUR 20M	1.8

Order No.	Type	Page	Order No.	Type	Page
9457260000	SAIBW-5/7	B.8	9457740300	SAIL-M12BW-4-3.0U	B.7
9457270000	SAIL-M12GM12W-5-XU	B.7	9457740500	SAIL-M12BW-4-5.0U	B.7
9457270150	SAIL-M12GM12W-5-1.5U	B.25	9457741000	SAIL-M12BW-4-10U	B.7
9457270150	SAIL-M12GM12W-5-1.5U	B.7	9457760000	SAIL-M12GM8W-3LX.XU	B.5
9457270300	SAIL-M12GM12W-5-3.0U	B.7	9457760150	SAIL-M12GM8W-3L1.5U	B.31
9457270500	SAIL-M12GM12W-5-5.0U	B.7	9457760150	SAIL-M12GM8W-3L1.5U	B.5
9457271000	SAIL-M12GM12W-5-10U	B.7	9457760300	SAIL-M12GM8W-3L3.0U	B.5
9457290000	SAISW-4/7	D.5	9457760500	SAIL-M12GM8W-3L5.0U	B.5
9457290000	SAISW-4/7	D.7	9457761000	SAIL-M12GM8W-3L10U	B.5
9457310000	SAIL-M12GM12W-4-XU	B.7	9457770000	SAIL-M12GM8G-3-XU	B.4
9457310150	SAIL-M12GM12W-4-1.5U	B.25	9457770150	SAIL-M12GM8G-3-1.5U	B.29
9457310150	SAIL-M12GM12W-4-1.5U	B.7	9457770150	SAIL-M12GM8G-3-1.5U	B.4
9457310300	SAIL-M12GM12W-4-3.0U	B.7	9457770300	SAIL-M12GM8G-3-3.0U	B.4
9457310500	SAIL-M12GM12W-4-5.0U	B.7	9457770500	SAIL-M12GM8G-3-5.0U	B.4
9457311000	SAIL-M12GM12W-4-10U	B.7	9457771000	SAIL-M12GM8G-3-10U	B.4
9457320000	SAIL-M12BW-3-XU	B.7	9457780150	SAIL-VSBD-M12G-1.5U	B.49
9457320150	SAIL-M12BW-3-1.5U	B.11	9457790000	SAIL-M12GM12W-3LX.XU	B.8
9457320150	SAIL-M12BW-3-1.5U	B.7	9457790150	SAIL-M12GM12W-3L1.5U	B.27
9457320300	SAIL-M12BW-3-3.0U	B.7	9457790150	SAIL-M12GM12W-3L1.5U	B.8
9457320500	SAIL-M12BW-3-5.0U	B.7	9457790300	SAIL-M12GM12W-3L3.0U	B.8
9457321000	SAIL-M12BW-3-10U	B.7	9457790500	SAIL-M12GM12W-3L5.0U	B.8
9457340000	SAIL-M12GM12G-5-XU	B.7	9457791000	SAIL-M12GM12W-3L10U	B.8
9457340030	SAIL-M12GM12G-5-0.3U	H.7	9457800000	SAIL-M12BW-3LX.XU	B.8
9457340060	SAIL-M12GM12G-5-0.6U	H.7	9457800150	SAIL-M12BW-3L1.5U	B.16
9457340150	SAIL-M12GM12G-5-1.5U	B.25	9457800150	SAIL-M12BW-3L1.5U	B.8
9457340150	SAIL-M12GM12G-5-1.5U	B.7	9457800300	SAIL-M12BW-3L3.0U	B.8
9457340150	SAIL-M12GM12G-5-1.5U	H.7	9457800500	SAIL-M12BW-3L5.0U	B.8
9457340300	SAIL-M12GM12G-5-3.0U	B.7	9457801000	SAIL-M12BW-3L10U	B.8
9457340500	SAIL-M12GM12G-5-5.0U	B.7	9457810000	SAIL-M12G-3-X.XU	B.4
9457341000	SAIL-M12GM12G-5-10U	B.7	9457810150	SAIL-M12G-3-1.5U	B.11
9457350000	SAI-8-MF 5P PUR 5M 0L	I.44	9457810150	SAIL-M12G-3-1.5U	B.4
9457380000	SAIL-M8BWS-3-XU	B.5	9457810300	SAIL-M12G-3-3.0U	B.4
9457380150	SAIL-M8BWS-3-1.5U	B.19	9457810500	SAIL-M12G-3-5.0U	B.4
9457380150	SAIL-M8BWS-3-1.5U	B.5	9457811000	SAIL-M12G-3-10U	B.4
9457380300	SAIL-M8BWS-3-3.0U	B.5	9457820000	SAIL-M12BG-3-X.XU	B.6
9457380500	SAIL-M8BWS-3-5.0U	B.5	9457820150	SAIL-M12BG-3-1.5U	B.11
9457381000	SAIL-M8BWS-3-10U	B.5	9457820150	SAIL-M12BG-3-1.5U	B.6
9457390000	SAIL-M12GM12W-3-XU	B.7	9457820300	SAIL-M12BG-3-3.0U	B.6
9457390150	SAIL-M12GM12W-3-1.5U	B.25	9457820500	SAIL-M12BG-3-5.0U	B.6
9457390150	SAIL-M12GM12W-3-1.5U	B.7	9457821000	SAIL-M12G-3-10U	B.6
9457390300	SAIL-M12GM12W-3-3.0U	B.7	9457850150	SAIL-M12BG-4-1.5U	B.19
9457390500	SAIL-M12GM12W-3-5.0U	B.7	9457850150	SAIL-M12BG-4-1.5U	B.5
9457391000	SAIL-M12GM12W-3-10U	B.7	9457850300	SAIL-M12BG-4-3.0U	B.5
9457400150	SAIL-VSC-M12G-1.5U	B.49	9457850500	SAIL-M12BG-4-5.0U	B.5
9457410150	SAIL-ZW-M8BW-3L1.5U	B.39	9457851000	SAIL-M8BG-4-10U	B.5
9457420000	SAIH-SL-3x0.75-8x0.34	B.57	9457890150	SAIL-M12GM12W-2/4-1.5U	B.26
9457430000	SAI-8-MF 5P PUR 10m	I.44	9457900000	SAIL-M12WM12W-5-XU	B.7
9457450000	SAIL-M8BG-3-X.XU	B.4	9457900150	SAIL-M12WM12W-5-1.5U	B.25
9457450150	SAIL-M8BG-3-1.5U	B.19	9457900150	SAIL-M12WM12W-5-1.5U	B.7
9457450150	SAIL-M8BG-3-1.5U	B.4	9457900300	SAIL-M12WM12W-5-3.0U	B.7
9457450300	SAIL-M8BG-3-3.0U	B.4	9457900500	SAIL-M12WM12W-5-6.0U	B.7
9457450500	SAIL-M8BG-3-5.0U	B.4	9457901000	SAIL-M12WM12W-5-10U	B.7
9457451000	SAIL-M8BG-3-10U	B.4	9457910000	SAIL-M12BG-5-X.XU	B.7
9457460000	SAIL-M8BW-3LX.XU	B.5	9457910150	SAIL-M12BG-5-1.5U	B.11
9457460150	SAIL-M8BW-3L1.5U	B.21	9457910150	SAIL-M12BG-5-1.5U	B.7
9457460150	SAIL-M8BW-3L1.5U	B.5	9457910300	SAIL-M12BG-5-3.0U	B.7
9457460300	SAIL-M8BW-3L3.0U	B.5	9457910500	SAIL-M12BG-5-5.0U	B.7
9457460500	SAIL-M8BW-3L5.0U	B.5	9457911000	SAIL-M12BG-5-10U	B.7
9457461000	SAIL-M8BW-3L10U	B.5	9457920150	SAIL-VSC-1.5U	B.49
9457490150	SAIL-ZW-M8BG-3-1.5U	B.39	9457930150	SAIL-VSB-1.5U	B.48
9457540000	SAIS-ZW-5	D.30	9457950150	SAIV-M12BG-4-1.5U	B.13
9457550000	SAIS-4/7	D.5	9457960150	SAIV-M12BW-4-1.5U	B.13
9457550000	SAIS-4/7	D.7	9457970000	SAIH-SL-5x0.75-16x0.34	B.57
9457560000	SAIH-SL-3x0.75-16x0.34	B.57	9457980000	SAIL-M12GM8W-3-XU	B.5
9457570150	SAIL-M12GM8WR-3-1.5U	B.30	9457980150	SAIL-M12GM8W-3-1.5U	B.29
9457590000	SAI-8-MP 5M 0.5/1.0U	I.8	9457980150	SAIL-M12GM8W-3-1.5U	B.5
9457600000	SAI-8-MP 10M 0.5/1.0U	I.8	9457980300	SAIL-M12GM8W-3-3.0U	B.5
9457610000	SAIL-M12G-5-XU	B.4	9457980500	SAIL-M12GM8W-3-5.0U	B.5
9457610150	SAIL-M12G-5-1.5U	B.11	9457981000	SAIL-M12GM8W-3-10U	B.5
9457610150	SAIL-M12G-5-1.5U	B.4			
9457610300	SAIL-M12G-5-3.0U	B.4			
9457610500	SAIL-M12G-5-5.0U	B.4			
9457611000	SAIL-M12G-5-10U	B.4			
9457670000	SAIL-M12W-5-XU	B.4			
9457670150	SAIL-M12W-5-1.5U	B.11			
9457670150	SAIL-M12W-5-1.5U	B.4			
9457670300	SAIL-M12W-5-3.0U	B.4			
9457670500	SAIL-M12W-5-5.0U	B.4			
9457671000	SAIL-M12W-5-10U	B.4			
9457680150	SAIL-VSB-M12G-1.5U	B.48			
9457690000	SAIL-M12BW-5-XU	B.7			
9457690150	SAIL-M12BW-5-1.5U	B.11			
9457690150	SAIL-M12BW-5-1.5U	B.7			
9457690300	SAIL-M12BW-5-3.0U	B.7			
9457690500	SAIL-M12BW-5-5.0U	B.7			
9457691000	SAIL-M12BW-5-10U	B.7			
9457700000	SAIBW-4/7	D.5			
9457700000	SAIBW-4/7	D.7			
9457710150	SAIL-VSA-1.5U	B.47			
9457720000	SAI-SA-3-IDC	I.26			
9457730000	SAIL-M12BG-4-X.XU	B.6			
9457730150	SAIL-M12BG-4-1.5U	B.11			
9457730150	SAIL-M12BG-4-1.5U	B.6			
9457730300	SAIL-M12BG-4-3.0U	B.6			
9457730500	SAIL-M12BG-4-5.0U	B.6			
9457731000	SAIL-M12BG-4-10U	B.6			
9457740000	SAIL-M12GM12G-5-XU	B.7			
9457740150	SAIL-M12BW-4-1.5U	B.11			
9457740150	SAIL-M12BW-4-1.5U	B.7			



# Addresses worldwide

<b>AE</b>	<b>United Arab Emirates</b> Weidmüller Middle East FZE P.O. Box 8591, SAIF-Zone Sharjah U.A.E. Phone +971 6 5572723 Fax +971 6 5572724 vme.info@weidmueller.com	<b>BY</b>	<b>Belarus</b> Technikom Ltd. Nezavisimosti pr. 177-9 Minsk 220125 Phone +375 17 3931177 Fax +375 17 3930080 vvm@technikon.by	<b>EC</b>	<b>Ecuador</b> Elsystec S. A. Electricidad Sistemas y Tecnología Vasco de Contreras N35-25 y Mañosa, Quito Phone +593 2 2456510 Fax +593 2 2456755 Elsystec@uiosatnet.net	<b>HU</b>	<b>Hungary</b> Weidmüller Kft Gubacsí út 6 1097 Budapest Phone +36 1 3827700 Fax +36 1 3827701 info@weidmueller.hu	<b>KW</b>	<b>Kuwait</b> KANA CONTROLS General Trading & Cont. CO. W.L.L. Al Rai Industrial Area, Plot 28-30, St. 31 P.O.Box: 25593 Safat, 13016 Phone +966-474 1373/4 Fax +966-474 1537 info@kanacontrols.com
<b>AR</b>	<b>Argentina</b> CPI SA Bauness 2660 1431 Buenos Aires Phone +54 11 45238008 Fax +54 11 45220546 info@cpi.com.ar www.cpi.com.ar	<b>CA</b>	<b>Canada</b> W Interconnections CANADA Ltd. 10 Spy Court, Markham, Ontario L3 R5 H6 Phone +1 905 475-1507 Fax +1 905 475-2798 info1@weidmueller.ca www.weidmueller.ca	<b>EE</b>	<b>Estonia</b> Representative Office Weidmüller Interface GmbH & Co. KG Udens str. 12-118 Riga, LV-1007 Latvia Phone +371 29254766 Fax +371 67624562 ilgonis.rudaks@ weidmueller.com	<b>ID</b>	<b>Indonesia</b> PT. Nego Electrindo Ruko Mega Grosir Cempaka Mas, Blok I No 20 – 22 Jl. Let.Jend. Supratno Jakarta 10640 Phone +62 21 42882255 Fax +62 21 42882266 sales@negolectrindo.co.id	<b>LB</b>	<b>Lebanon</b> Progress Engineering & Trading Enterprises Al Nahr Street, Beirut Phone +961 1 444664 Fax +961 1 561880 progress@inco.com.lb
<b>AT</b>	<b>Austria</b> Weidmüller GmbH Austria Straße 2, Industriezentrum Nö Süd Straße 2b M59 2351 Wiener Neudorf Phone +43 2236 6708-0 Fax +43 2236 6708-199 office.at@weidmueller.com	<b>CH</b>	<b>Switzerland</b> Weidmüller Schweiz AG Rundbuckstraße 2 8212 Neuhausen am Rheinfall Phone +41 52 6740707 Fax +41 52 6740708 info@weidmueller.ch www.weidmueller.ch	<b>CL</b>	<b>Chile</b> Felipe Bahamondes S.A./ ATS AGRO Maria Luisa Santander 0475 Casilla 3425 Santiago Phone +56 2 341-1271 Fax +56 2 341-1275 felipe@atsintech.com	<b>ES</b>	<b>Egypt</b> Standard Electric (OMEGA) 87, Mohamed Farid Street Heliopolis, Cairo Phone +20 26422977 Fax +20 26422955 stdelec@rite.com	<b>IE</b>	<b>Ireland</b> Please contact Weidmüller Ltd. in Great Britain
<b>AU</b>	<b>Australia</b> Weidmüller Pty. Ltd. P.O.Box 6944 Huntingwood Drive 43 Huntingwood, NSW 2148 Phone +61 2 9671-9999 Fax +61 2 9671-9911 info@weidmueller.com.au www.weidmueller.com.au	<b>CH</b>	<b>China</b> Weidmüller Interface International Trading (Shanghai) Co., Ltd. 25F, BM Intercontinental Business Center, 100 Yutong Road, Shanghai 200070 P.R. China Phone +86 21 22195008 Fax +86 21 22195009 www.cnweidmueller.com	<b>EG</b>	<b>Egypt</b> Weidmüller S. A. Narcis Monturiol 11-13 Pol. Ind. Sudeste 08960 Sant Just Desvern Barcelona Phone +34 93 4903386 Fax +34 93 3718055 weidmueller@weidmueller.es www.weidmueller.es	<b>ES</b>	<b>Spain</b> Weidmüller S. A. Narcis Monturiol 11-13 Pol. Ind. Sudeste 08960 Sant Just Desvern Barcelona Phone +34 93 4903386 Fax +34 93 3718055 weidmueller@weidmueller.es www.weidmueller.es	<b>IN</b>	<b>India</b> Weidmüller Electronics India Pvt. Ltd Plot # 32, 3rd Floor, North Court Lane North Avenue, Opp. Jogger's Park Kalyani Nagar, Maharastra 411006 Pune Phone +91 9049800960 Nitish.Rajan@weidmueller.de
<b>AZ</b>	<b>Azerbaijan</b> West Industries Ltd. Caspian Plaza, 5th Floor 44 J. Jabbarly Str., Baku Phone +99412 596 15 15 Fax +99412 596 14 93 sales@westi.com	<b>CN</b>	<b>China</b> Weidmüller Interface International Trading (Shanghai) Co., Ltd. 25F, BM Intercontinental Business Center, 100 Yutong Road, Shanghai 200070 P.R. China Phone +86 21 22195008 Fax +86 21 22195009 www.cnweidmueller.com	<b>FI</b>	<b>Finland</b> JUHA-ELEKTRO OY P. O. Box 57, 641 Helsinki Kylönpolku 6, 680 Helsinki Phone +358 10 8328 100 Fax +358 10 8328 109 info@juha-elektro.fi www.juha-elektro.fi	<b>FR</b>	<b>France</b> Weidmüller E. U. R. L. 12, Chausée Jules César B.P. 263 Oamy 95523 Cergy Pontoise Cedex Phone +33 1 34245500 Fax +33 1 34245501 mail@weidmueller.fr	<b>GB</b>	<b>Great Britain</b> Weidmüller Ltd Klippon House Centurion Court Office Meridian East, Meridian Business Park Leicester, LE19 1TP Phone +44 1162 823470 Fax +44 1162 893582 marketing@weidmueller.co.uk www.weidmueller.co.uk
<b>BA</b>	<b>Bosnia and Herzegovina</b> Representative Office Weidmüller Interface GmbH & Co. KG Beograd-Stari Grad Danice Marković 2 11050 Beograd Srbija Phone +381 11 288 5274 Fax +381 11 288 5274 zoran.rabrenovic@ weidmueller.com	<b>CO</b>	<b>Colombia</b> Automatización Avanzada S. A. Carrera 97 No.24c, 23 B4 4 Bogotá D. C. Phone +57 1 5478510 Fax +57 1 4223044 comercial@ automatizacionavanzada.com www. automatizacionavanzada.com	<b>CR</b>	<b>Costa Rica</b> ELVATRON S.A. la Urura 400 Norta Banco Costa Rica San José Costa Rica Phone +506 2 961060 Fax +506 2 200609 dirk.haase@elvatron.com www.elvatron.com	<b>GR</b>	<b>Greece</b> Electromara S.A. 1 An. Martali Str. 41335 Larissa Phone +30 20 552533188 Fax +30 24 10 283463189 valvizes@electromara.com.gr	<b>IT</b>	<b>Italy</b> Weidmüller S.R.L. Via Albert Einstein 4 20092 Cinisello Balsamo Milano Phone +39 02 660681 Fax +39 02 6124945 weidmueller@weidmueller.it www.weidmueller.it
<b>BE</b>	<b>Belgium</b> Weidmüller Benelux B.V. Mechelsesteenweg 519 bus 6 en 7 1930 Nossen Phone +32 2 752 4070 Fax +32 2 751 3606 info@weidmueller.be www.weidmueller.be	<b>CZ</b>	<b>Czech Republic</b> Weidmüller s. r. o. Lomnického 5/1705 14000 Praha 4 Phone +420 2 44001400 Fax +420 2 001499 office@weidmueller.cz www.weidmueller.cz	<b>DE</b>	<b>Germany</b> Weidmüller GmbH & Co. KG Postfach 3054 32720 Detmold Omhstraße 9 32758 Detmold Phone +49 5231 1428-0 Fax +49 5231 1428-116 weidmueller@weidmueller.de www.weidmueller.de	<b>DK</b>	<b>Denmark</b> Wexoe A/S Lejrevej 31 3500 Værløse Phone +45 45465800 Fax +45 45465801 wexoe@wexoe.dk www.wexoe.dk	<b>DK</b>	<b>Danmark</b> HORIZONS P.O.Box: 330607 Amman Jordan 11133 Phone +962 6 4882114 Fax +962 6 4882115 horizons@go.com.jo
<b>BG</b>	<b>Bulgaria</b> Weid-Bul EOOD 1756 Sofia 13, bul. "Kiment Ohridski" Phone +359 2 9632560 Fax +359 2 9631098 sofia@weidbul.com www.weidbul.com	<b>DE</b>	<b>Germany</b> Weidmüller GmbH & Co. KG Postfach 3054 32720 Detmold Omhstraße 9 32758 Detmold Phone +49 5231 1428-0 Fax +49 5231 1428-116 weidmueller@weidmueller.de www.weidmueller.de	<b>DK</b>	<b>Denmark</b> GA Contact Solutions 11, Ippokratous Str. 14452 Metamorfosi Attika Phone +30 210 2823233 Fax +30 210 2823233 gasales@gmail.com	<b>DK</b>	<b>Hong Kong</b> Weidmüller (Hong Kong) Limited Unit 1617, The Metropolis Tower, No.10, Metropolis Drive, Hunghom, Kowloon Phone +852 31548082 Fax +852 31548099 info-hk@weidmueller.de Hong Kong	<b>DK</b>	<b>Korea</b> Weidmüller Korea Co. Ltd. 6F Seokyung B/D, 242-54 Nonhyun-dong, Gangnam-gu Seoul, 135-830 Phone +82 2 5160003 Fax +82 2 5160090 info@weidmueller.co.kr
<b>BH</b>	<b>Bahrain</b> Khayber Trading Company P.O. Box 1976 Manama, Phone +973 720747 Fax +973 720331 khayber@batelco.com.bn	<b>DK</b>	<b>Denmark</b> Wexoe A/S Lejrevej 31 3500 Værløse Phone +45 45465800 Fax +45 45465801 wexoe@wexoe.dk www.wexoe.dk	<b>DK</b>	<b>Croatia</b> Elektro Partner d.o.o. Slavonska Avenija 24/6 10000 Zagreb Phone +385 1 6184793 Fax +385 1 6184795 elektropartner@zg.t-com.hr	<b>DK</b>	<b>Korea</b> Weidmüller Korea Co. Ltd. 6F Seokyung B/D, 242-54 Nonhyun-dong, Gangnam-gu Seoul, 135-830 Phone +82 2 5160003 Fax +82 2 5160090 info@weidmueller.co.kr	<b>DK</b>	<b>Macedonia</b> Weidmüller Representative Office GmbH & Co. KG Beograd-Stari Grad Danice Marković 2 11050 Beograd Srbija Phone +381 11 288 5274 Fax +381 11 288 5274 zoran.rabrenovic@ weidmueller.com
<b>BR</b>	<b>Brazil</b> Weidmüller Conexel do Brasil Conexões Elétricas Ltda. Rua Garcia Lorca, 176 03969-900, São Paulo SP Phone +55 11 43669600 Fax +55 11 43621677 vendas@weidmueller.com.br www.weidmueller.com.br	<b>DK</b>	<b>Denmark</b> Wexoe A/S Lejrevej 31 3500 Værløse Phone +45 45465800 Fax +45 45465801 wexoe@wexoe.dk www.wexoe.dk	<b>DK</b>	<b>Croatia</b> Weidmüller Representative Office GmbH & Co. KG Beograd-Stari Grad Danice Marković 2 11050 Beograd Srbija Phone +381 11 288 5274 Fax +381 11 288 5274 zoran.rabrenovic@ weidmueller.com	<b>DK</b>	<b>Korea</b> Weidmüller Korea Co. Ltd. 6F Seokyung B/D, 242-54 Nonhyun-dong, Gangnam-gu Seoul, 135-830 Phone +82 2 5160003 Fax +82 2 5160090 info@weidmueller.co.kr	<b>DK</b>	<b>Moldova</b> BERHORD A&D srl 44, srt. Samoilogețu 37/3 Off 414, b-dul Decebal, 3, Chișinău, MD 2001 Phone +373 22 507137 Fax +373 22 507134 atiuleanu@berhord.com
<b>ME</b>	<b>Montenegro</b> Representative Office Weidmüller Interface GmbH & Co. KG Beograd-Stari Grad Danice Marković 2 11050 Beograd Srbija Phone +381 11 288 5274 Fax +381 11 288 5274 zoran.rabrenovic@ weidmueller.com	<b>DK</b>	<b>Denmark</b> ELEKTRO – SMK doel UL. III Makedonska brigada b.b. 1000 Skopje Phone +389 22 460 295 Fax +389 22 460 298 Elektro-smk@telekabel.net.mk	<b>DK</b>	<b>Montenegro</b> Representative Office Weidmüller Interface GmbH & Co. KG Beograd-Stari Grad Danice Marković 2 11050 Beograd Srbija Phone +381 11 288 5274 Fax +381 11 288 5274 zoran.rabrenovic@ weidmueller.com	<b>DK</b>	<b>Macedonia</b> Representative Office Weidmüller Interface GmbH & Co. KG Beograd-Stari Grad Danice Marković 2 11050 Beograd Srbija Phone +381 11 288 5274 Fax +381 11 288 5274 zoran.rabrenovic@ weidmueller.com	<b>DK</b>	<b>Moldova</b> BERHORD A&D srl 44, srt. Samoilogețu 37/3 Off 414, b-dul Decebal, 3, Chișinău, MD 2001 Phone +373 22 507137 Fax +373 22 507134 atiuleanu@berhord.com
<b>HR</b>	<b>Croatia</b> Weidmüller Representative Office GmbH & Co. KG Beograd-Stari Grad Danice Marković 2 11050 Beograd Srbija Phone +381 11 288 5274 Fax +381 11 288 5274 zoran.rabrenovic@ weidmueller.com	<b>DK</b>	<b>Croatia</b> Weidmüller Representative Office GmbH & Co. KG Beograd-Stari Grad Danice Marković 2 11050 Beograd Srbija Phone +381 11 288 5274 Fax +381 11 288 5274 zoran.rabrenovic@ weidmueller.com	<b>DK</b>	<b>Croatia</b> Weidmüller Representative Office GmbH & Co. KG Beograd-Stari Grad Danice Marković 2 11050 Beograd Srbija Phone +381 11 288 5274 Fax +381 11 288 5274 zoran.rabrenovic@ weidmueller.com	<b>DK</b>	<b>Croatia</b> Weidmüller Representative Office GmbH & Co. KG Beograd-Stari Grad Danice Marković 2 11050 Beograd Srbija Phone +381 11 288 5274 Fax +381 11 288 5274 zoran.rabrenovic@ weidmueller.com	<b>DK</b>	<b>Croatia</b> Weidmüller Representative Office GmbH & Co. KG Beograd-Stari Grad Danice Marković 2 11050 Beograd Srbija Phone +381 11 288 5274 Fax +381 11 288 5274 zoran.rabrenovic@ weidmueller.com

Group companies



Agency abroad



Without own Agency



**MT** **Malta**  
E. S. S., Electrical Supplies & Services Ltd  
104 J. Sciberras Str.  
Hamrun HMR 08  
Phone +356 21 255 777  
Fax +356 21 255 999  
robert@ess.com.mt

**MU** **Mauritius**  
MUEBLO Electrical Ltd  
Office 26, Gateway building,  
St Jean Road, Quatre Bornes  
Phone +230 467 0989  
Fax +230 465 4051  
richard.mubelo@orange.mu

**MX** **Mexico**  
W Interconnections,  
S.A. DE C.V.  
Blvd. Hermanos Serdán  
No. 698  
Col. San Rafael Oriente  
Puebla, C.P. 72029  
Phone +52 222 22686227  
clientes@weidmuller.com.mx

**MY** **Malaysia**  
Connect Plus Technology Sdn Bhd  
No. 43, Jalan PJ5, 11/22,  
Bandar Sunway,  
46150 Petaling Jaya  
Selangor Darul Ehsan  
Phone +60 3 5633 7363  
Fax +60 3-5633 6662  
paul@cptech.com.my  
www.cptech.com.my

**NL** **Netherlands**  
Weidmüller Benelux B.V.  
Franciscusweg 221  
1216 SE Hilversum  
Postbus 1505  
1200 BM Hilversum  
Phone +31 35 6261261  
Fax +31 35 6232044  
info@weidmuller.nl  
www.weidmuller.nl

**NO** **Norway**  
Siv. Ing. J. F. Knudtzen A/S  
Billingstadsletta 97  
P.O. Box 160  
1378 Nesbru  
Phone +47 66 983350  
Fax +47 66 980955  
firmapost@jfknuftzen.no  
www.jfknuftzen.no

**NZ** **New Zealand**  
Cuthbert S. Steward Limited  
27 Te Puni Street  
POB 38496  
Petone, Wellington  
Phone +64 4 5686156  
Fax +64 4 5686056  
info@weidmuller.de

**OM** **Oman**  
DAN INTERNATIONAL LLC.  
P.O. BOX 2901  
111 Seeb  
Phone +968 503 677  
Fax +968 503 755  
yedu@daniintl.com

**PE** **Peru**  
IMPEXINCA S.A.C.  
Calle Ortiz de Zevallos N°105,  
18 Lima, Miraflores,  
Phone +51 1 447 5608  
info@impeixinca.pe

J & W CIA. S.A.  
Calle 6 Mz. D Lt. 23  
Urb. Ind. Grimanesa  
Callao 01  
Phone +51 1 57 22539  
Fax +51 1 57 20152  
lespinosa@jwcia.com  
www.jwcia.com

**PH** **Philippines**  
Enclosure Systems Specialists Inc  
Room 103 Narra Building  
2276 Don Chino Roces  
Avenue  
Makati City 1231  
Phone +63 2 813 8580  
Fax +63 2 813 8596  
sales\_encsys@pldtdsl.net

**PK** **Pakistan**  
Kana Controls (Pak)  
Apartment No. 33 C III  
Chenab Block,  
Allama Iqbal Town  
Lahore, Pakistan  
Phone +92 42 5419948  
+92 42 7845160  
Fax +92 42 5422895  
nadeem@kanapak.com  
www.kanapak.com

**PL** **Poland**  
Weidmüller Sp. z o.o.  
Ul. Gołodzinowska 10  
03-302 Warszawa  
Phone +48 22 5100940  
Fax +48 22 5100941  
biuro@weidmuller.com.pl  
www.weidmuller.pl

**PT** **Portugal**  
Weidmüller Sistemas de Interface S. A.  
Estrada Outeiro Polima,  
R. Augusto  
Dias da Silva, Lote B, Escr. 2  
2785-515 Abóboda -São Domingos de Rana  
Phone +351 21 4459191  
Fax +351 21 4455871  
www.weidmuller.pt

**QA** **Qatar**  
Doha Motors Trading Co.  
(Technical Division)  
Post Box No. 145  
Airport Road  
Doha - Qatar  
Phone +974 465 1441  
Fax +974 465 0925  
dmctech@qatar.net.qa

**RO** **Romania**  
Rominterface Impex SRL  
Str. Gh. Dem Teodorescu 30 A  
30916 Bucuresti - sector 3  
Phone +40 21 3220230  
Fax +40 21 3228857  
office@rominterface.ro

**RS** **Serbia**  
Representative Office  
Weidmüller Interface  
GmbH & Co. KG  
Ustaniceki 189, III sprat,  
lokaj 7a  
11050 Beograd  
Phone +381 11 288 5274  
Fax +381 11 288 5274  
zoran.rabrenovic@weidmuller.com  
ES-YU Elektrosistem  
Pariske komune 4/1  
11070 Novi Beograd, Serbia  
Phone +381 11 3018660  
Fax +381 11 2693608  
esyu@eunet.rs

**RU** **Russia**  
OOO Weidmüller  
Marshavskoye highway, 25A,  
bld. 6  
117105 Moskau  
Phone +7 495 771-6940  
Fax +7 495 771-6941  
info@weidmuller.ru  
www.weidmuller.ru

**SA** **Saudi-Arabia**  
Al Abdulkarim Holding Co.  
P.O. Box 4  
Dammam 31411  
Phone +96683373424  
Fax +9668338242  
salehs@akh.com.sa  
www.weidmuller.ae

**SA** **Saudi Arabia**  
Saudi Electric Supply Co.  
P.O. Box 3298  
Al Khobar 31952  
Phone +966 3 882 9546227  
Fax +966 3 882 9547  
Safdar.malik@sesco.ge.com

**SE** **Sweden**  
Weidmüller AB  
Axel Daniellsens väg 271  
P.O. box 31025  
200 49 Malmö  
Phone +46 (0) 7 71 43 00 44  
Fax +46 (0) 40 37 48 60  
info@weidmuller.se  
www.weidmuller.se

**SG** **Singapore**  
Weidmüller Pte. Ltd.  
70 Bendemeer Road  
#04-03 Luzerne  
Singapore 339940  
Phone +65 6841 5311  
Fax +65 6841 5377  
info@weidmuller.com.sg  
www.weidmuller.com.sg

**SI** **Slovenia**  
ELEKTROSPOJI d.o.o.  
Stegne 25, 1000 Ljubljana  
Phone +386 15 1113810  
Fax +386 15 111604  
info@elektrospoji.si  
www.elektrospoji.si

**SK** **Slovakia**  
ELEKTRIS s.r.o.  
Elektrárenska 1  
83104 Bratislava  
Phone +421 2 49200113  
Fax +421 2 49200119  
bratislava@elektris.sk

**TH** **Thailand**  
Pisanu Engineering Co., Ltd  
800/43-45 Soi Trakulsuk  
Asoke-dindaeng Road,  
Dindaeng, Bangkok 10400  
Phone +66 2 245 9113  
Fax +66 2 6429220  
jayasankar@pisanu.co.th  
www.pisanu.co.th

**TN** **Tunisia**  
Please contact  
Weidmüller E.U.R.L.  
in France

**TR** **Turkey**  
Weidmüller Elektronik Ticaret Ltd. Sirketi  
Kavacık Mah. Orhan Veli Kanık  
Caddesi 9/1  
34810 Beykoz - İstanbul  
Phone +90 216 5371070 (Pbx)  
Fax +90 216 5371077  
info@weidmuller.com.tr  
www.weidmuller.com.tr

**TW** **Taiwan**  
Fittatek Co., Ltd.  
12F No. 185 Fu-Kuo Road,  
Tso Ying Dist, Kaohsiung  
Phone +886 7 715 6610  
Fax +886 7 556 0858  
stanley@fittatek.com.tw  
www.fittatek.com.tw

Eukan Enterprise Ltd.  
No. 145 He Ping 2nd Rd  
Kaohsiung  
Phone +886 7 715 6610  
Fax +886 7 715 8748  
mark@eukan.com.tw  
www.eukan.com.tw

**UA** **Ukraine**  
TEKO INTERFACE  
Lomonosova str. 73g  
03022 Kiev  
Phone +38 044 3740640  
Fax +38 044 3740642  
weidmuller@tekointerface.com  
www.tekointerface.com.ua

**US** **United States**  
W-Interconnections Inc.  
821 Southlake Boulevard,  
Virginia - Richmond 23236  
Phone +1 804 7942877  
Fax +1 804 3792593  
info@weidmuller.com  
www.weidmuller.com

**UY** **Uruguay**  
REWO Uruguay S.A.  
AV. Bolivia 2001 Esq Roca fuerte  
Carrasco Montevideo 11300  
Phone / Fax +598 260 48439  
clorda@rewouruguay.com.uy

**UZ** **Uzbekistan**  
OOO "Elektro Potential"  
Gani Mavlyanova str., 2B  
100084 Tashkent  
Phone +998 98-3003821  
Fax +998 71-1249286  
mz1958@yandex.ru

We cannot guarantee that there are no mistakes in the publications or software provided by us to the customer for the purpose of making orders. We try our best to quickly correct errors in our printed media.

## X

All orders are based on our general terms of delivery, which can be reviewed on the websites of our group companies where you place your order. On demand we can also send the general terms of delivery to you.



## Weidmüller – Partner in Industrial Connectivity

As experienced experts we support our customers and partners around the world with products, solutions and services in the industrial environment of power, signal and data. We are at home in their industries and markets and know the technological challenges of tomorrow. We are therefore continuously developing innovative, sustainable and useful solutions for their individual needs. Together we set standards in Industrial Connectivity.

Weidmüller Interface GmbH & Co. KG  
Klingenbergsstraße 16  
32758 Detmold, Germany  
T +49 5231 14-0  
F +49 5231 14-292083  
[info@weidmueller.com](mailto:info@weidmueller.com)  
[www.weidmueller.com](http://www.weidmueller.com)



4 050118 168051

Order number: 1366750000/11/2012/SMDM

# X-ON Electronics

Largest Supplier of Electrical and Electronic Components

***Click to view similar products for weidmuller manufacturer:***

Other Similar products are found below :

[8924550000](#) [56956](#) [0133660000](#) [6720000227](#) [6720005111](#) [68676](#) [69718](#) [EXO24CH](#) [7760056106](#) [7940000218](#) [8005181001](#) [8008180000](#)  
[8432240000](#) [8463580000](#) [8545830000](#) [8689870000](#) [8705640000](#) [9001080000](#) [9003720000](#) [9004250000](#) [9004780000](#) [9013260000](#)  
[9014100000](#) [9019040000](#) [9026010000](#) [9028630000](#) [903708](#) [9037350000](#) [9046290000](#) [9129643500](#) [913155](#) [9159530000](#) [919656](#) [919764](#)  
[9202230000](#) [9202850000](#) [9456750000](#) [9457913000](#) [980811](#) [980826](#) [9912800003](#) [9916080000](#) [9916280012](#) [9918380000](#) [9919371205](#)  
[9919371224](#) [9925710000](#) [9926252005](#) [9927480024](#) [1166660000](#)